



1. REMOVE ALL WALLS, FLOORING, CEILING, AND APPURTENANCES WITHIN THE HATCHED DEMOLITION AREA. VA WILL REMOVE FURNITURE.
2. EXISTING FLOORING IS 12" VCT TILE IN MOST AREAS. BATHROOM FLOOR AND WALL ARE TILE. WAITING AREA 2B-108A IS CARPET.
3. DEMOLITION MUST BE PHASED ALONG WITH CONSTRUCTION.
4. PROTECT SMOKE DETECTORS.
5. REMOVE WALL COVERING FROM ALL CORRIDOR WALLS.
6. REMOVE PLUMBING FIXTURES AND ASSOCIATED PIPING AND HANGARS TO NEAREST MAIN LINE IN THE INTERSTITIAL.
7. REMOVE ELECTRICAL DEVICES AND CONDUIT TO NEAREST CABLE TRAY IN INTERSTITIAL. PULL WIRE BACK TO CIRCUIT BREAKER.
8. DEMO HVAC, DUCTWORK, FIRE SPRINKLERS, ELECTRICAL, NURSE CALL, CODE BLUE, AND DATA/TELEPHONE AS NEEDED.

① DISCONNECT AND REMOVE EXISTING MEDICAL AIR, OXYGEN, AND VACUUM FROM HEADWALL ASSEMBLY. REMOVE PIPING AND CAP IN INTERSTITIAL SPACE, INCLUDING ASSOCIATED HANGARS AND HARDWARE. RECERTIFY REMAINING MEDICAL GAS SYSTEM IN THIS BRANCH.

③ REMOVE VCT FLOORING AND VINYL BASE IN REMAINDER OF ROOM.

④ CERAMIC FLOOR AND WALL TILE TO REMAIN.

[illegible]