DOOR SCHEDULE - SECOND FLOOR		Size			Door				Frame				Details					
Door No.	Room Name	Width	Height	Thickness	Type	Material	Glass	Finish	Type	Material	Width	Finish	Sill	Jamb	Head	Hardware	Fire Rating	Comments
A207	A207 Equipment Storage	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	5B	45 min.	
A208	A208 Bathing Suite	DBL 4'/1'	7'-0"	1-3/4"	D3	Wood	N	STN	F5	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	4M		
A209	A209 Staff Lounge	3'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	1		
A209B	A209B Staff Toilet	3'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	2		
A210A	A210A Semi-Private Office	3'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	3E		
A213	A213 Workstations	3'-0"	7'-0"	1-3/4"	D1	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	3E		
C201	C201 Soiled Utility	3'-6"	7'-0"	1-3/4"	D1	HM	N	PNTD	F3	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	SH-3C	45 min.	
C202	C202 Clean Supply	3'-0"	7'-0"	1-3/4"	D1	HM	N	PNTD	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	SH-3C	45 min.	
C203	C203 Living Room	4'-0"	7'-0"	1-3/4"	D5	Wood	Y	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R7		
C203A	C203 Living Room	PR 3'-0"	7'-0"	1-3/4"	D6	Wood	Y	STN	F8	HM	4-7/8"	PNTD	---	E3/A601	E1/A601	See Note 2 Below		
C204	C204 Public Toilet	3'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R3A		
C205	C205 Dining Room	PR 4'-0"	7'-0"	1-3/4"	D8	Wood	N	STN	D8	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	SH-3D	45 min.	
C205B	C205B Pantry	3'-0"	7'-0"	1-3/4"	D1	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R2		
C206	C206 Living Room	PR 3'-0"	7'-0"	1-3/4"	D11	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	SH-3D	45 min.	
C208	C208 Bariatric Room	DBL 4'/1'	7'-0"	1-3/4"	D3	Wood	N	STN	F8	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R7A		
C208A	C208A Bariatric Toilet	4'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F2	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C209	C209 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C209A	C209A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C210	C210 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C210A	C210A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C211	C211 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C211A	C211A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C212	C212 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C212A	C212A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C213	C213 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C213A	C213A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C214	C214 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C214A	C214A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C215	C215 Bariatric Room	DBL 4'/1'	7'-0"	1-3/4"	D3	Wood	N	STN	F8	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R7A		
C215A	C215A Bariatric Toilet	4'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C217	C217 Secondary Carts Storage	4'-0"	7'-0"	1-3/4"	D9	HM	N	PNTD	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	SH-3C	45 min.	
C218	C218 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C218A	C218A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C219	C219 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C219A	C219A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C220	C220 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C220A	C220A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C221	C221 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C221A	C221A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C222	C222 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C222A	C222A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C223	C223 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C223A	C223A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C224	C224 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C224A	C224A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C225	C225 Resident Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R1		
C225A	C225A Resident Toilet	3'-6"	8'-5"	1-3/4"	D7	Wood	N	STN	F7	HM	4-7/8"	PNTD	---	C3/A601	C1/A601	See Note 1 Below		
C226	C226 HAC/Soiled Trash	3'-0"	7'-0"	1-3/4"	D9	HM	N	PNTD	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	5D		
C227	C227 Storage	3'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	5D		
C227A	C227A Clean Oxygen	2'-0"	7'-0"	1-3/4"	D1	Wood	N	STN	F6	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	5F	45 min.	
C227B	C227B Dirty Oxygen	2'-0"	7'-0"	1-3/4"	D1	Wood	N	STN	F6	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	5F	45 min.	
C228A	C228A Medication Room	3'-0"	7'-0"	1-3/4"	D1	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	SH-3C		
C229	C229 Team Conference	3'-0"	7'-0"	1-3/4"	D1	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	4J		
C230	C230 Clean Linen	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	SH-3C		
C231	C231 Staff Toilet	3'-0"	7'-0"	1-3/4"	D1	Wood	N	STN	F1	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	2		
C232	C232 Laundry Room	4'-0"	7'-0"	1-3/4"	D9	Wood	N	STN	F4	HM	4-7/8"	PNTD	---	A3/A601	A1/A601	R2B		
2-200	C2-200 Corridor	PR 3'-0"	7'-0"	1-3/4"	D2	HM	Y	PNTD	F8	HM	4-7/8"	PNTD	---	F3/A601	F1/A601	SH-3D	45 min.	
2-204	C2-200 Corridor	PR 3'-0"	7'-0"	1-3/4"	D2	HM	Y	PNTD	F8	HM	4-7/8"	PNTD	---	F3/A601	F1/A601	SH-3D	45 min.	

Note 1: All Resident Toilet Rooms are to have a sliding door system
Provide hardware consistent with Door depicted in Elevations on A408
as depicted in "Head at Resident Bathroom" Detail C1/A601, and appropriate for door type D7 on A601.
Resident toilet rooms are not to receive a lock.
Overhead track is to have integrated door stops at both ends.
Door frame is to be coordinated with patient lift, the track system is to be capable of single sided suspension in order to traverse the gap in the rail to allow for patient lift.

Note 2: Door C203A is not reflected in the floor plan. It is to be located in living room C203 were the 6'-0" opening is located to cooridor C2-200, as shown in Elevation 5/607.
Hardware is to be a sliding door system.

Revisions	Date
-	-
-	-
-	-
-	-
-	-
-	-
1 - CLARIFICATION AND CORRECTIONS TO DOOR JAMB, HEAD AND HARDWARE. - DOOR 'C203A' ADDED TO SCHEDULE	11/23/2016

CONSULTANTS:

Altus Architectural Studios, Inc.
12925 W. Dodge Road
Omaha, Nebraska 68154

Avantti Environmental Group
309 North Water Street
Suite 650
Milwaukee, WI 53202

Specialized Engineering Solutions, Inc.
10360 Ellison Circle
Omaha, Nebraska 68134

American Structurepoint, Inc.
7260 Shadeland Station
Indianapolis, IN 46256

Middleton Construction Consulting
330 East Kilbourn Ave
Suite 565
Milwaukee, WI 53202

ARCHITECT/ENGINEERS:

13100 watertown plank road
suite 200
elm grove, wi 53122

nagel architects

Nagel Architects Project Number: 140701

100% Bid Documents

Drawing Title: DOOR SCHEDULE SECOND FLOOR -

Approved: Project Director: - - -

Project Title: RENOVATE 3 WARDS OF CLC IN BLDG 134

Location: Captain James A. Lovell FHCC, North Chicago, IL

Date: June 1, 2016 | Checked: SAM | Drawn: EAG

Project Number: 556-14-011

Building Number: BLDG 134, WARDS 2C, 3A, 3B, 3C

Drawing Number: A602

Dwg 0.49 of 146

Office of Construction and Facilities Management

Department of Veterans Affairs

VA FORM 08-6231