

**Endo Clean Room Corrections Building 21**

**VA246-12-B-1153**

**Questions, Answers, and Clarifications**

**(Answers are in BOLD)**

1. WILL THE GFI RECPS. NEED TO HAVE WEATHER PROOF COVERS, OR STAINLESS COVERS.

**Install just the Stainless Steel Cover Plates.**

2. DO THE LIGHT FIXTURS HAVE TO BE WATER PROOF OR CAN THEY BE APPROVED FOR DAMP LOCATION.

**Lights to be for damp locations with a gasket.**

**Clarification of the pass through and Sinks**

1. On sheet 1 of 3, **delete** all work and material associated with **item # 8, Remove Medical Headwalls and store for reuse in another project**. Head wall will be removed prior to start of construction.
2. On sheet 1 of 3, **item # 13**, Disregard the note. The wall is a smoke barrier and does not require a fire rated unit Pass Through Window. It requires a Pass Through Chamber. It has to meet all requirements for NFPA for the installation within a smoke wall. I have included a drawing of a Pass Through Chamber that is required for that wall. It will have to have a mechanical locking system for the doors. Size of unit will be large enough to hold two(2) 13" W x22"L X 8"D scope boxes stacked on top.
3. On sheet 1 of 3, **item # 17**, Size of Pass Through window to be at least 24"x 24" Opening. I have included a drawing of a Pass Through Window.
4. On sheet 1 of 3, **delete** all work and material associated with **item # 20, Remove Frame and door and reverse swing of door**. Existing door to remain as is.
5. The sink is to have two (2) 22" LX16" W X7 ½" -8" D sinks with two (2) H & C water faucets, one H & C water sprayer, Push Button Height control for raising and lowering

the sink, Lever handles drains. Sinks are to be centered in unit with drain boards sloping back to sink from each end.