

Project No. 664-12-310 Convert-2 West Substance Abuse ADTP to SAR RTP

SPECIFICATIONS

CCTV

This is a stand alone system with fixed cameras

1- Chatsworth 24"x24' cube lockable enclosure for DVR, power supplies and UPS in Nurses office on south wall.

1-Pelco DX8116 DVR with approximately one month of recording on hard drive.

1-American Power 1000va UPS for all equipment in enclosure.

1-pelco plmc 19" LCD monitor in nurse's office for viewing of cameras.

10-Honeywell HD51 color 550 lines of hi resolution vandal proof mini dome cameras to cover all corridors exists from interior and room 2040A (dining room).

1-existing camera in front of nurses station to be wired into new DVR.

2-8 channel fused CCTV power supplies

1-coax feed from Nurses station on second floor to VAPD viewing station on first floor. Run cable only no tie in. Drawing 1-1-SC.

Note: All cable to be ran neatly free air in interstitial space. During regular hour with control cube and follow all Asbestos guide lines provide in the VA general requirement. Coordination with staff and patients schedule will be required.

CORRIDOR DOORS

New wall for doors will be framed from floor to ceiling with seismic bracing above ceiling.

Week-end and after hours (2nd shift) work be recommended do to liter traffic.

Cut and modify hand rail to accommodate new wall.

PAINT

Corridor Walls

Brand- Frazee envircote brand, **Finish-** Egg shell; **Color** – Hound CL2682M to be used on corridor walls to match existing.

Brand- Frazee envircote brand; **Finish-** Egg shell; **Color** -Log Wood CL2685A to be used in the corridor. The corridor areas require a two-tone paint color scheme.

Nurses Station Walls

Brand- Frazee envircote brand; **Finish-** Egg shell; **Color** –Secrete 5720W to be used on the walls of the nurses station.

Doors

Doors are to be painted as follows:

Brand – Frazee envircote; **Finish** – Semi-gloss; **Color** – Wharf 5253M to be used on doors and frames.

ELECTRICAL

Pull power from nearest available J-Box to be determined on site.

WINDOW

Manufacturer -CR Laurence; **Catalog Number:** SW3400DU; **Finish:** DURANODIC BRONZE;

Window Function – OXXO (Panel 1 -Fixed, Panel 2 – Operating in the center, Panel 3 – Operating in the center, Panel 4 – Fixed.)

FLOOR BASE

Bruke Flooring products: Molded rubber wall base 4” cove base Product Number CLAY 4CV-527P to be used for flooring patchwork around the door frames.