



GENERAL NOTES

A REFER TO SHEET H1 FOR INDEX, LEGEND, AND ADDITIONAL GENERAL NOTES.

NOTES

- 1 REMOVE EXISTING PROPELLER FAN, AND ASSOCIATED CONTROLS, ETC.
- 2 REMOVE EXISTING DUCTWORK AND ASSOCIATED SUPPORTS, DAMPERS, ETC.
- 3 REMOVE EXISTING AIR DEVICE AND ASSOCIATED DUCTWORK, SUPPORTS, DAMPERS, ETC.
- 4 REMOVE EXISTING AIR HANDLING UNIT AND ASSOCIATED DUCTWORK, PIPING, CONTROLS, ETC.
- 5 REMOVE EXISTING STEAM RADIATOR AND ASSOCIATED RUNOUT PIPING, VALVES, TRAPS, CONTROLS, ETC. RADIATOR TO BE RELOCATED IN NEW WORK.
- 6 REMOVE EXISTING RADIATOR COVER AND SAND BLAST FOR RE-INSTALLATION IN NEW WORK.
- 7 REMOVE EXISTING SMOKE DAMPER AND ASSOCIATED CONTROLS, ETC.
- 8 REMOVE EXISTING NON-ELECTRIC CONTROL VALVE AND STEAM TRAP FOR REPLACEMENT IN NEW WORK.
- 9 EXISTING AIR DEVICE TO REMAIN.
- 10 REMOVE DUCTWORK BACK TO THIS POINT AND CAP.
- 11 EXISTING DUCTWORK TO REMAIN.
- 12 CLEAN RADIATOR AND RADIATOR WELL TO SATISFACTION OF COTR.
- 13 EXISTING TRANSIT PANE BEHIND RADIATOR TO BE LEFT IN PLACE AND UNDISTURBED. CONTACT FOR COTR FOR THE ASBESTOS REPORT WHICH INDICATES THE TYPES AND LOCATIONS OF ALL IDENTIFIED ASB ON THE PROJECT WORK AREA.
- 14 REMOVE DUCTWORK BACK TO UNDERSIDE OF FLOOR AND CAP.

 FIRST FLOOR PLAN - REMOVALS
Scale: 1/8" = 1'-0"

[illegible]