



MAXIMUM PIPE/TUBING SUPPORT SPACING													
NOM. SIZE	IN. (MM)	THRU (20)	3/4 (20)	1 (25)	1 1/4 (32)	1 1/2 (40)	2 (50)	2 1/2 (65)	3 (75)	4 (100)	5 (125)	6 (150)	8 (200)
PIPE	(F)	(2.1)	(2.1)	(2.1)	(2.7)	(3.0)	(3.4)	(3.7)	(4.1)	(4.9)	(5.2)	(5.8)	(6.6)
TUBING	(M)	5 FT (1.5)	6 FT (1.8)	7 FT (2.1)	8 FT (2.4)	9 FT (2.7)	10 FT (3.0)	12 FT (3.7)	14 FT (4.0)	16 FT (4.1)	18 FT (4.9)	20 FT (5.2)	24 FT (6.6)

NOTE: FOR 5 FEET HANGER TIE SPACING OF SMALLEST SIZE ON TRAPEZE.