

NOTES

1. REMOVE ALL EXISTING PARTITIONS SHOWN WITH DASHED LINE. REPAIR WALL AND FLOOR FINISHES AND PREPARE SURFACES FOR NEW SCHEDULED FINISHES AS REQUIRED.
2. COMPUTER AND COMMUNICATION CABLES AND/OR OTHER WIRING, PIPING, TUBING, ETC. SERVING OTHER AREAS AND FUNCTIONS LOCATED ABOVE CEILING OR IN WALLS OF AREA OF SCOPE SHALL BE MAINTAINED DURING DEMOLITION/CONSTRUCTION PROCESS. COORDINATE ANY REQUIRED CHANGES TO THESE SYSTEMS WITH THE VA.
3. PREP ALL DOORS TO BE REFINISHED, PROTECT HARDWARE.
4. PREP ALL DOOR FRAMES FOR REPAINTING.
5. PREPARE WALLS AND FLOOR SLABS AS REQUIRED TO RECEIVE NEW FINISH MATERIALS WHERE EXISTING FINISH IS INDICATED TO BE REMOVED.
5. REMOVE EXISTING CORNER GUARDS, HANDRAILS, CRASH RAILS AND SHEET WALL PROTECTION IN AREAS OF SCOPE.
6. REMOVE ALL EXISTING WALLCOVERING AND WALL COVERING BORDERS. PREPARE ALL WALLS IN SCOPE AS REQUIRED TO RECEIVE NEW PAINTED FINISH.
7. REMOVE ALL EXISTING WALL BASE IN AREAS OF DEMOLITION.
8. RETAIN ALL TOILET ACCESSORIES FOR REINSTALLATION.
9. COORDINATE WITH OTHER TRADES.
10. PERFORM DAILY CLEAN UP.
11. INSTALL ALL MATERIALS PER MANUFACTURER'S SPECIFICATIONS.
12. REMOVE ALL EXISTING CEILING TILES WITH IN THE SCOPE OF WORK.

KEYED NOTES

- 1 DEMO AS NECESSARY TO PREP.
- 2 PREP WARDROBE TO RECEIVE NEW FINISH.
- 3 REMOVE WALL TO DECK.
- 4 REMOVE EXISTING CASEWORK.
- 5 REMOVE EXISTING TOILET AND SINK. REMOVE ALL EXISTING PIPING BACK TO SHUT OFF VALVE. CAP AND REMOVE WASTE AND VENT BACK TO MAIN.
- 6 REMOVE EXISTING DOOR AND FRAME.
- 7 CUBICLE CURTAIN TRACK TO REMAIN, CLEAN AND REPAIR AS NECESSARY.
- 8 REMOVE EXISTING HEADWALL FINISH, PREP TO RECEIVE NEW FINISH. REFER TO NEW WORK PLAN.
- 9 PREP BOTH SIDES (CORRIDOR & PATIENT ROOM) OF EXISTING LOCKERS TO RECEIVE NEW FINISH (INTERIOR & EXTERIOR).

LEGEND

- DETAIL INDICATOR
- ELEVATION INDICATOR
- BUILDING SECTION INDICATOR
- KEYNOTE
- DEMOLISHED ELEMENT
- SCOPE LIMIT LINE
- EXISTING ELEMENT TO REMAIN
- EXISTING FIREWALL MAINTAIN RATING

DEMOLITION PLAN
1/8" = 1'-0"

KEYPLAN - NOT TO SCALE

FULLY SPRINKLERED BUILDING
FINAL CONSTRUCTION DOCUMENTS

ARCHITECT/ENGINEERS:		Project Title A/E DESIGN RENOVATE 6B		Project Number 594-12-605		Office of Construction and Facilities Management	
PARADIGM ENGINEERS AND CONSTRUCTORS 9 Oak Drive - Oak, FL 34472 - PH: 502.339.8511 - www.paradigmconstruct.com		Drawing Title DEMOLITION PLAN		Building Number 1		Drawing Number 1AD101	
APPROVED PROJECT DIRECTOR		Location WEST PALM BEACH VAMC 725 NORTH MILITARY PALM BEACH GARDENS 33406-5400		Checked BKG		Drawn JDM	
DATE 09-11-2018		APPROVED PROJECT DIRECTOR		DATE 09-11-2018		DATE 09-11-2018	