

F1 FLOOR FINISH PLAN-6B
1/8" = 1'-0"

NOTES

1. ALL FLOORS TO RECEIVE SELF LEVELING COMPOUND.
2. INSTALL TRANSITIONS AT THRESHOLDS OF ALL FLOOR MATERIAL CHANGES. SEE DETAIL F8-1.AE501 FOR LUXURY VINYL TILE TRANSITION
3. REFER TO 1.AI601 FOR FINISH INFORMATION.

KEYED NOTES

1. INSTALL VA SEAL IN FLOOR. SEE DETAIL C8 ON THIS SHEET

C8 VA SEAL DETAIL

LEGEND

- INSTALL LVT-1 IN THIS AREA
- INSTALL LVT-2 IN THIS AREA.
- INSTALL EPOXY WITH URETHANE TOPCOAT IN THIS AREA, BASE SHALL BE COVED. SEE DETAIL
- INSTALL CPT-1 IN THIS AREA
- INSTALL LVT-3 IN THIS AREA



KEYPLAN - NOT TO SCALE

FULLY SPRINKLERED BUILDING
FINAL CONSTRUCTION DOCUMENTS

Revisions:	Date

ARCHITECT/ENGINEERS:

PARADIGM
ENGINEERS AND CONSTRUCTORS
9 Oak Drive - Ocala, FL 34472 - PH: 502.339.8511 - www.paradigmusa.com

11 March 2013
BLAINE VAN GANSBEKE
LICENSE
No 73599
STATE OF FLORIDA
PROFESSIONAL ENGINEER

Drawing Title: FLOOR FINISH PLAN	Project Title: A/E DESIGN RENOVATE 6B	Project Number: 594-12-605	Office of Construction and Facilities Management
Approved: Project Director	Location: WEST PALM BEACH VAMC, 7305 NORTH MILITARY TRAIL, PALM BEACH GARDENS 33410-6400	Building Number: 1	
	Date: 03-11-2013 / Checked: BVG / Drawn: DML	Drawing Number: 1.AI101	Department of Veterans Affairs

VA FORM 08-6231