

TABLE OF CONTENTS – SUPPLEMENTAL LEASE REQUIREMENTS

SECTION 1	GENERAL TERMS, CONDITIONS, AND STANDARDS	3
1.01	DEFINITIONS AND GENERAL TERMS (SMALL) (SEP 2015)	3
1.02	PUBLIC TRANSPORTATION (SMALL) (SEP 2015)	3
1.03	AUTHORIZED REPRESENTATIVES (JUN 2012)	3
1.04	HUBZONE SMALL BUSINESS CONCERNS ADDITIONAL PERFORMANCE REQUIREMENTS (SIMPLIFIED) (MAR 2012)	3
1.05	WAIVER OF RESTORATION (APR 2011)	3
1.06	NOVATION AND CHANGE OF OWNERSHIP (SMALL) (SEP 2015)	3
1.07	ASBESTOS (SMALL) (SEP 2015)	3
1.08	RENTAL CONSIDERATION (SMALL) (SEP 2015)	4
SECTION 2	CONSTRUCTION STANDARDS AND SHELL COMPONENTS	5
2.01	WORK PERFORMANCE (SMALL) (SEP 2015)	5
2.02	RECYCLED CONTENT PRODUCTS (COMPREHENSIVE PROCUREMENT GUIDELINES) (SMALL) (SEP 2015)	5
2.03	ENVIRONMENTALLY PREFERABLE BUILDING PRODUCTS AND MATERIALS (SMALL) (SEP 2015)	5
2.04	EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (SMALL) (SEP 2015)	5
2.05	WOOD PRODUCTS (SMALL) (SEP 2015)	5
2.06	ADHESIVES AND SEALANTS (AUG 2008)	5
2.07	BUILDING SHELL REQUIREMENTS (SMALL) (SEP 2015)	5
2.08	RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (SMALL) (SEP 2015)	5
2.09	MEANS OF EGRESS (MAY 2015)	5
2.10	AUTOMATIC FIRE SPRINKLER SYSTEM (SEP 2013)	6
2.11	FIRE ALARM SYSTEM (SEP 2013)	6
2.12	ENERGY INDEPENDENCE AND SECURITY ACT (SMALL) (MAR 2016)	6
2.13	ELEVATORS (SMALL) (SEP 2015)	7
2.14	DEMOLITION (JUN 2012)	7
2.15	ACCESSIBILITY (FEB 2007)	7
2.16	INTENTIONALLY DELETED	7
2.17	INTENTIONALLY DELETED	7
2.18	INTENTIONALLY DELETED	7
2.19	INTENTIONALLY DELETED	7
2.20	INSULATION: THERMAL, ACOUSTIC, AND HVAC (SMALL) (SEP 2015)	7
2.21	PAINTING – SHELL (SMALL) (SEP 2015)	8
2.22	INTENTIONALLY DELETED	8
2.23	MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (SMALL) (SEP 2015)	8
2.24	INTENTIONALLY DELETED	8
2.25	INTENTIONALLY DELETED	8
2.26	PLUMBING FIXTURES: WATER CONSERVATION (SMALL) (SEP 2015)	8
2.27	INTENTIONALLY DELETED	8
2.28	INTENTIONALLY DELETED	8
2.29	INTENTIONALLY DELETED	8
2.30	LIGHTING: INTERIOR AND PARKING – SHELL (SMALL) (SEP 2015)	8
2.31	INDOOR AIR QUALITY DURING CONSTRUCTION (SMALL) (SEP 2015)	8
2.32	NATIONAL HISTORIC PRESERVATION ACT REQUIREMENTS - LEASE (SMALL) (SEP 2015)	9
SECTION 3	DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES	10
3.01	SCHEDULE FOR COMPLETION OF SPACE (SIMPLIFIED) (SEP 2013)	10
3.02	ACCESS TO THE GOVERNMENT PRIOR TO ACCEPTANCE (SIMPLIFIED) (SEP 2015)	10
3.03	ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (SIMPLIFIED) (SEP 2015)	10
3.04	LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (SMALL) (SEP 2015)	10
3.05	AS-BUILT DRAWINGS (SMALL) (SEP 2015)	10
3.06	SEISMIC RETROFIT (SEP 2013)	10
SECTION 4	TENANT IMPROVEMENT COMPONENTS	11
4.01	TENANT IMPROVEMENTS AND PRICING (SMALL) (SEP 2015)	11
4.02	INTENTIONALLY DELETED	11
4.03	INTENTIONALLY DELETED	11
4.04	INTENTIONALLY DELETED	11
4.05	DOORS: INTERIOR (SMALL) (SEP 2015)	11
4.06	DOORS: HARDWARE (SMALL) (SEP 2015)	11
4.07	INTENTIONALLY DELETED	11
4.08	PAINTING – TI (SMALL) (SEP 2015)	11
4.09	FLOOR COVERINGS	11
4.10	INTENTIONALLY DELETED	11
4.11	ELECTRICAL: DISTRIBUTION (SMALL) (SEP 2015)	11
4.12	INTENTIONALLY DELETED	11
4.13	INTENTIONALLY DELETED	11

4.14	INTENTIONALLY DELETED	12
4.15	INTENTIONALLY DELETED	12
4.16	LIGHTING: INTERIOR AND PARKING – TI (SMALL) (SEP 2015).....	12
SECTION 5 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM		13
5.01	PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (SIMPLIFIED) (JUN 2012).....	13
5.02	UTILITIES (APR 2011)	13
5.03	INTENTIONALLY DELETED	13
5.04	INTENTIONALLY DELETED	13
5.05	JANITORIAL SERVICES (SMALL) (SEP 2015).....	13
5.06	SELECTION OF CLEANING PRODUCTS (SMALL) (SEP 2015).....	13
5.07	SELECTION OF PAPER PRODUCTS (APR 2015)	13
5.08	MAINTENANCE OF PROVIDED FINISHES (SMALL) (SEP 2015)	13
5.09	IDENTITY VERIFICATION OF PERSONNEL (SMALL) (SEP 2015).....	13
5.10	RANDOLPH-SHEPPARD COMPLIANCE (SMALL) (SEP 2015).....	14
5.11	INDOOR AIR QUALITY (SEP 2013)	14
5.12	RADON IN AIR (SEP 2013).....	14
5.13	RADON IN WATER (JUN 2012)	14
5.14	HAZARDOUS MATERIALS (SEP 2013).....	15
5.15	MOLD (SIMPLIFIED) (SEP 2013).....	15
5.16	OCCUPANT EMERGENCY PLANS (SMALL) (SEP 2015)	15
SECTION 6 ADDITIONAL TERMS AND CONDITIONS.....		16
6.01	SECURITY STANDARDS.....	16

SECTION 1 GENERAL TERMS, CONDITIONS, AND STANDARDS

1.01 DEFINITIONS AND GENERAL TERMS (SMALL) (SEP 2015)

Unless otherwise specifically noted, all terms and conditions set forth in this Lease shall be interpreted by reference to the following definitions, standards, and formulas:

A. Common Area Factor (CAF). The Common Area Factor (CAF) is a conversion factor determined by the Building owner and applied by the owner to the ABOA SF to determine the RSF for the leased Space. The CAF is expressed as a percentage of the difference between the amount of rentable SF and ABOA SF, divided by the ABOA SF. For example 11,500 RSF and 10,000 ABOA SF will have a CAF of 15% $[(11,500 \text{ RSF} - 10,000 \text{ ABOA SF}) / 10,000 \text{ ABOA SF}]$. For the purposes of this Lease, the CAF shall be determined in accordance with the applicable ANSI/BOMA standard for the type of space to which the CAF shall apply.

B. Rentable Space or Rentable Square Feet (RSF). Rentable Space is the area for which a tenant is charged rent. It is determined by the Building owner and may vary by city or by building within the same city. The Rentable Space may include a share of Building support/common areas such as elevator lobbies, Building corridors, and floor service areas. Floor service areas typically include restrooms, janitor rooms, telephone closets, electrical closets, and mechanical rooms. The Rentable Space does not include vertical building penetrations and their enclosing walls, such as stairs, elevator shafts, and vertical ducts. Rentable Square Feet is calculated using the following formula for each type of Space (e.g., office, warehouse, etc.) included in the Premises: $\text{ABOA SF of Space} \times (1 + \text{CAF}) = \text{RSF}$.

C. Space. The Space shall refer to that part of the Premises to which the Government has exclusive use, such as Office Area, or other type of Space. Parking areas to which the Government has rights under this Lease are not included in the Space.

D. Office Area. For the purposes of this Lease, Space shall be measured in accordance with the standard (Z65.1-1996) provided by American National Standards Institute/Building Owners and Managers Association (ANSI/BOMA) for Office Area, which means "the area where a tenant normally houses personnel and/or furniture, for which a measurement is to be computed." References to ABOA mean ANSI/BOMA Office Area.

1.02 PUBLIC TRANSPORTATION (SMALL) (SEP 2015)

Public transportation (for example commuter rail, light rail, buses, or subway station) shall be located within the immediate vicinity of the Building, but generally not exceeding **A WALKABLE 2,640 FEET**, as determined by the LCO.

1.03 AUTHORIZED REPRESENTATIVES (JUN 2012)

The signatories to this Lease shall have full authority to bind their respective principals with regard to all matters relating to this Lease. No other persons shall be understood to have any authority to bind their respective principals except to the extent that such authority may be explicitly delegated by notice to the other party, or to the extent that such authority is transferred by succession of interest. The Government shall have the right to substitute its Lease Contracting Officer (LCO) by notice without an express delegation by the prior LCO.

1.04 HUBZONE SMALL BUSINESS CONCERNS ADDITIONAL PERFORMANCE REQUIREMENTS (SIMPLIFIED) (MAR 2012)

If the Lessor is a qualified HUBZone small business concern (SBC) that did not waive the price evaluation preference then as required by 13 C.F.R. 126.700, the HUBZone SBC must spend at least 50% of the cost of the contract incurred for personnel on its own employees or employees of other qualified HUBZone SBC's and must meet the performance of the work requirements for subcontracting in 13 C.F.R. § 125.6(c). If the Lessor is a HUBZone joint venture, the aggregate of the qualified HUBZone SBC's to the joint venture, not each concern separately, must perform the applicable percentage of work required by this clause.

If the Lessor is a HUBZone small business concern (SBC) that did not waive the price evaluation preference, the Lessor shall provide a certification within 10 days after Lease award to the LCO (or representative designated by the LCO) that the Lessor was an eligible HUBZone SBC on the date of award. If it is determined within 20 days after award that a HUBZone SBC Offeror that has been awarded the Lease was not an eligible HUBZone SBC at the time of award, and the HUBZone SBC Lessor failed to provide the LCO with information regarding a change to its HUBZone eligibility prior to award, then the Lease shall be subject, at the LCO's discretion, to termination, and the Government will be relieved of all obligations to the Lessor in such an event and not be liable to the Lessor for any costs, claims, or damages of any nature whatsoever.

1.05 WAIVER OF RESTORATION (APR 2011)

The Lessor shall have no right to require the Government to restore the Premises upon termination of the Lease, and waives all claims against the Government for waste, damages, or restoration arising from or related to (a) the Government's normal and customary use of the Premises during the term of the Lease (including any extensions thereof), as well as (b) any initial or subsequent alteration to the Premises regardless of whether such alterations are performed by the Lessor or by the Government. At its sole option, the Government may abandon property in the Space following expiration of the Lease, in which case the property will become the property of the Lessor, and the Government will be relieved of any liability in connection therewith.

1.06 NOVATION AND CHANGE OF OWNERSHIP (SMALL) (SEP 2015)

Consistent with GSAM 570.115, in the event of a transfer of ownership of the leased premises or a change in the lessor's legal name, FAR 42.12 applies.

1.07 ASBESTOS (SMALL) (SEP 2015)

The leased space shall be free of all asbestos containing materials, except undamaged asbestos flooring in the space or undamaged boiler or pipe insulation outside the space, in which case an asbestos management program conforming to Environmental Protection Agency guidance shall be implemented. The space shall be free of other hazardous materials and in compliance with applicable Federal, State, and local environmental laws and regulations. If asbestos abatement work is to be performed in the Space after occupancy, the Lessor shall submit to the Government the occupant safety plan and a description of the methods of abatement and re-occupancy clearance, in accordance with OSHA, EPA, DOT, state, and local regulations and guidance, at least 4 weeks prior to the abatement work.

1.08 RENTAL CONSIDERATION (SMALL) (SEP 2015)

Rent shall not be adjusted for changes in real estate taxes or operating costs.

SECTION 2 CONSTRUCTION STANDARDS AND SHELL COMPONENTS

2.01 WORK PERFORMANCE (SMALL) (SEP 2015)

All work in performance of this Lease shall be done by skilled and licensed workers or mechanics and shall be acceptable to the LCO.

2.02 RECYCLED CONTENT PRODUCTS (COMPREHENSIVE PROCUREMENT GUIDELINES) (SMALL) (SEP 2015)

The Lessor shall comply with U.S. Environmental Protection Agency (EPA) in the Comprehensive Procurement Guidelines (CPG), 40 CFR Part 247, and its accompanying Recovered Materials Advisory Notice (RMAN), and to the extent feasible, the Resource Conservation and Recovery Act (RCRA), Section 6002, 1976. Any waiver or deviation from these requirements must be approved by the LCO.

2.03 ENVIRONMENTALLY PREFERABLE BUILDING PRODUCTS AND MATERIALS (SMALL) (SEP 2015)

The Lessor shall use environmentally preferable products and materials in accordance with EPA's environmentally preferable purchasing Web site, www.epa.gov/epp and USDA Bio-Preferred products Web site www.biopreferred.gov. The Lessor is encouraged to consider the lifecycle analysis of the product in addition to the initial cost.

2.04 EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (SMALL) (SEP 2015)

The Lessor shall reuse items or materials in the construction phase of the project, as long as such meet the quality standards set forth by the Government in this Lease.

2.05 WOOD PRODUCTS (SMALL) (SEP 2015)

For all new installations of wood products, the Lessor is encouraged to use independently certified forest products. Refer to the Forest Certification Resource Center (www.certifiedwood.org), the Forest Stewardship Council United States (www.fscus.org), or the Sustainable Forestry Initiative (www.sfiprogram.org).

Particle board, strawboard, and plywood materials shall comply with Department of Housing and Urban Development (HUD) standards for formaldehyde emission controls. All materials comprised of combustible substances, such as wood plywood and wood boards, shall be treated with fire retardant chemicals by a pressure impregnation process or other methods that treats the materials throughout as opposed to surface treatment.

2.06 ADHESIVES AND SEALANTS (AUG 2008)

All adhesives employed on this project (including, but not limited to, adhesives for carpet, carpet tile, plastic laminate, wall coverings, adhesives for wood, or sealants) shall be those with the lowest possible volatile organic compounds (VOC) content below 20 grams per liter and which meet the requirements of the manufacturer of the products adhered or involved. The Lessor shall use adhesives and sealants with no formaldehyde or heavy metals. Adhesives and other materials used for the installation of carpets shall be limited to those having a flash point of 140 degrees F or higher.

2.07 BUILDING SHELL REQUIREMENTS (SMALL) (SEP 2015)

A. The Building Shell shall be designed, constructed, and maintained in accordance with the standards set forth herein and completed prior to acceptance of Space.

B. Base structure and Building enclosure components shall be complete. All common areas accessible by the Government, such as lobbies, fire egress corridors and stairwells, elevators, garages, and service areas, shall be complete. Restrooms shall be complete and operational. All newly installed Building shell components, including but not limited to, heating, ventilation, and air conditioning (HVAC), electrical, ceilings, sprinklers, etc., shall be furnished, installed, and coordinated with TIs. Circulation corridors are provided as part of the base Building only on multi-tenanted floors where the corridor is common to more than one tenant. On single tenant floors, only the fire egress corridor(s) necessary to meet code is provided as part of the shell.

2.08 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (SMALL) (SEP 2015)

THE LESSOR REMAINS SOLELY RESPONSIBLE FOR DESIGNING, CONSTRUCTING, OPERATING, AND MAINTAINING THE LEASED PREMISES IN FULL ACCORDANCE WITH THE REQUIREMENTS OF THE LEASE. The Lessor shall, without additional compensation, correct or revise any errors or deficiencies in its designs, drawings, specifications, or other services, as noted by the Government's review or otherwise.

2.09 MEANS OF EGRESS (MAY 2015)

A. Prior to occupancy, the Premises and any parking garage areas shall meet or will be upgraded to meet either the applicable egress requirements in the National Fire Protection Association, Life Safety Code (NFPA 101) or the International Code Council, International Building Code (IBC), each current as of the Lease Award Date, or use an alternative approach or method that achieves an equivalent level of safety deemed acceptable by the Government.

B. The Space shall have unrestricted access to a minimum of two remote exits on each floor of Government occupancy.

C. Interlocking or scissor stairs located on the floor(s) where Space is located shall only count as one exit stair.

- D. A fire escape located on the floor(s) where Space is located shall not be counted as an approved exit stair.
- E. Doors shall not be locked in the direction of egress unless equipped with special locking hardware in accordance with requirements of NFPA 101 or the IBC.

2.10 AUTOMATIC FIRE SPRINKLER SYSTEM (SEP 2013)

- A. Any portion of the Space located below-grade, including parking garage areas, and all areas in a Building referred to as "hazardous areas" (defined in National Fire Protection Association (NFPA) 101) that are located within the entire Building (including non-Government areas) shall be protected by an automatic fire sprinkler system or an equivalent level of safety.
- B. For Buildings in which any portion of the Space is on or above the sixth floor, then, at a minimum, the Building up to and including the highest floor of Government occupancy shall be protected by an automatic fire sprinkler system or an equivalent level of safety.
- C. For Buildings in which any portion of the Space is on or above the sixth floor, and lease of the Space will result, either individually or in combination with other Government Leases in the Building, in the Government leasing 35,000 or more ANSI/BOMA Office Area SF of Space in the Building, then the entire Building shall be protected throughout by an automatic fire sprinkler system or an equivalent level of safety.
- D. Automatic fire sprinkler system(s) shall be installed in accordance with the requirements of NFPA 13, Standard for the Installation of Sprinkler Systems that was in effect on the actual date of installation.
- E. Automatic fire sprinkler system(s) shall be maintained in accordance with the requirements of NFPA 25, Standard for the Inspection, Testing, and Maintenance of Water-based Fire Protection Systems (current as of the Lease Award Date).
- F. "Equivalent level of safety" means an alternative design or system (which may include automatic fire sprinkler systems), based upon fire protection engineering analysis, which achieves a level of safety equal to or greater than that provided by automatic fire sprinkler systems.

2.11 FIRE ALARM SYSTEM (SEP 2013)

- A. A Building-wide fire alarm system shall be installed in the entire Building in which any portion of the Space is located on the 3rd floor or higher.
- B. The fire alarm system shall be installed in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code, that was in effect on the actual date of installation.
- C. The fire alarm system shall be maintained in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (current as of the Lease Award Date).
- D. The fire alarm system shall transmit all fire alarm signals to the local fire department via any of the following means: directly to the local fire department, to the (911) public communications center, to a central station, to a remote supervising station, or to a proprietary supervising station.
- E. If the Building's fire alarm control unit is over 25 years old as of the date of award of this Lease, Lessor shall install a new fire alarm system in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code (current as of the Lease Award Date), prior to Government acceptance and occupancy of the Space.

2.12 ENERGY INDEPENDENCE AND SECURITY ACT (SMALL) (MAR 2016)

- A. The Lessor shall either earn the ENERGY STAR® Label or,
- B. (i). Complete all cost effective energy efficiency and conservation improvements, agreed to by Lessor prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding Lease), and
- (ii). Obtain and publicly disclose the Building's current ENERGY STAR® score (using EPA's Portfolio Manager tool), unless the Lessor cannot access whole building utility consumption data, or there is no building category within Portfolio Manager to benchmark against, including spaces—
1. That are located in States with privacy laws that provide that utilities shall not provide such aggregated information to multitenant building owners; and
 2. For which tenants do not provide energy consumption information to the commercial building owner in response to a request from the building owner. (A Federal agency that is a tenant of the space shall provide to the building owner, or authorize the owner to obtain from the utility, the energy consumption information of the space for the benchmarking and disclosure required by this subparagraph D).
 3. That cannot be benchmarked (scored) using EPA's Portfolio Manager tool because of excessive vacancy; in which case Lessor agrees to obtain the score and publicly disclose it within 120 days of the eligibility to obtain a score using the EPA Portfolio Manager tool.

"Public disclosure" means posting the Energy Star® score on state or local websites in those areas that have applicable disclosure mandates, and reporting the score to the Government via Portfolio Manager. In the absence of an applicable state or local disclosure mandate, Lessor shall either generate and display the Energy Star® score in a public space at the building location or post the score on Lessor's or Lessor's Parent/Affiliate website.

C. Hydrology-related Requirements:

1. Per EISA Section 438, the sponsor of any development or redevelopment project involving a Federal facility with a footprint that exceeds 5,000 square feet shall use site planning, design, construction, and maintenance strategies for the property to maintain or restore, to the maximum extent technically feasible, the predevelopment hydrology of the Property with regard to the temperature, rate, volume, and duration of flow. If the Lessor proposes to satisfy the Government's space requirements through a development or redevelopment project, and the Government will be the sole or predominant tenant such that any other use of the Property will be functionally or quantitatively incidental to the Government's use, the Lessor is required to implement hydrology maintenance and restoration requirements as required by EISA Section 438.

a. For the purposes of applying EISA Section 438 in this Lease, "sponsor" shall mean "Lessor", and "exceeds 5,000 square feet" shall mean construction that disturbs 5,000 square feet or more of land area at the Property or on adjoining property to accommodate the Government's requirements, or at the Property for whatever reason. Information regarding implementation of the hydrology maintenance and restoration requirements can be found at: <http://www.epa.gov/greeningepa/technical-guidance-implementing-stormwater-runoff-requirements-federal-projects>

b. Lessor is required to implement these hydrology maintenance and restoration requirements to the maximum extent technically feasible, prior to acceptance of the Space, (or not later than one year after the Lease Award Date or Lease Term Commencement Date, whichever is later, of a succeeding or superseding lease). Additionally, this Lease requires EISA Section 438 storm water compliance not later than one year from the date of any applicable disturbance (as defined in EISA Section 438) of more than 5,000 square feet of ground area if such disturbance occurs during the term of the Lease if the Government is Government is the sole or predominant tenant. In the event the Lessor is required to comply with EISA Section 438, Lessor shall furnish the Government, prior to the filing for permits for the associated work, with a certification from Lessor's engineer that the design meets the hydrology maintenance and restoration requirements of EISA Section 438.

2.13 ELEVATORS (SMALL) (SEP 2015)

A. The Lessor shall provide suitable passenger and, when required by the Government, freight elevator service to any of the Premises not having ground level access. Service shall be available during the normal hours of operation specified in the in this Lease

B. Code: Elevators shall conform to the current requirements of the American Society of Mechanical Engineers ASME A17.1/CSA B44, Safety Code for Elevators and Escalators (current as of the Lease Award Date) Elevators shall be provided with Phase I emergency recall operation and Phase II emergency in-car operation in accordance with ASME A17.1/CSA B44. Fire alarm initiating devices (e.g., smoke detectors) used to initiate Phase I emergency recall operation shall be installed in accordance with the requirements of NFPA 72, National Fire Alarm and Signaling Code. The elevators shall be inspected and maintained in accordance with the current edition of the ASME A17.2, Inspector's Manual for Elevators. Except for the reference to ASME A17.1 in ABAAS, Section F105.2.2, all elevators must meet ABAAS requirements for accessibility in Sections 407, 408, and 409 of ABAAS.

C. Safety Systems: Elevators shall be equipped with telephones or other two-way emergency communication systems. The system used shall be marked and shall reach an emergency communication location staffed 24 hours per day, 7 days per week.

2.14 DEMOLITION (JUN 2012)

The Lessor shall remove existing abandoned electric, telephone, and data cabling and devices, as well as any other improvements or fixtures in place to accommodate the Government's requirements. Any demolition of existing improvements that is necessary to satisfy the Government's layout shall be done at the Lessor's expense.

2.15 ACCESSIBILITY (FEB 2007)

The Building, leased Space, and areas serving the leased Space shall be accessible to persons with disabilities in accordance with the Architectural Barriers Act Accessibility Standard (ABAAS), Appendices C and D to 36 CFR Part 1191 (ABA Chapters 1 and 2, and Chapters 3 through 10). To the extent the standard referenced in the preceding sentence conflicts with local accessibility requirements, the more stringent shall apply.

2.16 INTENTIONALLY DELETED

2.17 INTENTIONALLY DELETED

2.18 INTENTIONALLY DELETED

2.19 INTENTIONALLY DELETED

2.20 INSULATION: THERMAL, ACOUSTIC, AND HVAC (SMALL) (SEP 2015)

A. No insulation installed with this project shall be material manufactured using chlorofluorocarbons (CFCs), nor shall CFCs be used in the installation of the product.

B. All insulation containing fibrous materials exposed to air flow shall be rated for that exposure or shall be encapsulated.

C. Insulating properties for all materials shall meet or exceed applicable industry standards. Polystyrene products shall meet American Society for Testing and Materials (ASTM) C578 91.

D. All insulation shall be low emitting with not greater than .05 ppm formaldehyde emissions.

E. The maximum flame spread and smoke developed index for insulation shall meet the requirements of the applicable local codes and ordinances (current as of the Lease Award Date) adopted by the jurisdiction in which the Building is located.

2.21 PAINTING – SHELL (SMALL) (SEP 2015)

The Lessor shall bear the expense for all painting associated with the Building shell. These areas shall include all common areas. Exterior perimeter walls and interior core walls within the Space shall be spackled and prime painted with low VOC primer. If any Building shell areas are already painted prior to TIs, then the Lessor shall repaint, at the Lessor's expense, as necessary during TIs.

2.22 INTENTIONALLY DELETED

2.23 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (SMALL) (SEP 2015)

A. The Lessor shall be responsible for meeting the applicable requirements of all federal, state, and local codes and ordinances. When codes conflict, the more stringent standard shall apply.

B. The Lessor shall provide and operate all Building equipment and systems in accordance with applicable technical publications, manuals, and standard procedures.

C. Convenience outlets shall be installed in accordance with NFPA Standard 70, National Electrical Code, or local code, whichever is more stringent. The Lessor shall provide duplex utility outlets in restrooms, corridors, and dispensing areas.

2.24 INTENTIONALLY DELETED

2.25 INTENTIONALLY DELETED

2.26 PLUMBING FIXTURES: WATER CONSERVATION (SMALL) (SEP 2015)

For new installations and whenever plumbing fixtures are being replaced), all fixtures must conform to EPA WaterSense.: Information on EPA WaterSense fixtures can be found at <http://www.epa.gov/watersense/>.

2.27 INTENTIONALLY DELETED

2.28 INTENTIONALLY DELETED

2.29 INTENTIONALLY DELETED

2.30 LIGHTING: INTERIOR AND PARKING – SHELL (SMALL) (SEP 2015)

A. INTENTIONALLY DELETED

B. INTENTIONALLY DELETED

C. INTENTIONALLY DELETED.

D. BUILDING PERIMETER: Exterior parking areas, vehicle driveways, pedestrian walks, and the Building perimeter lighting levels shall be designed per Illuminating Engineering Society (IES) standards. Provide 5 foot-candles for doorway areas, 3 foot-candles for transition areas and at least 5 foot-candles throughout the parking lot. Parking lot fixtures shall provide a maximum to minimum uniformity ratio of 10:1.

E. PARKING STRUCTURES: The minimum illuminance level for parking structures is 3 foot-candles as measured on the floor with a uniformity ratio of 10:1.

F. EXTERIOR POWER BACKUP: Exterior egress, walkway, parking lot, and parking structure lighting must have emergency power backup to provide for safe evacuation of the Building.

2.31 INDOOR AIR QUALITY DURING CONSTRUCTION (SMALL) (SEP 2015)

A. All MSDS shall comply with Occupational Safety and Health Administration (OSHA) requirements. The Lessor and its agents shall comply with all recommended measures in the MSDS to protect the health and safety of personnel.

B. Where demolition or construction work occurs adjacent to occupied Space, the Lessor shall erect appropriate barriers (noise, dust, odor, etc.) and take necessary steps to minimize interference with the occupants. This includes maintaining acceptable temperature, humidity, and ventilation in the occupied areas during window removal, window replacement, or similar types of work.

2.32 NATIONAL HISTORIC PRESERVATION ACT REQUIREMENTS - LEASE (SMALL) (SEP 2015)

A. Where a Memorandum of Agreement or other pre-award agreement concluding the Section 106 consultation includes mitigation, design review or other continuing responsibilities of the Government, Lessor must allow the Government access to the Property to carry out compliance activities. For Tenant Improvements and other tenant-driven alterations within an existing historic building, that could affect historic properties, compliance also may require on-going design review. In these instances, Lessor will be required to retain, at its sole cost and expense, the services of a preservation architect who meets or exceeds the *Secretary of the Interior's Professional Qualifications Standards for Historic Architecture*, as amended and annotated and previously published in the Code of Federal Regulations, 36 C.F.R. part 61, and the *GSA Qualifications Standards for Preservation Architects*. These standards are available at: [HTTP://WWW.GSA.GOV/HISTORICPRESERVATION](http://www.gsa.gov/historicpreservation)>Project Management Tools>Qualification Requirements for Preservation Architects. The preservation architect will be responsible for developing preservation design solutions and project documentation required for review by the Government, the State Historic Preservation Officer (SHPO), the Tribal Historic Preservation Officer (THPO), if applicable, and other consulting parties in accordance with Section 106. For Tenant Improvements and other tenant-driven alterations within an existing historic building, the preservation architect must develop context-sensitive design options consistent with the *Secretary of the Interior's Standards for the Treatment of Historic Properties*.

B. The costs for development of design alternatives and review submittals for work required under the Lease are the sole responsibility of Lessor. In addition, building shell costs relating to such design alternatives are the sole responsibility of Lessor and must be included in the shell rent

SECTION 3 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES

3.01 SCHEDULE FOR COMPLETION OF SPACE (SIMPLIFIED) (SEP 2013)

Design and construction activities for the Space shall commence upon Lease award. The Lessor shall schedule the following activities to achieve timely completion of the work required by this Lease:

A. Design Intent Drawings. The Lessor shall prepare and deliver to the Government, as part of the shell cost, design intent drawings (DIDs) meeting all requirements set forth in the Lease within **10 Working Days** of the Lease Award Date. The Government shall respond within **10 Working Days** of receipt of the DIDs by either issuing a Notice to Proceed or providing notice indicating the manner in which the DIDs do not meet all requirements of the Lease. If the DIDs do not conform to the Lease requirements, the Lessor shall revise and resubmit the DIDs within 3 Working Days. The Lessor shall be responsible for delays to Acceptance of the Premises attributable to the Lessor's failure to prepare DIDs conforming to the Lease requirements.

B. Notice to Proceed (NTP). If the DIDs conform to the Lease requirements, the Government shall issue NTP; however, the Government shall not be obligated to issue a NTP less than 10 Working Days from receipt of DIDs, as originally submitted or revised. Issuance of NTP shall not be construed as a waiver of any requirement set forth in this Lease.

C. Construction Schedule. The Lessor shall complete all required build-out conforming to the Lease and approved DIDs within 40 Working Days of issuance of NTP.

3.02 ACCESS TO THE GOVERNMENT PRIOR TO ACCEPTANCE (SIMPLIFIED) (SEP 2015)

Subject to the Lessor's permission, which shall not be unreasonably withheld, the Government or its contractors shall have access to the Premises prior to acceptance of the Space to prepare the Space for occupancy. If the work to be completed by the Government is a prerequisite for the issuance of a Certificate of Occupancy, or its equivalent, the Government shall be entitled to at least 10 Working Days to complete work by its own contractors.

3.03 ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (SIMPLIFIED) (SEP 2015)

A. The Government shall accept the Space only if the construction of Building shell and TIs, as applicable, conforming to this Lease and any layout drawings is substantially complete, as determined by the Lease Contracting Officer, and a Certificate of Occupancy (C of O) has been issued. The Space shall be considered substantially complete only if the Space may be used for its intended purpose and completion of remaining work will not interfere unreasonably with the Government's enjoyment of the Space.

B. The Lessor shall provide a valid C of O, issued by the local jurisdiction, for the intended use of the Government. If the local jurisdiction does not issue C of O's or if the C of O is not available, the Lessor may satisfy this condition by providing a report prepared by a licensed fire protection engineer that indicates the Space and Building are compliant with all applicable local codes and ordinances and all fire protection and life safety-related requirements of this Lease.

3.04 LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (SMALL) (SEP 2015)

The Lease Term Commencement Date, and final measurement verification of the Premises, shall be memorialized by Lease Amendment.

3.05 AS-BUILT DRAWINGS (SMALL) (SEP 2015)

Not later than 60 days after the acceptance of the Space, the Lessor, at Lessor's expense, shall furnish to the Government a complete set of Computer Aided Design (CAD) files of as-built floor plans showing the Space under Lease, as well as corridors, stairways, and core areas. The plans shall have been generated by a CAD program which is compatible with the latest release of AutoCAD.

3.06 SEISMIC RETROFIT (SEP 2013)

The following requirements apply to Leases requiring seismic retrofit:

A. The Lessor shall provide a final construction schedule, all final design and construction documents for the seismic retrofit, including structural calculations, drawings, and specifications to the Government for review and approval prior to the start of construction. When required by local building code, a geotechnical report shall be made available to the Government.

B. The Lessor's registered civil or structural engineer shall perform special inspections to meet the requirements of Chapter 17 of the International Building Code (IBC).

C. For Leases requiring seismic retrofit, the Space will not be considered substantially complete until a Seismic Form E - Certificate Of Seismic Compliance - Retrofitted Building, certifying that the Building meets the Basic Safety Objective of ASCE/SEI 41, executed by a registered civil or structural engineer, has been delivered to the LCO.

SECTION 4 TENANT IMPROVEMENT COMPONENTS

4.01 TENANT IMPROVEMENTS AND PRICING (SMALL) (SEP 2015)

- A. The Lease is a fully serviced, turnkey Lease with a fixed rent that covers all Lessor costs, including all demolition, shell upgrades, TIs, insurance, operating costs, taxes, parking, and security upgrades. Rent will be based upon a proposed rental rate per **Parking Space**, limited by the offered rate and the maximum **Number of Parking Spaces** solicited under this RLP. The Tenant Improvements to be delivered by the Lessor will be based upon information provided with this Lease; the Lessor will be required to design and build the TIs required to meet VA standards. Offerors are encouraged to consider the use of existing fit-out and other improvements to minimize waste.
- B. INTENTIONALLY DELETED
- C. INTENTIONALLY DELETED

4.02 INTENTIONALLY DELETED

4.03 INTENTIONALLY DELETED

4.04 INTENTIONALLY DELETED

4.05 DOORS: INTERIOR (SMALL) (SEP 2015)

Doors within the Space shall have a minimum clear opening of 32" wide x 80" high and shall be flush, solid core, wood with a natural wood veneer face or an equivalent door pre-approved by the LCO. They shall meet the requirements of NFPA 101, Life Safety Code or the International Building Code (current as of the Lease Award Date). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semi-gloss oil-based paint with no formaldehyde.

4.06 DOORS: HARDWARE (SMALL) (SEP 2015)

Doors shall have door handles or door pulls with heavyweight hinges. All doors shall have corresponding doorstops (wall- or floor-mounted) and silencers. All door entrances leading into the Space from public corridors and exterior doors shall have automatic door closers. Doors designated by the Government shall be equipped with 5-pin, tumbler cylinder locks and strike plates. All locks shall be master keyed. Furnish at least two master keys for each lock to the Government. Any exterior entrance shall have a high security lock, with appropriate key control procedures, as determined by Government specifications. Hinge pins and hasps shall be secured against unauthorized removal by using spot welds or pinned mounting bolts. The exterior side of the door shall have a lock guard or astragal to prevent tampering of the latch hardware. Doors used for egress only shall not have any operable exterior hardware. All security-locking arrangements on doors used for egress shall comply with requirements of NFPA 101 or the International Building Code current as of the Lease Award Date.

4.07 INTENTIONALLY DELETED

4.08 PAINTING – TI (SMALL) (SEP 2015)

Prior to acceptance, all surfaces within the Space which are designated by GSA for painting shall be newly finished in colors acceptable to the Government, using products that minimize VOC off-gassing

4.09 FLOOR COVERINGS

The entire leased area shall be fully paved and stripped in accordance with city codes.

4.10 INTENTIONALLY DELETED

4.11 ELECTRICAL: DISTRIBUTION (SMALL) (SEP 2015)

- A. All electrical outlets shall be installed in accordance with NFPA Standard 70.
- B. The Lessor shall in all cases safely conceal outlets and associated wiring (for electricity, voice, and data) to the workstation(s) in a method acceptable to the Government.

4.12 INTENTIONALLY DELETED

4.13 INTENTIONALLY DELETED

4.14 INTENTIONALLY DELETED

4.15 INTENTIONALLY DELETED

4.16 LIGHTING: INTERIOR AND PARKING – TI (SMALL) (SEP 2015)

FIXTURES: Any additional lighting fixtures and/or components required beyond what would have been provided under the paragraph, "Lighting: Interior and Parking – Shell (SMALL)" are part of the TIs.

SECTION 5 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM

5.01 PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (SIMPLIFIED) (JUN 2012)

The Government's normal hours of operations are established as **6:00 AM to 9:00 PM**, Monday through Friday, with the exception of Federal holidays. Services, maintenance, and utilities shall be provided during these hours. The Government shall have access to the Premises and its Appurtenant Areas at all times without additional payment, including the use, during other than normal hours, of necessary services and utilities such as elevators, restrooms, lights, and electric power. Cleaning shall be performed during normal hours.

5.02 UTILITIES (APR 2011) The Lessor is responsible for providing all utilities necessary for base Building and tenant operations as part of the rental consideration.

5.03 INTENTIONALLY DELETED

5.04 INTENTIONALLY DELETED

5.05 JANITORIAL SERVICES (SMALL) (SEP 2015)

The Lessor shall maintain the Premises and all areas of the Property to which the Government has routine access in a clean condition and shall provide supplies and equipment for the term of the Lease. The following schedule describes the level of services intended. Performance will be based on the LCO's evaluation of results, not the frequency or method of performance.

A. Daily. Empty trash receptacles. Sweep entrances, lobbies, and corridors if applicable. Dispose of all trash and garbage generated in or about the Building. Spray buff resilient floors in main corridors, entrances, and lobbies if applicable. Clean elevators and escalators if applicable. Police sidewalks, parking areas, and driveways.

B. As required. Properly maintain plants and lawns. Provide initial supply, installation, and replacement of light bulbs, tubes, ballasts, and starters. Provide and empty exterior ash cans and clean area of any discarded cigarette butts. Remove snow and ice from entrances, exterior walks, and parking lots of the building by the beginning of the normal working hours and continuing throughout the day.

C. Pest control. Control pests as appropriate, using Integrated Pest Management techniques, as specified in the GSA Environmental Management Integrated Pest Management Technique Guide (E402-1001).

5.06 SELECTION OF CLEANING PRODUCTS (SMALL) (SEP 2015)

The Lessor shall use cleaning products (including general purpose cleaners, floor cleaners, hand soap, etc.) that comply with either the Green Seal standard, the UL/EcoLogo standard, EPA's Design for the Environment (DfE) designation, or a substitute acceptable to the LCO. Hand soap products shall also be USDA Certified BioPreferred.

5.07 SELECTION OF PAPER PRODUCTS (APR 2015)

The Lessor shall select paper and paper products (e.g., restroom tissue and paper towels) conforming to the Green Seal Standard (GS-1), or a substitute acceptable to the LCO.

5.08 MAINTENANCE OF PROVIDED FINISHES (SMALL) (SEP 2015)

A. Paint, wall coverings. Lessor shall maintain all wall coverings and high performance paint coatings in "like new" condition for the life of the Lease. All painted surfaces, shall be repainted at the Lessor's expense, including the moving and returning of furnishings, any time during the occupancy by the Government if the paint is peeling or permanently stained, except where damaged due to the negligence of the Government. All work shall be done after normal working hours as defined elsewhere in this Lease.

B. Flooring.

1. Except when damaged by the Government, the Lessor shall repair or replace flooring at any time during the Lease term when:

- a. Backing or underlayment is exposed;
- b. There are noticeable variations in surface color or texture;
- c. It has curls, upturned edges, or other noticeable variations in texture;
- d. Tiles are loose; or,
- e. Tears or tripping hazards are present.

2. Repair or replacement shall include the moving and returning of furnishings, including disassembly and reassembly of systems furniture per manufacturer's warranty, if necessary. Work shall be performed after normal hours.

5.09 IDENTITY VERIFICATION OF PERSONNEL (SMALL) (SEP 2015)

A. The Government reserves the right to verify identities of personnel with routine pre-occupancy and/or unaccompanied access to Government space. The Lessor shall comply with the agency personal identity verification procedures below that implement [Homeland Security Presidential](#)

Directive-12 (HSPD-12), Office of Management and Budget (OMB) guidance M-05-24 and M11-11, and Federal Information Processing Standards Publication (FIPS PUB) Number 201, as amended.

B. The Government reserves the right to conduct additional background checks on Lessor personnel and contractors with routine access to Government leased space throughout the term of the Lease.

C. Upon request, the Lessor will notify the Government whether they will use either the manual process and submit completed fingerprint charts and background investigation forms, or use the electronic process of ID verification, completed through the e-QIP system (www.opm.gov). This would be done for each employee of the Lessor, as well as employees of the Lessor's contractors or subcontractors who will provide building operating services requiring routine access to the Government's leased space for a period greater than 6 months. The Government may also require this information for the Lessor's employees, contractors, or subcontractors who will be engaged to perform alterations or emergency repairs in the Government's space.

5.10 RANDOLPH-SHEPPARD COMPLIANCE (SMALL) (SEP 2015)

The Government may provide vending machines within the Government's leased area under the provisions of the Randolph-Sheppard Act (20 USC 107 et. seq.). During the term of the Lease, the Lessor may not establish vending facilities within the leased Space that will compete with any Randolph-Sheppard vending facilities.

5.11 INDOOR AIR QUALITY (SEP 2013)

A. The Lessor shall control contaminants at the source and/or operate the Space in such a manner that the GSA indicator levels for carbon monoxide (CO), carbon dioxide (CO₂), and formaldehyde (HCHO) are not exceeded. The indicator levels for office areas shall be: CO 9 ppm time weighted average (TWA 8 hour sample); CO₂ 1,000 ppm (TWA); HCHO 0.1 ppm (TWA).

B. The Lessor shall make a reasonable attempt to apply insecticides, paints, glues, adhesives, and HVAC system cleaning compounds with highly volatile or irritating organic compounds, outside of working hours. Except in an emergency, the Lessor shall provide at least 72 hours advance notice to the Government before applying noxious chemicals in occupied Spaces and shall adequately ventilate those Spaces during and after application.

C. The Lessor shall promptly investigate indoor air quality (IAQ) complaints and shall implement the necessary controls to address the complaint.

D. The Government reserves the right to conduct independent IAQ assessments and detailed studies in Space that it occupies, as well as in space serving the Space (e.g., common use areas, mechanical rooms, HVAC systems, etc.). The Lessor shall assist the Government in its assessments and detailed studies by:

1. Making available information on Building operations and Lessor activities;
2. Providing access to Space for assessment and testing, if required; and
3. Implementing corrective measures required by the LCO.

E. The Lessor shall provide to the Government material safety data sheets (MSDS) upon request for the following products prior to their use during the term of the Lease: adhesives, caulking, sealants, insulating materials, fireproofing or firestopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finish for wood surfaces, janitorial cleaning products, pesticides, rodenticides, and herbicides. The Government reserves the right to review such products used by the Lessor within:

1. The Space;
2. Common Building areas;
3. Ventilation systems and zones serving the Space; and
4. The area above suspended ceilings and engineering space in the same ventilation zone as the Space.

F. Where hazardous gasses or chemicals (any products with data in the Health and Safety section of the MSDS sheets) may be present or used, including large-scale copying and printing rooms, segregate areas with deck-to-deck partitions with separate outside exhausting at a rate of at least 0.5 cubic feet per minute per SF, no air recirculation. The mechanical system must operate at a negative pressure compared with the surrounding spaces of at least an average of 5 Pa (pascal) (0.02 inches of water gauge) and with a minimum of 1 Pa (0.004 inches of water gauge) when the doors to the rooms are closed.

5.12 RADON IN AIR (SEP 2013)

If Space planned for occupancy by the Government is on the second floor above grade or lower, the Lessor shall, prior to occupancy, test the leased Space for 2 days to 3 days using charcoal canisters. The Lessor is responsible to provide Space in which radon levels in air are below the GSA action levels of 4 picoCuries per liter (pCi/L) for childcare and 25 pCi/L for all other space. After the initial testing, a follow-up test for a minimum of 90 days using alpha track detectors shall be completed. For further information on radon, go to: <http://www.epa.gov/radon/zonemap.html>.

5.13 RADON IN WATER (JUN 2012)

A. If the water source is not from a public utility, the Lessor shall demonstrate that water provided to the Premises is in compliance with EPA requirements and shall submit certification to the LCO prior to the Government occupying the Space.

B. If the EPA action level is reached or exceeded, the Lessor shall institute appropriate abatement methods which reduce the radon levels to below this action.

5.14 HAZARDOUS MATERIALS (SEP 2013)

A. The leased Space shall be free of hazardous materials, hazardous substances, and hazardous wastes, as defined by and according to applicable Federal, state, and local environmental regulations. Should there be reason to suspect otherwise, the Government reserves the right, at Lessor's expense, to require documentation or testing to confirm that the Space is free of all hazardous materials.

B. Lessor shall, to the extent of its knowledge, notify Government of the introduction of any hazardous materials onto the Property by Lessor or others, including but not limited to, co-tenants occupying Space in the Building.

5.15 MOLD (SIMPLIFIED) (SEP 2013)

A. Actionable mold is mold of types and concentrations in excess of that found in the local outdoor air.

B. The Lessor shall provide Space to the Government that is free from actionable mold and free from any conditions that reasonably can be anticipated to permit the growth of actionable mold or are indicative of the possibility that actionable mold will be present (indicators).

5.16 OCCUPANT EMERGENCY PLANS (SMALL) (SEP 2015)

The Lessor is required to cooperate, participate and comply with the development and implementation, and any subsequent revisions of the Government's Occupant Emergency Plan (OEP) and if necessary, a supplemental Shelter-in Place (SIP) Plan.

SECTION 6 ADDITIONAL TERMS AND CONDITIONS

6.01 SHELTER:

A covered shelter for a minimum of 30 persons must be provided on the parking property, adjacent to the shuttle bus pickup point.