

**SECTION 09 06 00  
SCHEDULE FOR FINISHES**

**PART I - GENERAL**

**1.1 DESCRIPTION**

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

**1.2 MANUFACTURERS**

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by the Contracting Officer's Technical Representative (COTR) with approval of the Contracting Officer for finish requirements.

**1.3 SUBMITALS**

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

**1.4 APPLICABLE PUBLICATIONS**

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.
- B. MASTER PAINTING INSTITUTE: (MPI)  
2001.....Architectural Painting Specification Manual

**PART 2- PRODUCTS**

**2.1 COLOR BOARD**

- A. Size: As required to display building finishes.
- B. Labeled for:
  - 1. Building name and Number.
  - 2. All finishes used.

**2.7 DIVISION 07 - THERMAL AND MOISTURE PROTECTION**

A. SECTION 07 92 00, JOINT SEALANTS

Location	Color	Manufacturer	Manufacturer Color
New to Existing Walls	White		

**2.8 DIVISION 08 - OPENINGS**

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including hardware attached to door	
Component	Color of Paint Type and Gloss
Door	EP2 (Epoxy, Gloss) - See 2.9 "Division 09 - Finishes for color"
Frame	EP2 (Epoxy, Gloss) - See 2.9 "Division 09 - Finishes for color"

B. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	EP2 (Epoxy, Gloss) - See 2.9 "Division 09 - Finishes for color"

D. SECTION 08 56 19, PASS WINDOWS

Material	Finish
Aluminum	Clear Anodized, Class II

C. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges	Stainless Steel	US32D
Door Closers	Powder Coated Steel	
Door Stops	Stainless Steel	US32D
Lock/ Latches	Stainless Steel	US32D
Protection Plates	Stainless Steel	US32D

D. SECTION 08 80 00, GLAZING

Glazing Type	Manufacturer	Mfg. Color Name/No.
G-1	NA	Clear Tempered Safety Glass

**2.9 DIVISION 09 - FINISHES**

A. SECTION 09 65 13, RESILIENT BASE AND ACCESSORIES

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
RB1	Rubber Base (RB)	4 inch		To match Burke "Pearl" 137
	Transition Strips			To match rubber base.

B. SECTION 09 67 00, RESINOUS FLOORING

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
RF1	Resinous Flooring (RF)			To be selected from Manufacturer's Standard colors
	Integral Base	6 inch		Color to match RF

Atlanta VA Medical Center  
 Decatur GA 30033

Renovate SPS  
 508-10-113

C. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
EP1	SemiGloss, Level 5		Match PPG Color 512-1 "Winter Mood"
EP2	SemiGloss, Level 5		Match PPG Color 309-4 "Quaking Grass"

2.10 DIVISION 10 - SPECIALTIES

A. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

Item	Material	Manufacturer	Mfg. Color Name/No.
Corner Guards	Stainless Steel		#4 Finish

B. SECTION 10 28 00, TOILET AND BATH ACCESSORIES

Item	Material	Manufacturer	Mfg. Color Name/No.
Paper Towel Dispensers	Stainless Steel		#4 Finish

**PART III EXECUTION**

**3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS**

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS	
Term	Abbreviation
Acoustical Ceiling	AT
Anodized Aluminum Colored	AAC
Anodized Aluminum Natural Finish	AA
Baked On Enamel	BE
Brick Face	BR
Carpet	CP
Carpet Module Tile	CPT
Concrete	C
Concrete Masonry Unit	CMU
Existing	E
Exposed Divider Strips	EXP
Exterior	EXT
Exterior Finish System	EFS
Exterior Paint	EXT-P
Exterior Stain	EXT-ST
Fabric Wallcovering	WF
Facing Tile	SCT
Floor Mats & Frames	FM
Floor Tile, Mosaic	FT
Fluorocarbon	FC
Granite	GT
Gypsum Wallboard	GWB
High Glazed Coating	SC
Latex Mastic Flooring	LM
Marble	MB

Material	MAT
Mortar	M
Multi-Color Coating	MC
Natural Finish	NF
Paint	P
Paver Tile	PVT
Plaster	PL
Plaster High Strength	HSPL
Plaster Keene Cement	KC
Plastic Laminate	HPDL
Polypropylene Fabric Wallcovering	PFW
Porcelain Paver Tile	PPT
Rubber Base	RB
Rubber Tile Flooring	RT
Stain	ST
Stone Flooring	SF
Suspension Decorative Grids	SDG
Veneer Plaster	VP
Vinyl Base	VB
Vinyl Coated Fabric Wallcovering	W
Vinyl Composition Tile	VCT
Vinyl Sheet Flooring	VSF
Vinyl Sheet Flooring (Welded Seams)	WSF
Wall Border	WB
Wood	WD

Atlanta VA Medical Center  
Decatur GA 30033

Renovate SPS  
508-10-113

### 3.2 FINISH SCHEDULE SYMBOLS

#### Symbol Definition

\*\* Same finish as adjoining walls  
- No color required  
E Existing  
XX To match existing  
EFTR Existing finish to remain  
RM Remove

**3.3 ROOM FINISH SCHEDULE**

B. ROOM FINISH SCHEDULE

Room No. and Name		FLOOR			BASE		WALL		CEILING		REMARKS
001 Scope Sterilization Room	N E W	RF-1			MAT	FCC	MAT	FCC	MAT	FCC	
				N	RF-1		E	EP1			EPOXY PAINT INFILL CMU - EP-1 EPOXY PAINT DOOR 001 - EP-2
				E	RF-1		E	EP1			EPOXY PAINT INFILL CMU - EP-1
				S	RF-1		E	EP1			
				W	RF-1		GWB	EP1			
				C					GWB	EP1	
002 Vestibule	N E W	RF-1		N	RF-1		GWB	EP1			
				E	RF-1		GWB	EP1			
				S	RF-1		E	EP1			
				W	RF-1		E	EP1			EPOXY PAINT DOORS 001 AND 002 - EP-2
				C					GWB	EP1	
003 Scope Cleaning Room	N E W	RF-1		N	E		E	EP1			
				E	QT-1		GWB	EP1			QT-1 QUARRY TILE BASE TO MATCH EXISTING.
				S	QT-1		GWB	EP1			QT-1 QUARRY TILE BASE TO MATCH EXISTING.

				W	QT-1		GWB	EP1			QT-1 QUARRY TILE BASE TO MATCH EXISTING.EPOXY PAINT DOOR 003 - EP-2
				C					GWB	EP1	
004 Washer Room	N E W	E		N	RB-1		GWB	EP1			
				E	RB-1		GWB	EP1			
				S	E		E				
				W	E		E	EP1			
				C					E	EP1	
E01 Soiled Receiving and Decontamination	E X I S T	E		N	E		E				
				E	E		E				
				S	E		E				
				W	QT-1		GWB	EP1			AT NEW WALLS AND INFILLS ONLY
				C					E		
E02 Soiled Linen Receiving	E X I S T	E		N	E		E				
				E	RB-1		GWB	EP1 - MATCH EXIST			
				S	E		E				
				W	E		E				
				C					E	EP1	

--- E N D---