

REPAIR CLC COURTYARD

CONTRACTOR QUESTIONS 24Feb2017

1) What is the anticipated start date for this project?

Anticipated award date is late March, with notice to proceed expected to be mid to late April, depending on weather.

2) M101 shows the 1-1/4" supply and return lines going to Man 1. Are there any special requirements for these pipes running outside of the building to the manifold?

This piping should be insulated per section 23 07 11 with Polyiso-cyanurate Closed-Cell Rigid insulation.

3) Drawing VS001 the 1'6" control joint and cut joint what type of concrete is to be in this 1'6" area?, LS001 does not have a legend that matches this area, please advise.

Stained concrete; see amendment #3 drawings.