

F4 ENLARGED ENTRANCE PLAN
1/2" = 1'-0"

0 3" 6" 1'

100% SUBMITTAL

GENERAL SHEET NOTES

A. SLOPE EXTERIOR CONCRETE TO DRAINS 1/4" PER FOOT MINIMUM.

B. PRE-ENGINEERED METAL CANOPY PLAN IS A BASIS OF DESIGN AND REQUIRES COORDINATION WITH PRE-ENGINEERED METAL CANOPY MANUFACTURER. MANUFACTURER MAY REQUIRE ADDITIONAL COLUMNS, BEAMS, OR VARYING CONFIGURATION TO COMPLY WITH MANUFACTURER DESIGN AND STANDARDS. CONTRACTOR SHALL COORDINATE PROPOSED PLAN WITH MANUFACTURER FOR ANY ADDITIONAL REQUIREMENTS BEFORE BID PRICING.

C. ALL DIMENSIONS AND EXISTING CONDITIONS TO BE FIELD VERIFIED BY THE CONTRACTOR.

D. CANOPY SHALL BE A COMPLETE PRE-ENGINEERED, PRE-FINISHED ALUMINUM CANOPY SYSTEM WITH INTEGRAL GUTTERS AND DOWNSPOUTS. CONTRACTOR SHALL FURNISH A COMPLETE SYSTEM WITH ALL PARTS, PIECES, CONNECTORS, ANCHORS AND OTHER COMPONENTS REQUIRED FOR PROPER PERFORMANCE AND FUNCTION.

SHEET KEYNOTES (X)

01. ALUMINUM DOWNSPOUT FROM ROOF ABOVE.
2. FULLY RECESSED STEP LIGHT. SEE ELECTRICAL DRAWINGS.
3. PLANTER DRAIN THROUGH WALL TO DAYLIGHT.
4. 4" PERFORATED DRAIN PIPE TYPICAL AT PLANTER AND NEW FOUNDATION.
5. 1" OPEN JOINT.
6. 6"X6" PRE-ENGINEERED METAL CANOPY COLUMN, TYPICAL.
7. PRE-CAST COPING, TYPICAL.
8. PRE-CAST COPING CONTROL JOINT, TYPICAL.
9. EDGE OF BRICK BELOW, TYPICAL.
10. STAINLESS STEEL HANDRAIL, TYPICAL.
11. STAINLESS STEEL GUARDRAIL TYPICAL..
12. CONCRETE SLAB CONTROL JOINT, TYP.
13. RAMP BEGINS.
14. EXISTING SITE LAMP.

COORDINATION DRAWINGS

THE MECHANICAL CONTRACTOR SHALL TAKE THE LEAD IN PREPARATION OF COORDINATION DRAWINGS. SUCH DRAWINGS SHALL BE ARRANGED AND DESIGNED THROUGH AND FROM COORDINATION WITH ALL OTHER MAJOR AND MINOR SUBCONTRACTORS AND THE GENERAL CONTRACTOR. PROVIDE PLAN VIEWS, SECTIONS AND ELEVATIONS AS REQUIRED TO FULLY COORDINATE ALL NEW WORK WITH ITSELF AND EXISTING CONDITIONS. DRAW TO SCALE (AT NOT LESS THAN 3/8" = 1'-0"). DRAWINGS SHALL SHOW, BUT NOT BE LIMITED TO: ALL WALL RATINGS; ALL DUCTWORK; ALL AIR DISTRIBUTION; MECHANICAL EQUIPMENT; MECHANICAL PIPING; FIRE PROTECTION PIPING; ALL PLUMBING PIPING; CABLE TRAYS (WITH ELEVATIONS NOTED); LIGHTING FIXTURES (WHEN CEILING MOUNTED); CEILING GRID AND CEILING HEIGHT; MAJOR BEAMS AND JOISTS (WITH ELEVATIONS MARKED); FIRE ALARM DEVICES AND SPEAKERS (WHERE CEILING MOUNTED); ELECTRICAL CONDUITS LARGER THAN 2-INCH DIAMETER; ELECTRICAL BUSWAY AND REQUIRED CLEARANCES; EQUIPMENT PROVIDED BY OTHERS THAT PROTRUDE INTO CEILING CAVITIES OR IMPEDE THE LOCATION OR ACCESS TO ABOVE CEILING PIPING, DUCTWORK OF OTHER EQUIPMENT. SECTIONS SHALL BE CUT THROUGH AREAS SHOWING MATERIALS AND SYSTEMS OF ALL CONTRACTS. IF THERE ARE ANY OUTSTANDING ISSUES THAT CANNOT BE RESOLVED, CONSULT WITH THE ARCHITECT AND/OR ENGINEER (THROUGH THE VA COTR) FOR GUIDANCE AND MAKE CORRECTIONS IN ACCORDANCE WITH DIRECTIONS GIVEN. IT IS IMPORTANT TO NOTE THAT FABRICATION CANNOT BEGIN UNTIL COORDINATION DRAWINGS HAVE BEEN APPROVED. ANY MATERIAL, EQUIPMENT, SYSTEMS, ETC., PROCUREMENT OR INSTALLATION COMMENCED PRIOR TO APPROVAL IS TAKEN AT THE CONTRACTORS OWN RISK AND MAY HAVE TO BE MODIFIED, MOVED AND/OR RECONFIGURED AT THE CONTRACTORS COST.

TYPICAL SYMBOLS

- EXISTING WALL, DOOR, WINDOW, MILLWORK, FIXTURE OR OTHER FIXTURE OR ASSEMBLY TO BE REMOVED.
- EXISTING WALL, DOOR, WINDOW, MILLWORK, FIXTURE OR OTHER FIXTURE OR ASSEMBLY TO REMAIN.
- NEW WALL
- SMOKE TIGHT WALL
- 1-HOUR FIRE RATED WALL
- 2-HOUR FIRE RATED WALL
- 1 HOUR FIRE SMOKE RATED WALL
- PROJECT LIMITS OF WORK
- NO PIPING OR DUCTWORK SHALL BE ROUTED THROUGH ELECTRICAL AND/OR DATA ROOMS.

KEY PLAN



REVISION NO.	REVISION DESCRIPTION	By	Date

Revisions

Department of Veterans Affairs
Medical Center
1826 Veterans Blvd.
Dublin, Ga. 31021

SEAL (DANIEL C. SALTRICK, REGISTERED ARCHITECT, 8867, NORTH CAROLINA, CHARLOTTE, NC) 6.10.11

Architect/Engineer Address
Harrell, Saltrick & Hopper
Design & Management Solutions for the Built Environment
151 LOCUST STREET, SUITE #1
AVONDALE ESTATES, GA 30002
P 704.814.1325
F 704.321.0833
WWW.HSHPC.COM

COPYRIGHT © 2011 HARRELL SALTRICK & HOPPER, PC

HSH PROJECT # 10004

Recommended Approvals:	
1. MEDICAL DIRECTOR	6. OPERATIONS SERVICE LINE MANAGER
2. ASSOCIATE DIRECTOR	7. INFECTION CONTROL SAFETY MANAGER
3. CHIEF OF STAFF	8. SAFETY MANAGER
4. ASSOC. DIRECTOR	9. GENERAL ENGINEER
5. SERVICE LINE MGRS.	10. COTR

Drawing Title: ENLARGED ARCHITECTURAL ENTRANCE PLAN

FULLY SPRINKLERED

Project Title: RENOVATE 13A FOR ENDOSCOPY SUITE

Drawn	Building Number	AutoCAD File Name
	MJF	
Checked	Reviewed	Const. Contract No.

Date: June 10, 2011

Project Number: 557-10-108

DRAWING No. A-403

Veterans Affairs