GENERAL SHEET NOTES

A. ALL DIMENSIONS ARE FROM FACE OF SHEET ROCK TO FACE OF SHEET ROCK.

B. ALL DIMENSIONS ALONG AN EGRESS ROUTE ARE CLEAR; INSIDE OF HANDRAILS, CHAIR RAILS, ETC.

SHEET KEYNOTES (X)

01. EXISTING 1-HOUR FIRE RATED WALL AT EXISTING CHASE.

02. NEW 1-HOUR FIRE RATED WALL AT EXISTING CHASE.

LIFE SAFETY SYMBOL LEGEND

ROOM — ROOM NAME
670 — AREA OF ROOM
20 NET — AREA PER OCCUPANT (NET OR GROSS)
33 PEOPLE — OCCUPANT LOAD PER ROOM

START OF EGRESS ROUTE (WITH TRAVEL DISTANCE NOTED)

DIRECTION OF TRAVEL

END OF EGRESS ROUTE (EXIT)

FEC — NEW FULLY RECESSED FIRE EXTINGUISHER CABINET.

RE — REQUIRED EXIT, DIRECTION AS INDICATED

EMERGENCY BATTERY PACK UNIT, SEE ELECTRICAL.

CEILING MOUNTED EXIT SIGN, SEE ELECTRICAL.

92 PERSON / 18.4" 72" REQ. PROV. — EGRESS OCCUPANT LOAD / PROVIDED EGRESS WIDTH / MINIMUM REQUIRED EGRESS WIDTH = (OCC. LOAD)(.2)

PROJECT LOCATION AND LIMITS OF WORK

TRAVELING DISTANCE: 137 FT.

TRAVELING DISTANCE: 195 FT.

TRAVELING DISTANCE: 181 FT.

NOTE:
THIS IS NOT AN ACCESSIBLE MEANS OF EGRESS

D1 LIFE SAFETY PLAN
1/8" = 1'-0"

NOTE:
FOR DURATION OF PROJECT: MAINTAIN FIRE ALARM PULL STATIONS AT EACH END AND MIDDLE OF PROJECT AREA. COVER SMOKE AND HEAT DETECTORS AND DISABLE FIRE ALARM SYSTEM (PROJECT AREA ONLY) DURING CONSTRUCTION ACTIVITIES. UNCOVER SMOKE AND HEAT DETECTORS AND ENABLE FIRE ALARM SYSTEM WHEN CONSTRUCTION ACTIVITIES ARE NOT TAKING PLACE (TYPICALLY AT NIGHT AND ON WEEKENDS).

TYPICAL SYMBOLS

EXISTING WALL, DOOR, WINDOW, MILLWORK, FIXTURE OR OTHER FIXTURE OR ASSEMBLY TO BE REMOVED.
EXISTING WALL, DOOR, WINDOW, MILLWORK, FIXTURE OR OTHER FIXTURE OR ASSEMBLY TO REMAIN.
NEW WALL
SMOKE TIGHT WALL
1-HOUR FIRE RATED WALL
2-HOUR FIRE RATED WALL
1 HOUR FIRE SMOKE RATED WALL
PROJECT LIMITS OF WORK
NO PIPING OR DUCTWORK SHALL BE ROUTED THROUGH ELECTRICAL AND/OR DATA ROOMS.

KEY PLAN

BLDG. #13

A = FIRST FLOOR
B = SECOND FLOOR

100% SUBMITTAL

REVISION NO.	REVISION DESCRIPTION		

Revisions | By | Date

Department of Veterans Affairs
Medical Center
1826 Veterans Blvd.
Dublin, Ga. 31021

SEAL — DANIEL C. SALTRICK, REGISTERED ARCHITECT, 8867, NORTH CAROLINA, CHARLOTTE, NC

Architect/Engineer Address
Harrell, Saltrick & Hopper
Design & Management Solutions for the Built Environment
151 LOCUST STREET, SUITE 3F, AVONDALE ESTATES, GA 30002
P 704.814.1335 F 704.321.0833
WWW.HSHPC.COM

COPYRIGHT © 2011 HARRELL SALTRICK & HOPPER, PC

HSH PROJECT # 10004

Recommended Approvals:	
1. MEDICAL DIRECTOR	6. OPERATIONS SERVICE LINE MANAGER
2. ASSOCIATE DIRECTOR	7. INFECTION CONTROL SAFETY MANAGER
3. CHIEF OF STAFF	8. SAFETY MANAGER
4. ASSOC. DIRECTOR	9. GENERAL ENGINEER
5. SERVICE LINE MGRS.	10. COTR

Drawing Title: LIFE SAFETY PLAN

FULLY SPRINKLERED

Project Title: RENOVATE 13A FOR ENDOSCOPY SUITE

Date: June 10, 2011

Project Number: 557-10-108

Drawn: MJF | Building Number | AutoCAD File Name | Checked | Reviewed | Const. Contract No.

DRAWING No. G-002

Veterans Affairs