

**BEARDSLEY DESIGN ASSOCIATES**  
**Architecture, Engineering & Landscape Architecture, P.C.**  
**64 South Street**  
**Auburn, New York 13021**

**ADDENDUM #2**

**SEPARATE LIFE SAFETY CIRCUITS PHASE II**

**DEPARTMENT OF VETERANS AFFAIRS**

**SYRACUSE, NEW YORK**

**BDA PROJECT #11148**

April 25, 2012

\*\*\*\*\*  
Drawings and Project Manual dated January 24, 2012, entitled "Separate Life Safety Circuits Phase II, Department of Veterans Affairs, Syracuse, NY" are hereby amended, clarified, and modified as follows:  
\*\*\*\*\*

- ITEM 1      -    REFER TO DRAWINGS A-101 FLOOR PLANS – DUMBWAITERS 1 AND 2, A-102 FLOOR PLANS – DUMBWAITERS 1 AND 2, A-103 FLOOR PLANS – DUMBWAITERS 1 AND 2, A-104 FLOOR PLANS – DUMBWAITERS 3 AND 4, A-105 FLOOR PLANS – DUMBWAITERS 3 AND 4, AND A-106 FLOOR PLANS – DUMBWAITERS 3 AND 4:
- Demolition Keyed Notes:
- Delete Keyed Note 1 in its entirety and replace with the following Keyed Note 1:  
                              “Provide steel lintel L4 x 3-1/2 x 5/16 (LLV) from inside of existing shaft over each opening. Shore existing CMU wall as required. Remove portion of CMU wall for new door opening. Refer to Specification Section 05 50 00 for additional information.”
- ITEM 2      -    REFER TO DRAWINGS A-104 FLOOR PLANS – DUMBWAITERS 3 AND 4, A-105 FLOOR PLANS – DUMBWAITERS 3 AND 4, AND A-106 FLOOR PLANS – DUMBWAITERS 3 AND 4:
- Demolition Keyed Notes:
- Delete Keyed Note 3 in its entirety and replace with the following Keyed Note 3:  
                              “Remove all dumbwaiter equipment. Contractor to remove dumbwaiter equipment within shaft (cab, ropes, pit buffers/channels, rails, control wiring, wireways/conduits, etc.) and within machine room (machines, controls, tool box, etc.). Dumbwaiter is under a service contract with Kone. Contractor must contact Kone at 315-425-0232 for coordination of dumbwaiter demolition.”

**END OF ADDENDUM #2**