

Toolcat Utility Work Machines / Toolcat 5600 Utility Work Machine Specifications & Options

Or similar item

Standard Optional Not Applicable

Units US

Bobcat 5600

Engine

Emissions Tier (EPA)

Tier 4

Engine Cooling

Liquid

Engine Fuel

Diesel

Horsepower

61 hp

Turbocharged Engine

Performance

Rated Operating Capacity (SAE)

1,500 lb

Operating Weight

5685 lb

Travel Speed

17 mph

Travel Speed - Max

17 mph

Travel Speed - Low

8 mph

Travel Speed - Reverse

8 mph

Machine Rated Capacity

2200 lb

3-Point Hitch

n/a

Capacities

Fuel Tank

20 gal

Cargo Box Bed Load Capacity

2000 lb

Cargo Box Length

56 in

Cargo Box Width

51 in

Cargo Box Height

10 in

Cargo Box Bed Load Height

38.2 in

Total Vehicle Rated Capacity

4200 lb

Hydraulic System

Auxiliary Std Flow

18.9 gal/min

Auxiliary Pressure

3,000 psi

Auxiliary High Flow

27.9 gal/min

Dimension

Length

181.6 in

Length without Attachment

145.3 in

Width

60 in

Width (with bucket)

62 in

Height

81 in

Height with Operator Cab

81 in

Bed Height From Ground

38.2 in

Cargo Box Maximum Load

2000 lb

Cargo Box Volume

18 ft³

Ground Clearance

9.2 in

Turning Radius (AWS Mode)

105 in

Outside Turning Diameter

210 in

Features

Heater Air Conditioning

Work Lights

Enclosed Operator Cab (ROPS/FOPS)

Auxiliary Hydraulics

Bob-Tach Attachment System

Joystick Control

Hydrostatic Transmission

Air Conditioning

Cab Enclosure