

PART III

SCHEDULE B -- SPECIAL REQUIREMENTS

PART III: SCHEDULE B--SPECIAL REQUIREMENTS

SECTION 1:	INSTRUCTIONS FOR PRICING THIS SCHEDULE	3
SECTION 2:	GENERAL INFORMATION AND INSTRUCTIONS FOR USERS	4
SECTION 3:	SPECIAL ITEMS FOR THE ENTIRE CMOP.....	5
	3.1 PUBLIC ADDRESS SYSTEM.....	5
	3.2 MASTER ANTENNA TELEVISION (BROADBAND) SYSTEM.....	5
	3.3 SECURITY MANAGEMENT AND CONTROL, AND CENTRALIZED POLICE SECURITY MANAGEMENT SYSTEMS	5
	3.4 MOTION INTRUSION DETECTOR (MID)	5
	3.5 DURESS ALARM AND EMERGENCY NOTIFICATION SYSTEM.....	5
	3.6 RADIO PAGING SYSTEM	5
	3.7 TWO-WAY RADIO SYSTEM.....	6
	3.8 SECURITY SURVEILLANCE TELEVISION (SSTV)	6
	3.9 INTERCOMMUNICATION SYSTEM	6
	3.10 VIDEO TELECONFERENCING SYSTEM (VTEL)	6
	3.11 VA SATELLITE TV SYSTEM.....	6
	3.12 ELECTRONIC ACCESS AND DOOR CONTROL SYSTEM	6
SECTION 4:	SPECIAL EQUIPMENT BY FUNCTIONAL AREA	7
	4.1 FUNCTIONAL AREAS	7
	4.2 ..FUNCTIONAL ROOM LIST	10
SECTION 5:	SUMMARY PRICE SHEET	

PART III: SCHEDULE B -- SPECIAL REQUIREMENTS

SECTION 1: INSTRUCTIONS FOR PRICING THIS SCHEDULE

The Offeror shall submit lump-sum pricing for the purchase and installation of special equipment items specified in Schedule B for laboratory and clinic areas. Offers shall be evaluated in accordance with Part I of the Basic Solicitation. All property placed in, upon, or attached to the premises to be leased, and for which the Government pays by means of lump-sum, shall be and remain the property of the Government, and may be removed or otherwise disposed of by the Government.

As part of the rental consideration, the Offeror must include supporting construction, HVAC systems, utilities, and electrical distribution systems for Offeror furnished equipment and VA furnished equipment to be installed in the CMOP. The price for each item in Schedule B shall include only the direct costs of obtaining and installing the item. Supporting structure(s) and distribution systems are included in the basic rent. Therefore, no additional costs relating to the distribution of services (including plumbing, sewage or electricity) or supporting construction should be ascribed to the special equipment costs in Schedule B.

Special equipment items for the clinic are listed in Sections 3 and 4 below. Pricing lines have been provided at each item to be included for pricing purposes in the offer. The Offeror is required to identify the total price involved for each line item. Totals for each Department or Service in the clinic must be entered on the Summary Price Sheet in the Schedule B document.

The Schedule B document is available as a convenience to Offerors in the form of an Excel workbook (electronic spreadsheet file). The individual worksheets (spreadsheets) in the file have been linked and formulas have been provided to facilitate computation of extended prices and totals. Electronic files are provided without warranty or obligation on the part of the government as to the accuracy or suitability for use. Users of electronic files shall agree to indemnify and hold the VA harmless from any and all claims, damages, losses and expenses including, but not limited to, attorney's fees arising from the use of the electronic files.

Offerors are responsible for the accuracy and completeness of the quantities, costs, subtotals, and totals in their proposals.

Items not listed in Schedule B are to be provided by the Lessor as part of the rental consideration. Such items are either specifically called for in the Basic Solicitation (e.g., drinking fountains) or identified in a paragraph specifying an allowance for payment under the provisions of the Basic Solicitation (e.g., telecommunications outlets) and are not identified for pricing purposes in Schedule B.

Estimated quantities have been provided in Schedule B for use in preparation of offers. An adjustment will be made at the time of final inspection on those items specified in Schedule B if there is any deviation between the quantity actually provided and the Government's estimated quantity.

SECTION 2: GENERAL INFORMATION AND INSTRUCTIONS FOR USERS

Brand Names: Certain equipment may be identified by make and model. Identification of these items in this Solicitation by a "brand name" description is intended to indicate the quality and characteristics of products that will be satisfactory and is not intended to be restrictive. Unless clearly indicated in the offer that an "equal" product is offered, the offer shall be considered as offering a referenced brand name product. Offers of "equal" products or equipment will be considered for this award if such product or equipment is clearly identified in the offer and is determined by the Government to fully meet the salient characteristics of the product or equipment named in this Solicitation. The Government's determination as to the acceptability of the "equal" product shall be based on information furnished or otherwise identified in the offer, as well as other information reasonably available to the VA. If the equipment cited in the Solicitation is no longer available, the manufacturer's currently available equipment that replaces the cited model shall be provided.

Caution to Offerors: The VA is not responsible for locating or securing any information not identified in the offer and not reasonably available to the VA. Accordingly, the Offeror shall furnish with its offer the manufacturer and model of equipment proposed and sufficient descriptive material such as cuts, illustrations, drawings, or other information for the VA to determine whether the product offered meets the specified salient characteristics and establishes exactly what the Offeror proposes to furnish.

Basis of Design: Offerors are advised that room layouts and equipment guide lists used in the development of this solicitation were based on VA PG-18-5, *Equipment Guide List*. These documents are the basis of design for VA facilities nationwide and may be found in VA's Technical Library at <http://www.cfm.va.gov/TIL/equip.asp>

SECTION 3: SPECIAL ITEMS FOR THE ENTIRE CMOP

Placement of special systems required by the entire CMOP will be shown on telecommunications drawings. Please price as totally installed and provide a unit cost for each item as listed in this Schedule. Adjustments in the contract at the time of approval of the equipment drawings will be made based on prices provided by the Offeror in this Schedule B document.

Specific Telecommunications Systems (all systems must be approved by the Contracting Officer or the Contracting Officer's designee.)

3.1 PUBLIC ADDRESS SYSTEM

Provide a public address system. The system will also allow zoning to the major occupied floor spaces such as admin, lobby production, warehouse, shipping, receiving, replenishment, break rooms, and smoking. Public address central equipment shall be located in Telephone Equipment Room. System(s) shall be as manufactured by Bogen, JBL, Dukane, or approved equivalent, as updated to most current technology or manufacturer.

3.2 MASTER ANTENNA TELEVISION (BROADBAND) SYSTEM

Provide a master antenna television (broadband) system. System(s) shall be as manufactured by Blonder Tongue, Scientific Atlanta, Olson Technologies, or approved equivalent, as updated to most current technology or manufacturer.

3.3 SECURITY MANAGEMENT AND CONTROL, AND CENTRALIZED POLICE SECURITY MANAGEMENT SYSTEMS

Provide security management and control, and centralized police security management systems. System(s) shall be as manufactured by Lockheed, Viper, Access Gold, Casi-Rusco, or approved equivalent, as updated to most current technology or manufacturer. LAN/WAN based systems must be on a separate and standalone system and NOT connected to the Facility's LAN/WAN. System must be capable of integrating with the existing VA CMOP Enterprise system.

3.4 MOTION INTRUSION DETECTOR (MID)

Provide a motion intrusion detection system. System shall be Security Metrics, Ademco, Honeywell, or approved equivalent, as updated to most current technology or manufacturer. System must be capable of integrating with the existing VA CMOP Enterprise system.

3.5 DURESS ALARM AND EMERGENCY NOTIFICATION SYSTEM

Provide a duress alarm and emergency notification panic system with visual and audible annunciation at Central Reception Area, connected to selected locations throughout the facility, with call out to a security monitoring company. System shall be Code Blue Pole Systems or approved equivalent, as updated to most current technology or manufacturer. Under no circumstance shall the telephone system be used to provide duress alarm functions. System must be capable of integrating with the existing VA CMOP Enterprise system.

3.6 RADIO PAGING SYSTEM

Provide radio paging system (identified as Public Safety Operation and upgraded to Life Safety when interfaced to Code One (Blue)) as required. System(s) shall be as manufactured

by Motorola, Johnson, Kenwood, or approved equivalent, as updated to most current technology or manufacturer.

3.7 TWO-WAY RADIO SYSTEM

Provide two-way radio systems as required. System(s) shall be as manufactured by Motorola, Johnson, Vertex Standard, or approved equivalent, as updated to most current technology or manufacturer.

3.8 SECURITY SURVEILLANCE TELEVISION (SSTV)

Provide a complete operational SSTV monitoring system with cameras monitoring the building interior, exterior, and parking lot. Provide equipment to monitor each camera. System(s) shall be as manufactured by Panasonic, Video Tek, Pelco, or approved equivalent, as updated to most current technology or manufacturer. System must be capable of integrating with the existing VA CMOP Enterprise system.

3.9 INTERCOMMUNICATION SYSTEM

Provide an intercommunication system. System(s) shall be as manufactured by Bogen, Aiphone, Leviton, or approved equivalent, as updated to most current technology or manufacturer.

3.10 VIDEO TELECONFERENCING SYSTEM (VTEL)

Provide cabling and outlets for the VTEL system. The VA shall provide equipment required for the VTEL system. Install a CAT 6 cable from a data outlet in designated Treatment, Telemedicine, and Classroom to Telephone Equipment Room. Cable from each room shall terminate in center of Telephone Equipment room with thirty (30) feet of excess cable and shall be tagged to indicate room that cable serves. System(s) shall be as manufactured by Polycom, Tandberg, HP, or approved equivalent, as updated to most current technology or manufacturer.

3.11 VA SATELLITE TV SYSTEM

Provide cabling, outlets, and roof support for VA satellite TV system for reception of VA internal programming. VA shall provide satellite dish for Lessor installation. The VA shall furnish and install system equipment. Provide coaxial cable, Belden 7731A, from TV outlets in Classroom and Conference Room to Telephone Equipment Room. Cable from each room shall be installed to center of Telephone Equipment Room above ceiling with thirty (30) LF of excess cable. Cables shall be tagged to identify room that cable serves. Provide coaxial cable from Telephone Equipment Room to Satellite Dish location on roof (250 LF). Provide roof support for satellite dish and means of anchoring satellite dish to roof. System(s) shall be as manufactured by Scientific Atlanta, Blonder Tongue, Pico Macom, or approved equivalent, as updated to most current technology or manufacturer.

3.12 ELECTRONIC ACCESS AND DOOR CONTROL SYSTEM

Provide complete, operational electronic card, keypad, access, and door control system. All access control system products shall be furnished and installed by the same company. System shall be Dyna Lock, Locknetics, Sentrol, or approved equivalent, as updated to most current technology or manufacturer. System must be capable of integrating with the existing VA CMOP Enterprise system.

**Part III: Schedule B – Special Requirements
Sections 1 – 4.1 -- Page 6 of 7**

SECTION 4: SPECIAL EQUIPMENT BY FUNCTIONAL AREA This document lists the special equipment required for each room type in each Functional Area. Although every room type in the Outpatient Clinic is listed, not every room will have special equipment. Where (NR) is indicated, there are no "special requirements" in that room.

4.1 FUNCTIONAL AREAS

Administration
Quality Management
Logistics
Facility Management
Fiscal
Information Technology
Administrative Support
Production
Receiving
Shipping
Replenishment
Warehouse
Production Support
Controlled Substances