


MECHANICAL DEMOLITION FLOOR PLAN




## GENERAL DEMOLITION NOTES

1. REMOVE HVAC UNIT, DUCTWORK, SUPPORTS, GRILLES, ETC. AND DISPOSE OF. WORK IS LOCATED IN OPEN ROOM.
2. REMOVE ASSOCIATE THERMOSTATS.
3. TEMPORARILY CAP OR TERMINATE UTILITIES FOR LATER RECONNECTION. SEE BELOW FOR FURTHER INFORMATION ON ELECTRICAL.
4. CEILING MOUNTED EQUIPMENT, LIGHTS, CONDUIT, ETC. ABOVE HVAC TO REMAIN. RELOCATE LIGHTING TO ACCOMMODATE NEW DUCTWORK WHERE NECESSARY.
5. DEMO WORK TO BE COMPLETED IN CONJUNCTION WITH NEW WORK PHASING. SEE SHEET WH101 FOR PHASING DETAILS.
6. AFTER NEW AHU IS OPERATIONAL, TESTED, AND BALANCED, REMOVE EXISTING WINDOW AC UNITS AND REPLACE WINDOW TO MATCH EXISTING. LOCATION AND QUANTITY TO BE FIELD VERIFIED. WORK TO BE DONE OFF HOURS AND 2 WEEK NOTICE SHALL BE PROVIDED FOR COORDINATION WITH VA STAFF.

## DEMOLITION KEY NOTES

- 1 REMOVE ALL AHU AND EXHAUST FANS, LOCATION AND EXTENT OF WORK TO BE FIELD VERIFIED.
- 2 OFFICE CEILING GRID AND TILES TO REMAIN.
- 3 AIR INTAKE DEMO TO BE TEMPORARILY SEALED FROM WEATHER UNTIL NEW INSTALLED.
- 4 DEMO EXISTING STEAM RADIATOR BACK TO INSULATED STEAM PIPING AND CAP.
- 5 REPAIR HOLE IN WALL TO MATCH EXISTING.
- 6 DEMO EXISTING EXHAUST FAN, DUCTWORK, AND GRILLE. REPAIR EXTERIOR WALL.

	BID AMENDMENT 07	03/02/17
Revisions:		Date



Dept. of Veterans Affairs  
Medical Center  
5000 W. National Avenue  
Milwaukee, WI

**ARCHITECT/ENGINEERS:**  
  
**Clement J. Zablocki VAMC  
Facility Management Division**  
  
**Engineer: Kevin Matthews  
Designer: Kevin Matthews**

Drawing Title:  
**BLDG 70/C BASEMENT  
MECHANICAL - DEMO**  
  
Approved (Project Director):  
**Nathan Tracer**

Project Title:  
**UPGRADE VARIOUS SMALL AIR  
CONDITIONING  
COMPONENTS AND UNITS**  
  
Location:  
**Milwaukee VAMC, Milwaukee WI**  
  
Date:  
**11-22-2016**

Checked  
**NET**

Drawn  
**JLD**

Project Number:  
**698-17-109**  
  
Building Number:  
**70-B**  
  
Drawing Number:  
**MD-101**  
  
Dwg. 6 of 20

**Office of  
Construction  
and Facilities  
Management**  
  
 Department of  
Veterans Affairs