

Project Number 849-MR17-03

Remove and Reset Brick Pavers

at the

Hampton National Cemetery

TECHNICAL SPECIFICATION

TABLE OF CONTENTS

SECTION:

01 00 02	General Requirements
01 33 23	Shop Drawings, Product Data, and Samples
01 45 29	Testing Laboratory Services
01 74 19	Waste Management
02 41 10	Demolition and Site Clearing
31 20 11	Earth Moving
32 14 16	Brick Unit Paving

DRAWING:

849M&R1703-01	Hampton NC Brick Paver South Section
849M&R1703-02	Hampton NC Brick Paver North Section
849M&R1703-03	Hampton NC Typical Paver New Construction Detail

SECTION 01 00 02
GENERAL REQUIREMENTS

1.1 STATEMENT OF BID ITEM(S)

A. Contractor shall provide all labor, tools, materials, equipment, and supervision necessary to complete the work identified on the attached drawing sheets at the Hampton National Cemetery. Hampton National Cemetery is located at Cemetery Road at Marshall Avenue, Hampton, Virginia 23669. Work includes but may not be limited to:

1. Complete all plans and submittals prior to removing patio furnishings, pavers or beginning tree removal.
2. Move all mats, benches and picnic tables from the brick paver area to a cemetery location designated by the Contracting Officer Representative (COR).
3. Remove and set aside all landscaping timbers and mulch to allow for construction of the pavement.
4. Remove pavers and segregate on pallets based on color. Chipped, cracked, deformed, or permanently stained pavers should be disposed of. Assume that 10 percent of the existing bricks will need to be replaced.
5. Remove and dispose of the concrete pavers in front of the grave locator kiosk and concrete edge blocks surrounding the two trees in the middle of the patio area.
6. Remove and dispose of any existing edge retainers and all paver bedding sand. In areas designated, remove the existing aggregate base material. A portion of the existing base material should be retained to level any portions of the existing pavement that are not designated to have new aggregate base installed.
7. In designated areas, compact the existing subgrade, install geotextile fabric, place new aggregate base to a depth of 6 inches, and compact.
8. In areas not receiving new aggregate base, recompact the existing base using any removed base material to fill in areas that do not meet plan elevation tolerance requirements.
9. Install edge restraints on all pavement edges not abutting concrete curbs, stairs, or foundations. Place mortared edge paver course per approved pattern plans.

10. Place bedding sand, screed the sand, place pavers per the approved pattern plans, vibrate the pavers, and place joint sand.
11. After acceptance the Contractor shall restore all adjacent landscaping timbers and mulch, and return all mats and patio furnishings to designated locations. Contractor shall replace any adjacent bushes, shrubs, or turf damaged during construction.

1.2 DRAWINGS

- A. Drawings are included. Refer to Table Contents for drawing numbers.

1.3 SITE VISIT

- A. Bidders may inspect the site, investigate by observation, and Request Information via (RFI) and responses through the Contracting Office to satisfy their understanding of the work to be done, all general, local and technical conditions that may affect the cost and the feasibility of their proposal. In no event shall failure to inspect the site constitute grounds for a claim after award. Visitors planning to conduct a site visit shall contact the Cemetery Director or Foreman to make arrangements:

Cemetery POC(s):

Hampton National Cemetery (Station #849) - Janice M. Hill, Cemetery Director

(540) 825-0027

District Technical POC:

Timothy P. Sullivan, North Atlantic District (NAD) Engineer

(215) 381-3787 (ext. 4664)

1.4 SAFETY REQUIREMENTS

- A. Contractor foreman shall be onsite during all work activities and shall have completed OSHA 30-hour training. Prior to commencing work, general contractor shall provide proof that an OSHA certified "competent person" (CP) (29 CFR 1926.20(b)(2)) will maintain a presence at the work site whenever the general or subcontractors are present.

- B. Provide safeguards, including warning signs, barricades, temporary fences, warning lights, and other similar items that are required for protection of all personnel during demolition and removal operations.
- C. Fire and safety rules shall be observed in performance of work: Wherever a cutting torch or other equipment that might cause a fire is used, provide and maintain fire extinguishers nearby ready for immediate use. Instruct all possible users in use of fire extinguishers.

1.5 PERFORMANCE DETAILS

- A. Contractor shall complete all work within 60 calendar days after receipt of Notice to Proceed, subject to all terms, conditions, provisions and schedules of the contract. No cost time extension will be considered for cold weather delays as requested by the Contractor.
- B. Work Hours: Work may be performed between the normal hours of 8:00 a.m. and 4:30 p.m., Monday through Friday. At the Contractor's request; with prior coordination with the cemetery director and with the written permission of the COR; work will also be permitted to be scheduled for weekends and/or Holidays, only in the following situations: In emergency situations caused by the Contractor, or when severe adverse weather prohibits work during the week, the Contractor shall arrange to work on weekends and/or holidays in order to meet the contract performance period. The Government will not compensate the Contractor for any alternate work schedules needed to complete all contract work within the contract performance period. No work will be permitted during Memorial Day or Veteran's Day weekend activities or during any other Federal Holidays. No work will be performed at the immediate site of a scheduled interment or ceremony. Notwithstanding, if any work under this contract is required outside of the VA's normal working hours (8:00 a.m. to 4:30 p.m. Monday through Friday excluding holidays), the Contractor shall coordinate with the cemetery director and COR and request a deviation in writing to the COR at least 72 hours in advance.
- C. When working on a Government site, the Contractor shall coordinate with the COR on a daily basis, before start of work, the daily work schedule to ensure that no work is being performed at the immediate site of a

scheduled interment or ceremony. Burial activities at a National Cemetery shall take precedence over Contractor activities. Cemetery interment services cannot be disturbed. To cause the least possible interference with cemetery activities, the Contractor shall cease all work in areas where burials are taking place. Contractor equipment and personnel are prohibited from passing through the service area during this period.

D. The Contractor shall execute daily work in such a manner as to interfere as little as possible with work being done by others. Keep roads clear of materials, debris, equipment and vehicles at all times. Materials and equipment shall not be stored in other than assigned areas. At the end of each day the Contractor shall maintain all Contractor and Government property impacted by the Contractor's performance of work in a high standard of quality and cleanliness required for a national shrine.

E. Contractor personnel are subject to the cemetery rules of conduct. The Contractor is responsible for ensuring that no contract work causes any committal service, ceremony, procession or visitation to be delayed, altered, or otherwise impacted in such a way that the dignity, security, or safety of the event or visit is compromised.

F. Motor Vehicle Restrictions

1. Contractor and employees shall coordinate parking and access with the COR.

1.6 OPERATIONS AND STORAGE AREAS

A. The Contractor shall confine all operations (including storage of materials) on Government premises to areas authorized or approved by the Contracting Officer. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any nature occasioned by the Contractor's performance. Contractor shall coordinate all work and obtain and pay for any required permits necessary for completion of this project.

B. The Contractor shall, under regulations prescribed by the Contracting Officer, use only established roadways, or use temporary roadways constructed by the Contractor when and as authorized by the Contracting

Officer. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.

- C. Construction Fence shall be required only when required as noted on construction drawings. Before construction operations begin, Contractor shall provide a chain link construction fence, seven feet minimum height, around the construction area indicated on the drawings. Provide gates as required for access with necessary hardware, including hasps and padlocks. Fasten fence fabric to terminal posts with tension bands and to line posts and top and bottom rails with tie wires spaced at maximum 15 inches. Bottom of fences shall extend to one inch above grade. Remove the fence when directed by the COR.
- D. No utility service such as water, gas, steam, sewers or electricity, or fire protection systems and communications systems may be interrupted without prior approval of the COR. Electrical work shall be accomplished with all affected circuits or equipment de-energized. When an electrical outage cannot be accomplished, work on any energized circuits or equipment shall not commence without a detailed work plan, and the Cemetery Director's prior knowledge and written approval.
- E. Contractor shall submit a request to interrupt any such services to COR, in writing, 7 days in advance of proposed interruption. Request shall state reason, date, exact time of, and approximate duration of such interruption.
- F. Contractor will be advised (in writing) of approval of request, or of which other date and/or time such interruption will cause least inconvenience to operations of Cemetery. Interruption time approved by Cemetery may not occur at other than Contractor's normal working hours.
- G. Major interruptions of any system must be requested, in writing, at least 15 calendar days prior to the desired time and shall be performed as directed by the COR.

- H. Abandoned Lines: All service lines such as wires, cables, conduits, ducts, pipes and the like, and their hangers or supports, which are to be abandoned but are not required to be entirely removed, shall be sealed, capped or plugged at the main, branch or panel they originate from. The lines shall not be capped in finished areas, but shall be removed and sealed, capped or plugged in ceilings, within furred spaces, in unfinished areas, or within walls or partitions; so that they are completely behind the finished surfaces.
- I. Minimize interference of construction activities with flow of Cemetery traffic, comply with the following:
1. Keep roads, walks and entrances to grounds, to parking and to occupied areas of buildings clear of construction materials, debris and standing construction equipment and vehicles.
 2. Method and scheduling of required cutting, altering and removal of existing roads, walks and entrances must be coordinated and approved by the COR.
- J. Coordination of Construction with Cemetery Director: The burial activities at a National Cemetery shall take precedence over construction activities. The Contractor shall cooperate and coordinate with the Cemetery Director, through the COR, in arranging construction schedule to cause the least possible interference with cemetery activities in actual burial areas. Construction noise during the interment services shall not disturb the service. Trucks and workmen shall not pass through the service area during this period:
1. The Contractor is required to discontinue his work sufficiently in advance of Easter Sunday, Mother's Day, Father's Day, Memorial Day, Veteran's Day and/or Federal holidays, to permit him to clean up all areas of operation adjacent to existing burial plots before these dates.
 2. Cleaning up shall include the removal of all equipment, tools, materials and debris and leaving the areas in a clean, neat condition.
- K. The Contractor shall clean any Government property; including cemetery structures, headstones and monuments; that are soiled or stained

because of Contractor's performance. The Contractor shall wash-down with water all soiled or stained structures, headstones and monuments at the end of each workday. Any such cleaning or washing shall be brought to the immediate attention of the COR prior to cleaning or washing. No hazardous chemicals shall be used at any time on Government property.

- L. At the end of each day, the Contractor shall remove all debris from the cemetery site resulting from the performance of the work. The Contractor shall ensure at all times that rubbish and trash generated by the Contractor is kept clear of vehicular and pedestrian traffic throughout the site. The Government will not provide receptacle(s) for disposal of debris related to this contract. The Contractor will be permitted to place trash receptacle dumpsters in the COR approved staging area.

1.7 Contractor Personnel Standards of Behavior (Work on a Government Installation)

A. Dignity Clause:

1. Every action by contractor personnel at a national cemetery shall be performed with the special care, reverence, dignity, and respect that acknowledge the cemetery as the final resting place that commemorates the service and sacrifice that service members, Veterans and their families made for our Nation. Critically important is the awareness required of the Contractor employees of the remains buried in the grounds where the work is performed. The utmost care shall be given to these remains and the headstones and flat grave markers that mark those gravesites and memorialize the service of individuals.
2. Contractors shall not walk, stand, lean, sit or jump on headstones or markers. Nor shall they drive over them. Contractor personnel should use tools approved by the Contracting Officer Representative (COR), such as shovels,

pry bars or pinch bars to lift flat markers out of the ground; pick axes are not an acceptable tool.

B. Smoking is prohibited inside any buildings at the cemetery. Possession of weapons is prohibited from any cemetery buildings and grounds. Enclosed containers, including tool kits, shall be subject to search. Violations of VA regulations may result in citation answerable in the United States (Federal) District Court, not a local district, state, or municipal court

C. Contractor personnel are required to adhere to the following standards of dress, conduct, supervision and training while performing work on a Government Installation. Any violations shall be subject to immediate enforcement action by the Contracting Officer if these standards are not met. Contractor is responsible for training and safety precautions prescribed by OSHA regarding safety equipment and devices. Contractor personnel shall:

1. Be fully clothed at all times, to include upper garment to cover body from the waist to the neck and long pants or slacks. Garments, which have a message, slogan or printing of any kind other than the Contractor's business attire, are prohibited. Uniforms are acceptable.
2. Maintain a neat and professional appearance throughout its workforce, vehicles, equipment, and maintenance areas. Uniforms are acceptable. If uniforms are used, they must be in unison among all employees.
3. Not engage in loud or boisterous behavior, angry outbursts or use profane or abusive language at any time on Government premises. Playing radios and/or electronic games/devices shall only be done at lunchtime and in a designated break area. Due to the sensitive mission of the cemetery, Contractor

employees shall come into daily contact with grieving individuals, therefore Contractor employees shall exercise and exhibit absolute decorum, courtesy, and respect while within the cemetery or at its perimeter or entrances. Inquiries from cemetery visitors shall be politely referred to Government cemetery staff. Gratuities of any kind are strictly prohibited.

4. Consume food and beverage only within areas designated by the cemetery director (or his/her designated representative). Intoxication, and violence or criminal acts of any kind shall not be tolerated and is cause for immediate removal from a Government Installation. Use or sale of intoxicating beverages and/or drugs is strictly prohibited and use of tobacco products is only allowed in specific areas designated by the cemetery director (or his/her designated representative).
5. Only take breaks/rest periods, lunch breaks and bathrooms breaks in the Contractor Break Area, designated by the cemetery director (or his/her designated representative), not in the field. Misconduct shall form the basis for immediate contract enforcement action, to include immediate removal from the cemetery.
6. The Contractor shall ensure that his/her employees (including Contractor Consultants, Sub-Contractors, etc.) are aware of all the terms and conditions set forth in the contract regarding their performance and conduct.

1.8 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS

- A. The Contractor shall preserve and protect all structures, equipment, and vegetation (such as trees, shrubs, and grass) on or adjacent to the work site, which are not to be removed and which do not unreasonably interfere with the work required under this contract. The Contractor shall only remove trees when specifically authorized to do so, and shall avoid damaging vegetation that will remain in place. If any limbs or branches of trees are broken during contract performance, or by the careless operation of equipment, or by workmen, the Contractor shall trim those limbs or branches with a clean cut and paint the cut with a tree-pruning compound as directed by the Contracting Officer.
- B. The Contractor shall protect from damage all existing improvements and utilities at or near the work site and on adjacent property of a third party, the locations of which are made known to or should be known by the Contractor. The Contractor shall repair any damage to those facilities, including those that are the property of a third party, resulting from failure to comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

1.9 RESTORATION

- A. Remove, cut, alter, replace, patch and repair existing work as necessary to install new work. Except as otherwise shown or specified, do not cut, alter or remove any structural work, and do not disturb any ducts, plumbing, steam, gas, or electric work without approval of the COR. Existing work to be altered or extended and that is found to be defective in any way, shall be reported to the COR before it is disturbed. Materials and workmanship used in restoring work, shall conform in type and quality to that of original existing construction, except as otherwise shown or specified.
- B. Upon completion of contract, deliver work complete and undamaged. Existing work (walls, ceilings, partitions, floors, mechanical and electrical work, lawns, paving, roads, walks, etc.) disturbed or

removed as a result of performing required new work, shall be patched, repaired, reinstalled, or replaced with new work, and refinished and left in as good condition as existed before commencing work.

- C. At Contractor's own expense, Contractor shall immediately restore to service and repair any damage caused by Contractor's workmen to existing piping and conduits, wires, cables, etc., of utility services or of fire protection systems and communications systems (including telephone) which are not scheduled for discontinuance or abandonment.
- D. Expense of repairs to such utilities and systems not shown on drawings or locations of which are unknown will be covered by adjustment to contract time and price in accordance with clause entitled "CHANGES" (FAR 52.243-4 and VAAR 852.236-88) and "DIFFERING SITE CONDITIONS" (FAR 52.236-2).

1.10 LAYOUT OF WORK

- A. The Contractor shall lay out the work from Government established base lines and bench marks, indicated on the drawings, and shall be responsible for all measurements in connection with the layout. The Contractor shall furnish, at Contractor's own expense, all stakes, templates, platforms, equipment, tools, materials, and labor required to lay out any part of the work. The Contractor shall be responsible for executing the work to the lines and grades that may be established or indicated by the Contracting Officer. The Contractor shall also be responsible for maintaining and preserving all stakes and other marks established by the Contracting Officer until authorized to remove them. If such marks are destroyed by the Contractor or through Contractor's negligence before their removal is authorized, the Contracting Officer may replace them and deduct the expense of the replacement from any

1.11 TEMPORARY TOILETS

- A. When necessary, contractor shall provide temporary sanitary toilet accommodations. Coordinate location with Cemetery Director. Keep such places clean and free from flies. Failure to maintain satisfactory condition in toilets will deprive Contractor of the privilege to use such toilets.

1.12 AVAILABILITY AND USE OF UTILITY SERVICES

A. 120 outlets may be available and shall be coordinated with the COR for use if necessary.

B. Water for Construction: Furnish temporary water service.

1. Contractor may obtain water by connecting to the Cemetery water distribution system. Provide reduced pressure backflow preventer at each connection as per code. Water is available at no cost to the Contractor.

2. Maintain connections, pipe, fittings and fixtures and conserve water-use so none is wasted. Failure to stop leakage or other wastes will be cause for revocation at COR's discretion of use of water from Cemetery's system.

- - - E N D - - -

SECTION 01 33 23
SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES

- 1-1. Refer to Articles titled SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FAR 52.236-21) and, SPECIAL NOTES (VAAR 852.236-91), in GENERAL CONDITIONS.
- 1-2. For the purposes of this contract, samples including laboratory samples to be tested, test reports, certificates, and manufacturers' literature and data shall also be subject to the previously referenced requirements. The following text refers to all items collectively as SUBMITTALS.
- 1-3. Submit for approval, all of the items specifically mentioned under the separate sections of the specification, with information sufficient to evidence full compliance with contract requirements. Materials, fabricated articles and the like to be installed in permanent work shall equal those of approved submittals. After an item has been approved, no change in brand or make will be permitted unless:
 - A. Satisfactory written evidence is presented to, and approved by Contracting Officer, that manufacturer cannot make scheduled delivery of approved item or;
 - B. Item delivered has been rejected and substitution of a suitable item is an urgent necessity or;
 - C. Other conditions become apparent which indicates approval of such substitute item to be in best interest of the Government.
- 1-4. Forward submittals in sufficient time to permit proper consideration and approval action by Government. Time submission to assure adequate lead time for procurement of contract - required items. Delays attributable to untimely and rejected submittals including any laboratory samples to be tested will not serve as a basis for extending contract time for completion.
- 1-5. Submittals will be reviewed for compliance with contract requirements by the Contracting Officer's Representative.
- 1-6. The Government reserves the right to require additional submittals, whether or not particularly mentioned in this contract. If additional submittals beyond those required by the contract are furnished pursuant to request therefor by Contracting Officer, adjustment in contract

price and time will be made in accordance with Articles titled CHANGES (FAR 52.243-4) and CHANGES - SUPPLEMENT (VAAR 852.236-88) of the GENERAL CONDITIONS.

- 1-7. Schedules called for in specifications shall be submitted for use and information of Department of Veterans Affairs. However, the Contractor shall assume responsibility for coordinating and verifying schedules. The Contracting Officer assumes no responsibility for checking schedules or layout drawings for exact sizes, exact numbers and detailed positioning of items.
- 1-9. Submittals must be submitted by Contractor only and shipped prepaid. Contracting Officer assumes no responsibility for checking quantities or exact numbers included in such submittals.
 - A. Submit samples in single units unless otherwise specified. Submit shop drawings, schedules, manufacturers' literature and data, and certificates in duplicate, except where a greater number is specified.
 - B. Submittals will receive consideration only when covered by a transmittal letter signed by Contractor. Letter shall be sent via first class mail or e-mail in DF format; and shall contain the list of items, name of Cemetery, name of Contractor, contract number, applicable specification paragraph numbers, applicable drawing numbers (and other information required for exact identification of location for each item), manufacturer and brand, ASTM or Federal Specification Number (if any) and such additional information as may be required by specifications for particular item being furnished. In addition, catalogs shall be marked to indicate specific items submitted for approval.
 1. A copy of letter must be enclosed with items, and any items received without identification letter will be considered "unclaimed goods" and held for a limited time only.
 2. Each sample, certificate, manufacturers' literature and data shall be labeled to indicate the name and location of the Cemetery, name of Contractor, manufacturer, brand, contract number and ASTM or Federal Specification Number as applicable and location(s) on project.
 3. Required certificates shall be signed by an authorized representative of manufacturer or supplier of material, and by Contractor.

- C. In addition to complying with the applicable requirements specified in preceding Article 1.9, samples which are required to have Laboratory Tests (those preceded by symbol "LT" under the separate sections of the specification shall be tested, at the expense of Contractor, in a commercial laboratory approved by Contracting Officer.
1. Laboratory shall furnish Contracting Officer with a certificate stating that it is fully equipped and qualified to perform intended work, is fully acquainted with specification requirements and intended use of materials and is an independent establishment in no way connected with organization of Contractor or with manufacturer or supplier of materials to be tested.
 2. Certificates shall also set forth a list of comparable projects upon which laboratory has performed similar functions during past five years.
 3. Samples and laboratory tests shall be sent directly to approved commercial testing laboratory.
 4. Contractor shall send a copy of transmittal letter to the Contracting Officer's Representative with submission of material to a commercial testing laboratory.
 5. Laboratory test reports shall be sent directly to Contracting Officer's Representative for appropriate action.
 6. Laboratory reports shall list contract specification test requirements and a comparative list of the laboratory test results. When tests show that the material meets specification requirements, the laboratory shall so certify on test report.
 7. Laboratory test reports shall also include a recommendation for approval or disapproval of tested item.
- D. If submittal samples have been disapproved, resubmit new samples as soon as possible after notification of disapproval. Such new samples shall be marked "Resubmitted Sample" in addition to containing other previously specified information required on label and in transmittal letter.
- E. Approved samples will be kept on file by the Contracting Officer's Representative at the site until completion of contract, at which time such samples will be delivered to Contractor as Contractor's property. Where noted in technical sections of specifications, approved samples in good condition may be used in their proper locations in contract

work. At completion of contract, samples that are not approved will be returned to Contractor only upon request and at Contractor's expense. Such request should be made prior to completion of the contract. Disapproved samples that are not requested for return by Contractor will be discarded after completion of contract.

F. Submittal drawings (shop, erection or setting drawings) and schedules, required for work of various trades, shall be checked before submission by technically qualified employees of Contractor for accuracy, completeness and compliance with contract requirements. These drawings and schedules shall be stamped and signed by Contractor certifying to such check.

1. For each drawing required, submit one legible photographic paper or vellum reproducible.

2. Reproducible shall be full size.

3. Each drawing shall have marked thereon, proper descriptive title, including Cemetery location, project number, manufacturer's number, reference to contract drawing number, detail Section Number, and Specification Section Number.

4. A space 4-3/4 by 5 inches) shall be reserved on each drawing to accommodate approval or disapproval stamp.

5. Submit drawings, ROLLED WITHIN A MAILING TUBE, fully protected for shipment.

6. One reproducible print of approved or disapproved shop drawings will be forwarded to Contractor.

7. When work is directly related and involves more than one trade, shop drawings shall be submitted to Architect-Engineer under one cover.

1-10. Submittals shall be submitted for approval to the Contracting Officer's Representative.

- - - E N D - - -

SECTION 01 45 29
TESTING LABORATORY SERVICES

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section specifies materials testing activities and inspection services required during project construction to be provided by a Testing Laboratory retained and paid for by Contractor. Refer to Section 01 00 02, GENERAL REQUIREMENTS, for additional information.

1.2 RELATED DOCUMENTS

- A. Section 01 00 02, GENERAL REQUIREMENTS.

1.3 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to extent referenced. Publications are referenced in text by the basic designation only. Comply with applicable provisions and recommendations of the following, except as otherwise shown or specified.
- B. American Association of State Highway and Transportation Officials (AASHTO):
- | | |
|----------------|--|
| T27-11 | Sieve Analysis of Fine and Coarse Aggregates |
| T96-02(R2006) | Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine |
| T99-10 | The Moisture-Density Relations of Soils Using a 2.5 Kg (5.5 lb.) Rammer and a 305 mm (12 in.) Drop |
| T104-99(R2007) | Soundness of Aggregate by Use of Sodium Sulfate or Magnesium Sulfate |
| T180-10 | Moisture-Density Relations of Soils using a 4.54 kg (10 lb.) Rammer and a 457 mm (18 in.) Drop |
| T191-02(R2006) | Density of Soil In-Place by the Sand-Cone Method |
- C. American Society for Testing and Materials (ASTM):
- | | |
|----------|---|
| A325-10 | Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength |
| A370-12a | Definitions for Mechanical Testing of Steel Products |
| A490-12 | Heat Treated Steel Structural Bolts, 150 ksi Minimum Tensile Strength |

C31/C31M-12	Making and Curing Concrete Test Specimens in the Field
C33/C33M-13	Concrete Aggregates
C39/C39M-12	Compressive Strength of Cylindrical Concrete Specimens
C109/C109M-12	Compressive Strength of Hydraulic Cement Mortars
C138/C138M-12a	Unit Weight, Yield, and Air Content (Gravimetric) of Concrete
C140-13	Sampling and Testing Concrete Masonry Units and Related Units
C143/C143M-12	Slump of Hydraulic Cement Concrete
C172/C172M-10	Sampling Freshly Mixed Concrete
C173/C173M-12	Air Content of freshly Mixed Concrete by the Volumetric Method
C330/C330M-09	Lightweight Aggregates for Structural Concrete
C567/C567M-11	Density Structural Lightweight Concrete
C780-12a	Pre-construction and Construction Evaluation of Mortars for Plain and Reinforced Unit Masonry
C1019-11	Sampling and Testing Grout
C1064/C1064M-12	Freshly Mixed Hydraulic Cement Concrete
C1077-13	Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation
C1314-12	Compressive Strength of Masonry Prisms
C1364-10b	Architectural Cast Stone
D698-12	Laboratory Compaction Characteristics of Soil Using Standard Effort
D1143/D1143M-07	Deep Foundations Under Static Axial Compressive Load
D1188-07	Bulk Specific Gravity and Density of Compacted Bituminous Mixtures Using Paraffin-Coated Specimens
D1556-07	Density and Unit Weight of Soil in Place by the Sand-Cone Method
D1557-12	Laboratory Compaction Characteristics of Soil Using Modified Effort

D2166-06	Unconfined Compressive Strength of Cohesive Soil
D2167-08	Density and Unit Weight of Soil in Place by the Rubber Balloon Method
D2216-10	Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
D2974-07	Moisture, Ash, and Organic Matter of Peat and Other Organic Soils
D3666-11	Minimum Requirements for Agencies Testing and Inspection Bituminous Paving Materials
D3740-12a	Minimum Requirements for Agencies Engaged in Testing and/or Inspection of Soil and Rock
E94-04(2010)	Radiographic Examination
E164-08	Contact Ultrasonic Testing of Weldments
E329-11c	Agencies Engaged in Construction Inspection, Testing, or Special Inspection
E543-13	Agencies Performing Nondestructive Testing
E709-08	Guide for Magnetic Particle Testing
E1155-96(2008)	Determining FF Floor Flatness and FL Floor Levelness Numbers

D. American Welding Society (AWS):

D1.1-07	Structural Welding Code-Steel
---------	-------------------------------

1.4 REQUIREMENTS

A. Accreditation Requirements: Testing Laboratory retained and paid for by Contractor must be accredited by one or more of the National Voluntary Laboratory Accreditation Program (NVLAP) programs acceptable in the geographic region for the project. Submit for approval to the RE/COR a copy of the Certificate of Accreditation and Scope of Accreditation. For testing laboratories that have not yet obtained accreditation by a NVLAP program, submit an acknowledgement letter from one of the laboratory accreditation authorities indicating that the application for accreditation has been received and the accreditation process has started, and submit to the RE/COR for approval, certified statements, signed by an official of the testing laboratory attesting that the proposed laboratory, meets or conforms to the ASTM standards listed below as appropriate to the testing field.

1. Laboratories engaged in testing of construction materials must meet the requirements of ASTM E329.

2. Laboratories engaged in testing of concrete and concrete aggregates must meet the requirements of ASTM C1077.
 3. Laboratories engaged in testing of bituminous paving materials must meet the requirements of ASTM D3666.
 4. Laboratories engaged in testing of soil and rock, as used in engineering design and construction, must meet the requirements of ASTM D3740.
 5. Laboratories engaged in inspection and testing of steel, stainless steel, and related alloys will be evaluated according to ASTM A880.
 6. Laboratories engaged in non-destructive testing (NDT) must meet the requirements of ASTM E543.
 7. Laboratories engaged in Hazardous Materials Testing must meet the requirements of OSHA and EPA.
- B. Inspection and Testing: Testing laboratory to inspect materials and workmanship and perform tests described herein and additional tests requested by RE/COR. When it appears materials furnished, or work performed by Contractor fail to meet construction contract requirements, Testing Laboratory must direct attention of RE/COR to such failure.
- C. Written Reports: Testing laboratory to submit test reports to RE/COR, Contractor within 24 hours after each test is completed unless other arrangements are agreed to in writing by the RE/COR. Submit reports of tests that fail to meet construction contract requirements on colored paper. Reports shall include photographs showing the items inspected such as but not limited to reinforcing steel or earthwork compaction.
- D. Verbal Reports: Give verbal notification to RE/COR immediately of any irregularity.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 EARTHWORK

- A. General: The Testing Laboratory is to provide qualified personnel, materials, equipment, and transportation as required to perform the services identified/required herein, within the agreed to schedule and/or time frame. The work to be performed is as identified herein including, but not be limited to, the following:
1. Observe fill and subgrades during proof-rolling to evaluate suitability of surface material to receive fill or base course. Provide recommendations to the RE/COR regarding suitability or

- unsuitability of areas where proof-rolling was observed. Where unsuitable results are observed, witness excavation of unsuitable material and recommend to RE/COR extent of removal and replacement of unsuitable materials and observe proof-rolling of replaced areas until satisfactory results are obtained.
2. Provide full time observation of fill placement and compaction and field density testing in building areas and provide full time observation of fill placement and compaction and field density testing in pavement areas to verify that earthwork compaction obtained is in accordance with contract documents.
 3. Provide supervised geotechnical technician to inspect excavation, subsurface preparation, and backfill for structural fill.
- B. Testing Compaction:
1. Determine maximum density and optimum moisture content for each type of fill, backfill and subgrade material used, in compliance with one of the following standards: // AASHTO // T99/T180 // Method A // // ASTM // D698 // D1557 // Method A // ASTM D698 and/or ASTM D1557.
 2. Make field density tests in accordance with the primary testing method following either ASTM D2922 or AASHTO T238. Field density tests utilizing one of ASTM D1556, AASHTO T191, or ASTM D2167. Should the testing laboratory propose these alternative methods, they must provide satisfactory explanation to the RE/COR before the tests are conducted.
 - a. Building Slab Subgrade: At least one test of subgrade for every 185 m² (2000 square feet) of building slab, but in no case fewer than three tests. In each compacted fill layer, perform one test for every 185 m² (2000 square feet) of overlaying building slab, but in no case fewer than three tests.
 - b. Foundation Wall Backfill: One test per 30 m (100 feet) of each layer of compacted fill but in no case fewer than two tests.
 - c. Pavement Subgrade: One test for each 335 m² (400 square yards), but in no case fewer than two tests.
 - d. Curb, Gutter, and Sidewalk: One test for each 90 m (300 feet), but in no case fewer than two tests.
 - e. Trenches: One test at maximum 30 m (100 foot) intervals per 1200 mm (4 foot) of vertical lift and at changes in required density, but in no case fewer than two tests.

- f. Footing Subgrade: At least one test for each layer of soil on which footings will be placed. Subsequent verification and approval of each footing subgrade may be based on a visual comparison of each subgrade with related tested subgrade when acceptable to RE/COR. In each compacted fill layer below wall footings, perform one field density test for every 30 m (100 feet) of wall. Verify subgrade is level, all loose or disturbed soils have been removed, and correlate actual soil conditions observed with those indicated by test borings.
- C. Testing for Footing Bearing Capacity: Evaluate if suitable bearing capacity material is encountered in footing subgrade.
- D. Testing Materials: Test suitability of on-site and off-site borrow as directed by RE/COR.

3.2 FOUNDATION PILES [NOT USED]

3.3 LANDSCAPING

- A. Test topsoil for organic materials, pH, phosphate, potash content, and gradation of particles.
 - 1. Test for organic material by using ASTM D2974.
 - 2. Determine percent of silt, sand, clay, and foreign materials such as rock, roots, and vegetation.
 - 3. Test for moisture absorption capacity.
- B. Submit laboratory test report of topsoil to RE/COR.
- C. Submit recommendations for soil amendments, from a regional soil conservation service or cooperative extension, to bring soil into compliance with minimum parameters in these specifications.

3.4 ASPHALT CONCRETE PAVING

- A. Aggregate Base Course:
 - 1. Determine maximum density and optimum moisture content for aggregate base material in accordance with one of the following: // AASHTO T180, Method D // ASTM D1557, Method D //.
 - 2. Make a minimum of three field density tests on each day's final compaction on each aggregate course in accordance with either AASHTO T191 or ASTM D1556.
 - 3. Sample and test aggregate as necessary to insure compliance with specification requirements for gradation, wear, and soundness as specified in the applicable state highway standards and specifications.
- B. Asphalt Concrete:

1. Aggregate: Sample and test aggregates in stock pile and hot-bins as necessary to insure compliance with specification requirements for gradation (AASHTO T27), wear (AASHTO T96), and soundness (AASHTO T104).
2. Temperature: Check temperature of each load of asphalt concrete at mixing plant and at site of paving operation.
3. Density: Make a minimum of two field density tests in accordance with ASTM D1188 of asphalt base and surface course for each day's paving operation.

3.5 SITE WORK CONCRETE

- A. Test site work concrete including materials for concrete as required in Article CONCRETE of this section.

3.6 CONCRETE

- A. Batch Plant Inspection and Materials Testing:
 1. Perform continuous batch plant inspection until concrete quality is established to satisfaction of RE/COR with concurrence of Contracting Officer and perform periodic inspections thereafter as determined by RE/COR.
 2. Periodically inspect and test batch proportioning equipment for accuracy and report deficiencies to RE/COR.
 3. Sample and test mix ingredients as necessary to insure compliance with specifications.
 4. Sample and test aggregates daily and as necessary for moisture content. Test the dry rodded weight of the coarse aggregate whenever a sieve analysis is made, and when it appears there has been a change in the aggregate.
 5. Certify, in duplicate, ingredients and proportions and amounts of ingredients in concrete conform to approved trial mixes. When concrete is batched or mixed off immediate building site, certify (by signing, initialing or stamping thereon) on delivery slips (duplicate) that ingredients in truck-load mixes conform to proportions of aggregate weight, cement factor, and water-cement ratio of approved trial mixes.
- B. Field Inspection and Materials Testing:
 1. Provide a technician at site of placement at all times to perform concrete sampling and testing.
 2. Review the delivery tickets of the ready-mix concrete trucks arriving on-site. Notify the Contractor if the concrete cannot be

- placed within the specified time limits or if the type of concrete delivered is incorrect. Reject any loads that do not comply with the Specification requirements. Rejected loads are to be removed from the site at the Contractor's expense. Any rejected concrete that is placed will be subject to removal.
3. Take concrete samples at point of placement in accordance with ASTM C172. Mold and cure compression test cylinders in accordance with ASTM C31. Make at least three cylinders for each 40 m³ (50 cubic yards) or less of each concrete type, and at least three cylinders for any one day's pour for each concrete type. Label each cylinder with an identification number. RE/COR may require additional cylinders to be molded and cured under job conditions.
 4. Perform slump tests in accordance with ASTM C143. Test the first truck each day, and every time test cylinders are made. Test pumped concrete at the hopper and at the discharge end of the hose at the beginning of each day's pumping operations to determine change in slump.
 5. Determine the air content of concrete per ASTM C173. For concrete required to be air-entrained, test the first truck and every 20 m³ (25 cubic yards) thereafter each day. For concrete not required to be air-entrained, test every 80 m³ (100 cubic yards) at random. For pumped concrete, initially test concrete at both the hopper and the discharge end of the hose to determine change in air content.
 6. If slump or air content fall outside specified limits, make another test immediately from another portion of same batch.
 7. Perform unit weight tests in compliance with ASTM C138 for normal weight concrete and ASTM C567 for lightweight concrete. Test the first truck and eachtime cylinders are made.
 8. Notify laboratory technician at batch plant of mix irregularities and request materials and proportioning check.
 9. Verify that specified mixing has been accomplished.
 10. Environmental Conditions: Determine the temperature per ASTM C1064 for each truckload of concrete during hot weather and cold weather concreting operations:
 - a. When ambient air temperature falls below 4.4 degrees C (40 degrees F), record maximum and minimum air temperatures in each 24 hour period; record air temperature inside protective

- enclosure; record minimum temperature of surface of hardened concrete.
- b. When ambient air temperature rises above 29.4 degrees C (85 degrees F), record maximum and minimum air temperature in each 24 hour period; record minimum relative humidity; record maximum wind velocity; record maximum temperature of surface of hardened concrete.
11. Inspect the reinforcing steel placement, including bar size, bar spacing, top and bottom concrete cover, proper tie into the chairs, and grade of steel prior to concrete placement. Submit detailed report of observations.
12. Observe conveying, placement, and consolidation of concrete for conformance to specifications.
13. Observe condition of formed surfaces upon removal of formwork prior to repair of surface defects and observe repair of surface defects.
14. Observe curing procedures for conformance with specifications, record dates of concrete placement, start of preliminary curing, start of final curing, end of curing period.
15. Observe preparations for placement of concrete:
- a. Inspect handling, conveying, and placing equipment, inspect vibrating and compaction equipment.
 - b. Inspect preparation of construction, expansion, and isolation joints.
16. Observe preparations for protection from hot weather, cold weather, sun, and rain, and preparations for curing.
17. Observe concrete mixing:
- a. Monitor and record amount of water added at project site.
 - b. Observe minimum and maximum mixing times.
18. Measure concrete flatwork for levelness and flatness as follows:
- a. Perform Floor Tolerance Measurements F_F and F_L in accordance with ASTM E1155. Calculate the actual overall F- numbers using the inferior/superior area method.
 - b. Perform all floor tolerance measurements within 48 hours after slab installation and prior to removal of shoring and formwork.
 - c. Provide the Contractor and the RE/COR with the results of all profile tests, including a running tabulation of the overall F_F and F_L values for all slabs installed to date, within 72 hours after each slab installation.

19. Other inspections:

- a. Grouting under base plates.
- b. Grouting anchor bolts and reinforcing steel in hardened concrete.

C. Laboratory Tests of Field Samples:

1. Test compression test cylinders for strength in accordance with ASTM C39. For each test series, test one cylinder at 7 days and one cylinder at 28 days. Use remaining cylinder as a spare tested as directed by RE/COR. Compile laboratory test reports as follows: Compressive strength test to be the result of one cylinder, except when one cylinder shows evidence of improper sampling, molding or testing, in which case it must be discarded and strength of spare cylinder to be used.
2. Make weight tests of hardened lightweight structural concrete in accordance with ASTM C567.
3. Furnish certified compression test reports (duplicate) to RE/COR. In test report, indicate the following information:
 - a. Cylinder identification number and date cast.
 - b. Specific location at which test samples were taken.
 - c. Type of concrete, slump, and percent air.
 - d. Compressive strength of concrete in MPa (psi).
 - e. Weight of lightweight structural concrete in kg/m³ (pounds per cubic feet).
 - f. Weather conditions during placing.
 - g. Temperature of concrete in each test cylinder when test cylinder was molded.
 - h. Maximum and minimum ambient temperature during placing.
 - i. Ambient temperature when concrete sample in test cylinder was taken.
 - j. Date delivered to laboratory and date tested.

3.7 REINFORCEMENT

- A. Review mill test reports furnished by Contractor.
- B. Make one tensile and one bend test in accordance with ASTM A370 from each pair of samples obtained.
- C. Written report must include, in addition to test results, heat number, manufacturer, type and grade of steel, and bar size.
- D. Perform tension tests of mechanical and welded splices in accordance with ASTM A370.

3.8 PRESTRESSED CONCRETE

- A. Inspection at Plant: Forms, placement and concrete cover of reinforcing steel and tendons, placement and finishing of concrete, and tensioning of tendons.
- B. Concrete Testing: Test concrete including materials for concrete required in Article, CONCRETE of this section, except make two test cylinders for each day's production of each strength of concrete produced.
- C. Test tendons for conformance with ASTM A416 and furnish report to RE/COR.
- D. Inspect members to insure that specification requirements for curing and finishes have been met.

3.9 ARCHITECTURAL CAST STONE

- A. Perform testing according to ASTM C1364 or verify compliance by reviewing previous test results of same product.
- B. Inspect the plant to verify that specification requirements for curing and finishes have been met.

3.10 MASONRY

- A. Mortar Tests:
 - 1. Laboratory compressive strength test:
 - a. Comply with ASTM C780.
 - b. Obtain samples during or immediately after discharge from batch mixer.
 - c. Furnish molds with 50 mm (2 inch), 3 compartment gang cube.
 - d. Test one sample at 7 days and 2 samples at 28 days.
 - 2. Two tests during first week of operation; one test per week after initial test until masonry completion.
- B. Grout Tests:
 - 1. Laboratory compressive strength test:
 - a. Comply with ASTM C1019.
 - b. Test one sample at 7 days and 2 samples at 28 days.
 - c. Perform test for each 230 m² (2500 square feet) of masonry.
- C. Masonry Unit Tests:
 - 1. Laboratory Compressive Strength Test:
 - a. Comply with ASTM C140.
 - b. Test 3 samples for each 460 m² (5000 square feet) of wall area.
- D. Prism Tests: For each type of wall construction indicated, test masonry prisms per ASTM C1314 for each 460 m² (5000 square feet) of wall area.

Prepare one set of prisms for testing at 7 days and one set for testing at 28 days.

E. Field Inspection and Materials Testing:

1. Verify the following prior to grouting:

- a. Grout space is clean.
- b. Type, spacing, and placement of reinforcement, connectors, and anchors comply with the contract requirements.

3.11 STRUCTURAL STEEL [NOT USED]

3.12 STEEL DECKING [NOT USED]

3.13 SHEAR CONNECTOR STUDS [NOT USED]

- - - E N D - - -

SECTION 01 74 19
CONSTRUCTION WASTE MANAGEMENT

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section specifies the requirements for the management of non-hazardous building construction and demolition waste.
- B. Waste disposal in landfills shall be minimized to the greatest extent possible. Of the inevitable waste that is generated, as much of the waste material as economically feasible shall be salvaged, recycled or reused.
- C. Contractor shall use all reasonable means to divert construction and demolition waste from landfills and incinerators, and facilitate their salvage and recycle not limited to the following:
 - 1. Waste Management Plan development and implementation.
 - 2. Techniques to minimize waste generation.
 - 3. Sorting and separating of waste materials.
 - 4. Salvage of existing materials and items for reuse or resale.
 - 5. Recycling of materials that cannot be reused or sold.
- D. At a minimum the following waste categories shall be diverted from landfills:
 - 1. Soil.
 - 2. Inerts (eg, concrete, masonry and asphalt).
 - 3. Clean dimensional wood and palette wood.
 - 4. Green waste (biodegradable landscaping materials).
 - 5. Engineered wood products (plywood, particle board and I-joists, etc).
 - 6. Metal products (eg, steel, wire, beverage containers, copper, etc).
 - 7. Cardboard, paper and packaging.
 - 8. Bitumen roofing materials.
 - 9. Plastics (eg, ABS, PVC).
 - 10. Carpet and/or pad.
 - 11. Gypsum board.
 - 12. Insulation.
 - 13. Paint.
 - 14. Fluorescent lamps.

1.3 QUALITY ASSURANCE

- A. Contractor shall practice efficient waste management when sizing, cutting and installing building products. Processes shall be employed

to ensure the generation of as little waste as possible. Construction /Demolition waste includes products of the following:

1. Excess or unusable construction materials.
 2. Packaging used for construction products.
 3. Poor planning and/or layout.
 4. Construction error.
 5. Over ordering.
 6. Weather damage.
 7. Contamination.
 8. Mishandling.
 9. Breakage.
- B. Establish and maintain the management of non-hazardous building construction and demolition waste set forth herein. Conduct a site assessment to estimate the types of materials that will be generated by demolition and construction.
- C. Contractor shall develop and implement procedures to recycle construction and demolition waste to a minimum of 50 percent.
- D. Contractor shall be responsible for implementation of any special programs involving rebates or similar incentives related to recycling. Any revenues or savings obtained from salvage or recycling shall accrue to the contractor.
- E. Contractor shall provide all demolition, removal and legal disposal of materials. Contractor shall ensure that facilities used for recycling, reuse and disposal shall be permitted for the intended use to the extent required by local, state, federal regulations. The Whole Building Design Guide website <http://www.wbdg.org/tools/cwm.php> provides a Construction Waste Management Database that contains information on companies that haul, collect, and process recyclable debris from construction projects.
- F. Contractor shall assign a specific area to facilitate separation of materials for reuse, salvage, recycling, and return. Such areas are to be kept neat and clean and clearly marked in order to avoid contamination or mixing of materials.
- G. Contractor shall provide on-site instructions and supervision of separation, handling, salvaging, recycling, reuse and return methods to be used by all parties during waste generating stages.
- H. Record on daily reports any problems in complying with laws, regulations and ordinances with corrective action taken.

1.4 TERMINOLOGY

- A. Class III Landfill: A landfill that accepts non-hazardous resources such as household, commercial and industrial waste resulting from construction, remodeling, repair and demolition operations.
- B. Clean: Untreated and unpainted; uncontaminated with adhesives, oils, solvents, mastics and like products.
- C. Construction and Demolition Waste: Includes all non-hazardous resources resulting from construction, remodeling, alterations, repair and demolition operations.
- D. Dismantle: The process of parting out a building in such a way as to preserve the usefulness of its materials and components.
- E. Disposal: Acceptance of solid wastes at a legally operating facility for the purpose of land filling (includes Class III landfills and inert fills).
- F. Inert Backfill Site: A location, other than inert fill or other disposal facility, to which inert materials are taken for the purpose of filling an excavation, shoring or other soil engineering operation.
- G. Inert Fill: A facility that can legally accept inert waste, such as asphalt and concrete exclusively for the purpose of disposal.
- H. Inert Solids/Inert Waste: Non-liquid solid resources including, but not limited to, soil and concrete that does not contain hazardous waste or soluble pollutants at concentrations in excess of water-quality objectives established by a regional water board, and does not contain significant quantities of decomposable solid resources.
- I. Mixed Debris: Loads that include commingled recyclable and non-recyclable materials generated at the construction site.
- J. Mixed Debris Recycling Facility: A solid resource processing facility that accepts loads of mixed construction and demolition debris for the purpose of recovering re-usable and recyclable materials and disposing non-recyclable materials.
- K. Permitted Waste Hauler: A company that holds a valid permit to collect and transport solid wastes from individuals or businesses for the purpose of recycling or disposal.
- L. Recycling: The process of sorting, cleansing, treating, and reconstituting materials for the purpose of using the altered form in the manufacture of a new product. Recycling does not include burning, incinerating or thermally destroying solid waste.

1. On-site Recycling - Materials that are sorted and processed on site for use in an altered state in the work, i.e. concrete crushed for use as a sub-base in paving.
 2. Off-site Recycling - Materials hauled to a location and used in an altered form in the manufacture of new products.
- M. Recycling Facility: An operation that can legally accept materials for the purpose of processing the materials into an altered form for the manufacture of new products. Depending on the types of materials accepted and operating procedures, a recycling facility may or may not be required to have a solid waste facilities permit or be regulated by the local enforcement agency.
- N. Reuse: Materials that are recovered for use in the same form, on-site or off-site.
- O. Return: To give back reusable items or unused products to vendors for credit.
- P. Salvage: To remove waste materials from the site for resale or re-use by a third party.
- Q. Source-Separated Materials: Materials that are sorted by type at the site for the purpose of reuse and recycling.
- R. Solid Waste: Materials that have been designated as non-recyclable and are discarded for the purposes of disposal.
- S. Transfer Station: A facility that can legally accept solid waste for the purpose of temporarily storing the materials for re-loading onto other trucks and transporting them to a landfill for disposal, or recovering some materials for re-use or recycling.

1.5 SUBMITTALS

- A. Prior to final invoice, location of facility where concrete materials were taken for recycling; along with weight tickets indicating amount of material recycled.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. List of each material and quantity to be salvaged, recycled, reused.
- B. List of each material and quantity proposed to be taken to a landfill.
- C. Material tracking data: Receiving parties, dates removed, transportation costs, weight tickets, tipping fees, manifests, invoices, net total costs or savings.

PART 3 - EXECUTION

3.1 COLLECTION

- A. Provide all necessary containers, bins and storage areas to facilitate effective waste management.
- B. Clearly identify containers, bins and storage areas so that recyclable materials are separated from trash and can be transported to respective recycling facility for processing.
- C. Hazardous wastes shall be separated, stored, disposed of according to local, state, federal regulations.

3.2 DISPOSAL

- A. Contractor shall be responsible for transporting and disposing of materials that cannot be delivered to a source-separated or mixed materials recycling facility to a transfer station or disposal facility that can accept the materials in accordance with state and federal regulations.
- B. Construction or demolition materials with no practical reuse or that cannot be salvaged or recycled shall be disposed of at a landfill or incinerator.

3.3 REPORT

- A. With each application for progress payment, submit a summary of construction and demolition debris diversion and disposal including beginning and ending dates of period covered.
- B. Quantify all materials diverted from landfill disposal through salvage or recycling during the period with the receiving parties, dates removed, transportation costs, weight tickets, manifests, invoices. Include the net total costs or savings for each salvaged or recycled material.
- C. Quantify all materials disposed of during the period with the receiving parties, dates removed, transportation costs, weight tickets, tipping fees, manifests, invoices. Include the net total costs for each disposal.

- - - E N D - - -

**SECTION 02 41 10
DEMOLITION AND SITE CLEARING**

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section specifies all site preparation work, demolition and removal of buildings, portions of buildings, utilities, other structures and debris from trash dumps shown.

1.2 RELATED WORK

- B. Safety Requirements: GENERAL CONDITIONS Article, ACCIDENT PREVENTION.
- C. Disconnecting utility services prior to demolition: Section 01 00 02, GENERAL REQUIREMENTS.
- D. Reserved items that are to remain the property of the Government: Section 01 00 02, GENERAL REQUIREMENTS.

1.3 PROTECTION

- A. Perform demolition in such manner as to eliminate hazards to persons and property; to minimize interference with use of adjacent areas, utilities and structures or interruption of use of such utilities; and to provide free passage to and from such adjacent areas of structures. Comply with requirements of GENERAL CONDITIONS Article, ACCIDENT PREVENTION.
- B. Provide safeguards, including warning signs, barricades, temporary fences, warning lights, and other similar items that are required for protection of all personnel during demolition and removal operations. Comply with requirements of Section 01 00 02, GENERAL REQUIREMENTS.
- C. Maintain fences, barricades, lights, and other similar items around exposed excavations until such excavations have been completely filled.
- D. Provide enclosed dust chutes with control gates from each floor to carry debris to truck beds and govern flow of material into truck. Provide overhead bridges of tight board or prefabricated metal construction at dust chutes to protect persons and property from falling debris.
- E. Prevent spread of flying particles and dust. Sprinkle rubbish and debris with water to keep dust to a minimum. Do not use water if it results in hazardous or objectionable condition such as, but not limited to; ice, flooding, or pollution. Vacuum and dust the work area daily.
- F. In addition to previously listed fire and safety rules to be observed in performance of work, include following:

1. No wall or part of wall shall be permitted to fall outwardly from structures.
 2. Maintain at least one stairway in each structure in usable condition to highest remaining floor. Keep stairway free of obstructions and debris until that level of structure has been removed.
 3. Wherever a cutting torch or other equipment that might cause a fire is used, provide and maintain fire extinguishers nearby ready for immediate use. Instruct all possible users in use of fire extinguishers.
 4. Keep hydrants clear and accessible at all times. Prohibit debris from accumulating within a radius of 4500 mm (15 feet) of fire hydrants.
- G. Before beginning any demolition work, survey the site and examine the drawings and specifications to determine the extent of the work. Take necessary precautions to avoid damages to existing items to remain in place, to be reused, or to remain the property of the Cemetery; any damaged items shall be repaired or replaced as approved by the Resident Engineer/Contracting Officer's Representative (RE/COR). Coordinate the work of this section with all other work and shall construct and maintain shoring, bracing, and supports as required. Ensure that structural elements are not overloaded and shall be responsible for increasing structural supports or adding new supports as may be required as a result of any cutting, removal, or demolition work performed under this contract. Do not overload structural elements. Provide new supports and reinforcement for existing construction weakened by demolition or removal works. Repairs, reinforcement, or structural replacement must have RE/COR's approval.

1.4 UTILITY SERVICES

- A. Demolish and remove outside utility service lines shown to be removed.
- B. Remove abandoned outside utility lines that would interfere with installation of new utility lines and new construction.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 SITE CLEARING

- A. General: Remove trees, shrubs, grass, and other vegetation, pavements, improvements, or obstructions, as required, to permit installation of new construction. Remove similar items elsewhere on site or premises

as specifically indicated. Removal includes digging out and off-site disposal of stumps and roots.

1. For the purposes of the tree stump removal, the stump shall include a conical volume of lateral roots, heart roots, and root mass extending in a horizontal radius as measured at a point 6 inches above the ground and vertically downward from the same point. The horizontal radius shall be calculated at 6 inches for each inch of tree diameter. The downward vertical distance at 12 inches for the first inch of diameter and an additional 6 inches for each inch of diameter thereafter with a maximum depth of 2 1/2 feet.
 2. All lateral roots with a diameter less than 1 inch shall be removed to a depth of 6 inches below the planned subgrade elevation and all roots larger than 1 inch to a depth of 12 inches below the planned subgrade elevation.
- B. Erosion Control: Provide erosion control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways. Install silt fence and inlet protection as shown and as per requirements of the SWPPP, prior to any soil disturbance activities. Provide temporary seeding as required by the SWPPP.
- C. Maintain site controls in accordance with Storm Water Pollution Prevention Plan and repair as directed by COTR to sustain compliance with SPDES permit. Maintain all records as required by the SWPPP. Perform inspections as required by the SWPPP.
- D. Topsoil - On-site: Topsoil is defined as friable clay loam surface soil found in a depth of not less than 150 mm (6 inches). Satisfactory topsoil is reasonably free and/or screened of subsoil, clay lumps, stones, and other objects over 25 mm (1 inch) in diameter, and without weeds, roots, and other objectionable material.
1. Strip topsoil to whatever depths encountered in a manner to prevent intermingling with underlying subsoil or other objectionable material. Remove heavy growths of grass from areas before stripping.
 - a. Where existing trees are indicated to remain, leave existing topsoil in place within drip lines to prevent damage to root system.
 2. Stockpile topsoil in storage piles in areas indicated or directed. Construct storage piles to provide free drainage of surface water.

- Cover storage piles to prevent wind erosion in accordance with the Storm Water Pollution Prevention Plan. Refer to Division 2 Section 32 90 00, "Planting" for soil amendments required prior to spreading topsoil.
- a. Stockpile shall be contained with erosion and sediment controls (silt fence) and stabilized if undisturbed in accordance with the Storm Water Pollution Prevention Plan.
- 3. Dispose of unsuitable or excess topsoil as specified for disposal of waste material only after approval of the Architect.
- E. Clearing and Grubbing: Clear site of trees, shrubs, and other vegetation, except for those indicated to be left standing.
- 1. Completely remove stumps, roots, and other debris protruding through ground surface.
 - 2. Use only hand methods for grubbing inside drip line of trees indicated to remain.
 - 3. Fill depressions caused by clearing and grubbing operations with satisfactory soil material, unless further excavation or earthwork is indicated.
 - a. Place fill material in horizontal layers not exceeding 150 mm (6 inches) loose depth, and thoroughly compact each layer to a density equal to adjacent original ground.
- F. Removal of Improvements: Remove existing above-grade and below-grade improvements as indicated and as necessary to facilitate new construction.
- G. Abandonment or removal of certain underground pipe or conduits may be indicated on mechanical or electrical drawings and is included under work of related Division 15 and 16 Sections. Removing abandoned underground piping or conduits interfering with construction is included under this Section, except as indicated to be abandoned in-place.
- H. Continue maintenance of erosion controls in compliance with the Storm Water Pollution Prevention Plan until the work is completed and the threat of erosion is gone by either around surface stabilizer or lawn "grow-in" is at 85% complete. Temporary erosion control devices shall not be removed until the area is certified as being stabilized by the Qualified Inspector.

3.2 DEMOLITION

- A. Completely demolish and remove buildings and structures, including all appurtenances related or connected thereto, as noted below:
 - 1. As required for installation of new utility service lines.
 - 2. To full depth within an area defined by hypothetical lines located 1500 mm (5 feet) outside building lines of new structures.
- B. Debris, including brick, concrete, stone, metals and similar materials shall become property of Contractor and shall be disposed of by him daily, off the Cemetery Property to avoid accumulation at the demolition site. Materials that cannot be removed daily shall be stored in areas specified by the RE/COR. Break up concrete slabs below grade that do not require removal from present location into pieces not exceeding 600 mm (24 inches) square to permit drainage. Contractor shall dispose debris in compliance with applicable federal, state or local permits, rules and/or regulations.
- C. In removing buildings and structures of more than two stories, demolish work story by story starting at highest level and progressing down to third floor level. Demolition of first and second stories may proceed simultaneously.
- D. Remove and legally dispose of all materials, other than earth to remain as part of project work, from any trash dumps shown. Materials removed shall become property of contractor and shall be disposed of in compliance with applicable federal, state or local permits, rules and/or regulations. All materials in the indicated trash dump areas, including above surrounding grade and extending to a depth of 1500 mm (5 feet) below surrounding grade, shall be included as part of the lump sum compensation for the work of this section. Materials that are located beneath the surface of the surrounding ground more than 1500 mm (5 feet), or materials that are discovered to be hazardous, shall be handled as unforeseen. The removal of hazardous material shall be referred to Hazardous Materials specifications. Burning is not permitted on the property.
- E. Remove existing utilities as indicated or uncovered by work and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the RE/COR. When Utility lines are encountered that are not indicated on the drawings, the RE/COR shall be notified prior to further work in that area.

3.2 CLEAN-UP

- A. On completion of work of this section and after removal of all debris, leave site in clean condition satisfactory to RE/COR. Clean-up shall include off the Cemetery Property disposal of all items and materials not required to remain property of the Government as well as all debris and rubbish resulting from demolition operations.

- - - E N D - - -

**SECTION 31 20 11
EARTH MOVING (SHORT FORM)**

PART 1 - GENERAL

1.1 DESCRIPTION

This section specifies the requirements for furnishing all equipment, materials, labor and techniques for earthwork including excavation, fill, backfill and site restoration utilizing fertilizer, seed and/or sod.

1.2 DEFINITIONS

A. Unsuitable Materials:

1. Fills: Topsoil, frozen materials; construction materials and materials subject to decomposition; clods of clay and stones larger than 75 mm (3 inches); organic materials, including silts, which are unstable; and inorganic materials, including silts, too wet to be stable.
2. Existing Subgrade (except footings): Same materials as above paragraph, that are not capable of direct support of slabs, pavement, and similar items, with the possible exception of improvement by compaction, proof rolling, or similar methods of improvement.
3. Existing Subgrade (footings only): Same as Paragraph 1, but no fill or backfill.

B. Earthwork: Earthwork operations required within the new construction area. It also includes earthwork required for auxiliary structures and buildings and sewer and other trench work throughout the job site.

C. Degree of Compaction: Degree of compaction is expressed as a percentage of maximum density obtained by the test procedure presented in any of the following: // AASHTO // T99 // T180 // Method A. // ASTM // D698 // D1557 // Method A. //

D. The term fill means fill or backfill as appropriate.

1.3 RELATED WORK

A. Materials testing and inspection during construction: Section 01 45 29, TESTING LABORATORY SERVICES.

1.4 CLASSIFICATION OF EXCAVATION

- A. Unclassified Excavation: Removal and disposal of pavements and other man-made obstructions visible on the surface; utilities, and other items including underground structures indicated to be demolished and removed; together with any type of materials regardless of character of material and obstructions encountered.
- B. Classified Excavation: Removal and disposal of all material not defined as rock.

C. Rock Excavation:

1. Solid ledge rock (igneous, metamorphic, and sedimentary rock).
2. Bedded or conglomerate deposits so cemented as to present characteristics of solid rock which cannot be excavated without blasting; or the use of a modern power excavator (shovel, backhoe, or similar power excavators) of no less than 0.75 m³ (1 cubic yard) capacity, properly used, having adequate power and in good running condition.
3. Boulders or other detached stones each having a volume of 0.4 m³ (1/2 cubic yard) or more.

1.5 MEASUREMENT AND PAYMENT FOR ROCK EXCAVATION

- A. Measurement: Cross section and measure the uncovered and separated materials, and compute quantities by the Registered Professional Land Surveyor or Registered Civil Engineer, specified in Section 01 00 02, GENERAL REQUIREMENTS. Do not measure quantities beyond the following limits:
1. 300 mm (12 inches) outside of the perimeter of formed footings.
 2. 600 mm (24 inches) outside the face of concrete work for which forms are required, except for footings.
 3. 150 mm (6 inches) below the bottom of pipe and not more than the pipe diameter plus 600 mm (24 inches) in width for pipe trenches.
 4. The outside dimensions of concrete work for which no forms are required (trenches, conduits, and similar items not requiring forms).

1.6 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Rock Excavation Report:
1. Certification of rock quantities excavated.
 2. Excavation method.
 3. Labor.
 4. Equipment.
 5. Land Surveyor's or Civil Engineer's name and official registration stamp.
 6. Plot plan showing elevations.
- C. Furnish to Resident Engineer, soil samples, suitable for laboratory tests, of proposed off site or on site fill material.

1.7 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.
- B. American Nursery and Landscape Association (ANLA):

- 2004.....American Standard for Nursery Stock
- C. American Association of State Highway and Transportation Officials (AASHTO):
- T99-01 (R2004).....Moisture-Density Relations of Soils Using a 2.5 kg (5.5 lb) Rammer and a 305 mm (12 inch) Drop
- T180-01 (2004).....Moisture-Density Relations of Soils Using a 4.54-kg [10 lb] Rammer and a 457 mm (18 inch) Drop
- D. American Society for Testing and Materials (ASTM):
- D698-07.....Laboratory Compaction Characteristics of Soil Using Standard Effort
- D1557-07.....Laboratory Compaction Characteristics of Soil Using Modified Effort
- E. Standard Specifications of (Insert name of local state) State Department of Transportation, latest revision.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Fills: Materials approved from on site and off site sources having a minimum dry density of 1760 kg/m³ (110 pcf), a maximum Plasticity Index of 6, and a maximum Liquid Limit of 30.
- B. Granular Fill:
1. Under concrete slab, crushed stone or gravel graded from 25 mm (1 inch) to 4.75 mm (No. 4).
 2. Bedding for sanitary and storm sewer pipe, crushed stone or gravel graded from 13 mm (1/2 inch) to 4.75 mm (No. 4).
- C. Fertilizer: (5-10-5) delivered to site in unopened containers that clearly display the manufacturer's label, indicating the analysis of the contents.
- D. Seed: Grass mixture comparable to existing turf delivered to site in unopened containers that clearly display the manufacturer's label, indicating the analysis of the contents.
- E. Sod: Comparable species with existing turf. Use State Certified or State Approved sod when available. Deliver sod to site immediately after cutting and in a moist condition. Thickness of cut must be 19 mm to 32 mm (3/4 inch to 1 1/4 inches) excluding top growth. There shall be no broken pads and torn or uneven ends.

PART 3 - EXECUTION

3.1 SITE PREPARATION

- A. Clearing: Clearing within the limits of earthwork operations as described or designated by the Resident Engineer. Work includes removal

of trees, shrubs, fences, foundations, incidental structures, paving, debris, trash and any other obstructions. Remove materials from the Cemetery Property.

- B. Tree Removal: Removal all trees shall be accomplished under the direction and guidance of an ISA Certified Arborist provided by the Contractor. All trees shall be topped prior to falling and all limbs over 3 ½" in diameter must be lowered to the ground by ropes. At no time should any branches, tree limbs or sections of the trunk be dropped to the ground or on any headstones. The Contractor will be responsible for any damage to the turf, roads or headstones caused by dropping parts of the tree directly to the ground.
- C. Grubbing:
 - 1. For the purposes of the tree stump removal, the stump shall include a conical volume of lateral roots, heart roots, and root mass extending in a horizontal radius as measured at a point 6 inches above the ground and vertically downward from the same point. The horizontal radius shall be calculated at 6 inches for each inch of tree diameter. The downward vertical distance at 12 inches for the first inch of diameter and an additional 6 inches for each inch of diameter thereafter with a maximum depth of 2 1/2 feet.
 - 2. All lateral roots with a diameter less than 1 inch shall be removed to a depth of 6 inches below the planned subgrade elevation and all roots larger than 1 inch to a depth of 12 inches below the planned subgrade elevation.
 - 3. Nonperishable solid objects which will be a minimum of 30 mm (1 foot) below subgrade may be left.
- D. Surrounding Trees and Shrubs: Trees and shrubs, not shown for removal, may be removed from the areas within 4500 mm (15 feet) of new construction and 2250 mm (7'-6") of utility lines if such removal is recommended by an ISA Certified Arborist provided by the contractor and approved in advance by the Contracting Officer Representative (COR). Remove materials from the Cemetery Property. Trees and shrubs, shown to be transplanted, shall be dug with a ball of earth and burlapped in accordance with the latest issue of the, "American Standard for Nursery Stock", of the American Association of Nurserymen, Inc. Transplant trees and shrubs to a permanent or temporary position within two hours after digging. Maintain trees and shrubs held in temporary locations by watering as necessary and feeding semi-annually with liquid fertilizer with a minimum analysis of 5 percent nitrogen, 10 percent phosphorus and 5 percent potash. Maintain plants moved to permanent positions as specified for plants in temporary locations until the conclusion of the

contract. Box, and otherwise protect from damage, existing trees and shrubs which are not shown to be removed in the construction area. Repair immediately damage to existing trees and shrubs by trimming, cleaning and painting damaged areas, including the roots, in accordance with standard industry horticultural practice for the geographic area and plant species. Building materials shall not be stored closer to trees and shrubs that are to remain, than the farthest extension of their limbs.

- E. Stripping Topsoil: Unless otherwise indicated on the drawings, the limits of earthwork operations shall extend anywhere the existing grade is filled or cut or where construction operations have compacted or otherwise disturbed the existing grade or turf. Strip topsoil as defined herein, or as indicated in the geotechnical report, from within the limits of earthwork operations as specified above unless specifically indicated or specified elsewhere in the specifications or shown on the drawings. Topsoil shall be fertile, friable, natural topsoil of loamy character and characteristic of the locality. Topsoil shall be capable of growing healthy horticultural crops of grasses. Stockpile topsoil and protect as directed by the Resident Engineer. Eliminate foreign material, such as weeds, roots, stones, subsoil, frozen clods, and similar foreign materials, larger than 0.014 m³ (1/2 cubic foot) in volume, from soil as it is stockpiled. Retain topsoil on the station. Remove foreign materials larger than 50 mm (2 inches) in any dimension from topsoil used in final grading. Topsoil work, such as stripping, stockpiling, and similar topsoil work, shall not, under any circumstances, be carried out when the soil is wet so that the tilth of the soil will be destroyed.
1. Cemetery Projects: Recommend that the top soil be tested for chemicals, pesticides and fertilizers if topsoil is to be removed from lands formerly utilized as farmland, to verify suitability for use as topsoil in the cemetery where new lawn areas are to be established.
 2. Concrete Slabs and Paving: Score deeply or saw cut to insure a neat, straight cut, sections of existing concrete slabs and paving to be removed where excavation or trenching occurs. Extend pavement section to be removed a minimum of 300 mm (12 inches) on each side of widest part of trench excavation and insure final score lines are approximately parallel unless otherwise indicated. Remove material from the Cemetery Property.
- F. Disposal: All materials removed from the property shall be disposed of at a legally approved site, for the specific materials, and all removals

shall be in accordance with all applicable Federal, State and local regulations. No burning of materials is permitted onsite.

3.2 EXCAVATION

- A. Shoring, Sheet piling and Bracing: Shore, brace, or slope to its angle of repose banks of excavations to protect workmen, banks, adjacent paving, structures, and utilities, in compliance with OSHA requirements.
 - 1. Extend shoring and bracing to the bottom of the excavation. Shore excavations that are carried below the elevations of adjacent existing foundations.
 - 2. If the bearing of any foundation is disturbed by excavating, improper shoring or removal of shoring, placing of backfill, and similar operations, provide a concrete fill support under disturbed foundations, as directed by Resident Engineer, at no additional cost to the Government. Do not remove shoring until permanent work in excavation has been inspected and approved by Resident Engineer.
- B. Excavation Drainage: Operate pumping equipment, and/or provide other materials, means and equipment as required, to keep excavations free of water and subgrades dry, firm, and undisturbed until approval of permanent work has been received from Resident Engineer. Approval by the Resident Engineer is also required before placement of the permanent work on all subgrades. When subgrade for foundations has been disturbed by water, remove the disturbed material to firm undisturbed material after the water is brought under control. Replace disturbed subgrade in trenches by mechanically tamped sand or gravel. When removed disturbed material is located where it is not possible to install and properly compact disturbed subgrade material with mechanically compacted sand or gravel, the Resident Engineer should be contacted to consider the use of flowable fill.
- C. Blasting: Blasting shall be permitted only when authorized by the Resident Engineer. Blasting shall be done with explosives of such quantity and power, and fired in such sequence and locations as to not injure personnel, damage or crack rock against which concrete is to be placed, damage property, or damage existing work or other portions of new work. The Contractor shall be responsible for damage caused by blasting operations.
- D. Building Earthwork:
 - 1. Excavation shall be accomplished as required by drawings and specifications.
 - 2. Excavate foundation excavations to solid undisturbed subgrade.
 - 3. Remove loose or soft material to solid bottom.

4. Fill excess cut under footings or foundations with 25 MPa (3000 psi) concrete, poured separately from the footings.
5. Do not tamp earth for backfilling in footing bottoms, except as specified.

E. Trench Earthwork:

1. Utility trenches (except sanitary and storm sewer):
 - a. Excavate to a width as necessary for sheeting and bracing and proper performance of the work.
 - b. Grade bottom of trenches with bell-holes, scooped-out to provide a uniform bearing.
 - c. Support piping on undisturbed earth unless a mechanical support is shown.
 - d. The length of open trench in advance of pipe laying shall not be greater than is authorized by the Resident Engineer.
2. Sanitary and storm sewer trenches:
 - a. Trench width below a point 150 mm (6 inches) above top of the pipe shall be 600 mm (24 inches) for up to and including 300 mm (12 inches) diameter and four-thirds diameter of pipe plus 200 mm (8 inches) for pipe larger than 300 mm (12 inches). Width of trench above that level shall be as necessary for sheeting and bracing and proper performance of the work.
 - b. The bottom quadrant of the pipe shall be bedded on undisturbed soil or granular fill.
 - 1) Undisturbed: Bell holes shall be no larger than necessary for jointing. Backfill up to a point 300 mm (12 inches) above top of pipe shall be clean earth placed and tamped by hand.
 - 2) Granular Fill: Depth of fill shall be a minimum of 75 mm (3 inches) plus one-sixth of pipe diameter below the pipe of 300 mm (12 inches) above top of pipe. Place and tamp fill material by hand.
 - c. Place and compact as specified the remainder of backfill using acceptable excavated materials. Do not use unsuitable materials.
 - d. Use granular fill for bedding where rock or rocky materials are excavated.

- F. Site Earthwork: Excavation shall be accomplished as required by drawings and specifications. Remove subgrade materials, that are determined by the COR as unsuitable, and replace with acceptable material. If there is a question as to whether material is unsuitable or not, the Contractor shall obtain samples of the material, under the direction of the Resident Engineer, and the materials shall be examined by an independent

testing laboratory for soil classification to determine whether it is unsuitable or not. Testing of the soil shall be performed by the contractor's Testing Laboratory. When unsuitable material is encountered and removed, the contract price and time will be adjusted in accordance with Articles, DIFFERING SITE CONDITIONS, CHANGES and CHANGES-SUPPLEMENT of the GENERAL REQUIREMENTS as applicable. Adjustments to be based on meters (yardage) in cut section only.

G. Finished elevation of subgrade shall be as follows:

1. Pavement Areas - bottom of the pavement or base course as applicable.
2. Planting and Lawn Areas - 100 mm (4 inches) below the finished grade, unless otherwise specified or indicated on the drawings.

3.3 FILLING AND BACKFILLING

- A. General: Do not fill or backfill until all debris, unsatisfactory soil materials, obstructions, and deleterious materials have been removed from the excavation. Proof-roll exposed subgrades with a fully loaded dump truck. Use excavated materials or borrow for fill and backfill, as applicable. Do not use unsuitable excavated materials. Do not backfill until foundation walls have been completed above grade and adequately braced, waterproofing or dampproofing applied, and pipes coming in contact with backfill have been installed, and inspected and approved by Resident Engineer.
- B. Proof-rolling Existing Subgrade: Proof-roll with a fully loaded dump truck. Make a minimum of one pass in each direction. Remove unstable uncompactable material and replace with granular fill material completed to mix requirements specified.
- C. Placing: Place material in horizontal layers not exceeding 200 mm (8 inches) in loose depth and then compacted. Do not place material on surfaces that are muddy, frozen, or contain frost.
- D. Compaction: Use approved equipment (hand or mechanical) well suited to the type of material being compacted. Do not operate mechanized vibratory compaction equipment within 3000 mm (10 feet) of new or existing building walls without the prior approval of the Resident Engineer. Moisten or aerate material as necessary to provide the moisture content that will readily facilitate obtaining the specified compaction with the equipment used. Compact each layer until there is no evidence of further compaction and to not less than 95 percent of the maximum density determined in accordance with any of the following test methods: // AASHTO // T99 // T180 // Method A // ASTM // D698 // D1557 Method A //.

3.4 GRADING

- A. General: Uniformly grade the areas within the limits of this section, including adjacent transition areas. Smooth the finished surface within specified tolerance. Provide uniform levels or slopes between points where elevations are indicated, or between such points and existing finished grades. Provide a smooth transition between abrupt changes in slope.
- B. Cut rough or sloping rock to level beds for foundations. In unfinished areas fill low spots and level off with coarse sand or fine gravel.
- C. Slope backfill outside the building away from the building walls for a minimum distance of 1800 mm (6 feet).
- D. The finished grade shall be 150 mm (6 inches) below bottom line of windows or other building wall openings unless greater depth is shown.
- E. Place crushed stone or gravel fill under concrete slabs on grade tamped and leveled. The thickness of the fill shall be 150 mm (6 inches), unless otherwise indicated.
- F. Finish subgrade in a condition acceptable to the Resident Engineer at least one day in advance of the paving operations. Maintain finished subgrade in a smooth and compacted condition until the succeeding operation has been accomplished. Scarify, compact, and grade the subgrade prior to further construction when approved compacted subgrade is disturbed by contractor's subsequent operations or adverse weather.
- G. Grading for Paved Areas: Provide final grades for both subgrade and base course to +/- 6 mm (0.25 inches) of indicated grades.

3.5 LAWN AREAS

- A. General: Harrow and till to a depth of 100 mm (4 inches), new or existing lawn areas to remain, which are disturbed during construction. Establish existing or design grades by dragging or similar operations. Do not carry out lawn areas earthwork out when the soil is wet so that the tilth of the soil will be destroyed. Plant bed must be approved by Resident Engineer before seeding or sodding operation begins.
- B. Finished Grading: Begin finish grading after rough grading has had sufficient time for settlement. Scarify subgrade surface in lawn areas to a depth of 100 mm (4 inches). Apply topsoil so that after normal compaction, dragging and raking operations (to bring surface to indicated finish grades) there will be a minimum of 100 mm (4 inches) of topsoil over all lawn areas; make smooth, even surface and true grades, which will not allow water to stand at any point. Shape top and bottom of banks to form reverse curves in section; make junctions with undisturbed areas to conform to existing topography. Solid lines within grading limits indicate finished contours. Existing contours, indicated

by broken lines are believed approximately correct but are not guaranteed.

- C. Fertilizing: Incorporate fertilizer into the soil to a depth of 100 mm (4 inches) at a rate of 12 kg/100 m² (25 pounds per 1000 square feet).
- D. Seeding: Seed at a rate of 2 kg/100 m² (4 pounds per 1000 square feet) and accomplished only during periods when uniform distribution may be assured. Lightly rake seed into bed immediately after seeding. Roll seeded area immediately with a roller not to exceed 225 kg/m (150 pounds per foot) of roller width.
- E. Sodding: Topsoil shall be firmed by rolling and during periods of high temperature the topsoil shall be watered lightly immediately prior to laying sod. Sod strips shall be tightly butted at the ends and staggered in a running bond fashion. Placement on slopes shall be from the bottom to top of slope with sod strips running across slope. Secure sodded slopes by pegging or other approved methods. Roll sodded area with a roller not to exceed 225 kg/m (150 pounds per foot) of the roller width to improve contact of sod with the soil.
- F. Watering: The Resident Engineer is responsible for having adequate water available at the site. As sodding is completed in any one section, the entire sodded area shall be thoroughly irrigated by the contractor, to a sufficient depth, that the underside of the new sod pad and soil, immediately below sod, is thoroughly wet. Resident Engineer will be responsible for sod after installation and acceptance.

3.6 DISPOSAL OF UNSUITABLE AND EXCESS EXCAVATED MATERIAL

- A. Disposal: Remove surplus satisfactory soil and waste material, including unsatisfactory soil, trash, and debris, and legally dispose of it off Cemetery property.
 - 1. Remove waste material, including unsatisfactory soil, trash, and debris, and legally dispose of it off Cemetery property.
- B. Place excess excavated materials suitable for fill and/or backfill on site where directed.
- C. Remove from site and dispose of any excess excavated materials after all fill and backfill operations have been completed.
- D. Segregate all excavated contaminated soil designated by the Resident Engineer from all other excavated soils, and stockpile on site on two 0.15 mm (6 mil) polyethylene sheets with a polyethylene cover. A designated area shall be selected for this purpose. Dispose of excavated contaminated material in accordance with State and Local requirements.

3.6 CLEAN-UP

Upon completion of earthwork operations, clean areas within contract limits, remove tools, and equipment. Provide site clear, clean, free of

debris, and suitable for subsequent construction operations. Remove debris, rubbish, and excess material from the Cemetery Property.

- - - E N D - - -

**SECTION 32 14 16
BRICK UNIT PAVING**

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This work shall consist of removing and resetting existing brick pavers and the installation of additional brick pavers on either the existing recompacted base course or new base course at locations identified in plans. All existing brick pavers are to be removed, brushed or cleaned, segregated based on color, and stacked on pallets. Damaged, cracked, or chipped bricks are to be replaced. All bricks are to be placed on new bedding sand.
- B. Section Includes:
 - 1. Clay Brick Pavers
 - 2. Mortar
 - 3. Jointing and Bedding Sand
 - 4. Aggregate Base Course
 - 5. Geotextiles
 - 6. Edge Restraints

1.2 RELATED REQUIREMENTS

- A. Subgrade backfill, preparation, and compaction: Section 31 20 11 Earth Moving (Short Form).

1.3 APPLICABLE PUBLICATIONS

- A. Comply with references to extent specified in this section.
- B. American Association of State Highway and Transportation Officials (AASHTO)
 - 1. M147-65-UL-04 - Materials for Aggregate and Soil-Aggregate Subbase, Base, and Surface Courses.
 - 2. T180-D - Moisture-Density Relations for Soils.
- C. ASTM International (ASTM):
 - 1. C136, Standard Test Method for Sieve Analysis of Fine and Course Aggregates
 - 2. C144-11 - Aggregate for Masonry Mortar.
 - 3. C150/C150M-16 - Portland Cement
 - 4. C207-06(2011) - Hydrated Lime for Masonry Purposes.
 - 5. C270-14a - Mortar for Unit Masonry.
 - 6. C902-15 - Pedestrian and Light Traffic Paving Brick.

1.4 SUBMITTALS

- A. Submittal Procedures: Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Submittal Shop Drawings and Details:
 - 1. Show brick paving layout and patterns, describing materials, geotextile locations, drain locations, and installation details, methods, phasing, and facility accessibility plan during construction.
- C. Manufacturer's Literature and Data:
 - 1. Description of each product.
- D. Samples:
 - 1. Brick: Full size of each type and color.
 - a. Minimum five individual samples to show full color and texture range.
 - 2. Mortar: Samples of brick with mortar joints of each color.
 - 3. Geotextiles: One square foot of geotextile marked with manufacturer.
 - 4. Edge restraint: Three foot sample section of edge restraint and one spike.
- E. Test Reports: Certify products comply with specifications:
 - 1. Sieve analysis results in accordance with ASTM C136 for bedding and joint sand.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications:
 - 1. Regularly installs specified products
 - 2. Installed specified products with satisfactory service on five similar projects
 - a. Project Experience List: Provide contact names and addresses for completed projects.
- B. Mockups: Not Used,

1.6 DELIVERY

- A. Deliver products in manufacturer's original sealed packaging.
- B. Mark packaging, legibly. Indicate manufacturer's name or brand, type, color, production run number, and manufacture date.
- C. Before installation, return or dispose of products within distorted, damaged, or opened packaging.

1.7 STORAGE AND HANDLING

- A. Store masonry materials under waterproof covers on planking clear of ground.
- B. Protect products from damage during handling and construction operations.

1.8 FIELD CONDITIONS

- A. Environment:
 - 1. Product Temperatures: Do not install or work with any products unless the minimum temperature has been 4 degrees C (40 degrees F) for a minimum 48 hours before installation.
 - 2. Do not install sand or pavers during rain or snowfall.
 - 3. Do not install sand over frozen aggregate base.
 - 4. Do not install aggregate base course on frozen subgrade.

1.9 WARRANTY

- A. Construction Warranty: FAR clause 52.246-21, "Warranty of Construction."

PART 2 - PRODUCTS**2.1 SYSTEM PERFORMANCE**

- A. Design brick complying with specified performance:
 - 1. Slip Resistance: ASTM C902.

2.2 PRODUCTS - GENERAL

- A. Basis of Design: Match existing conditions
- B. Provide each paving system component from one manufacturer and from one production run.

2.3 CLAY BRICK PAVERS

- A. Paving Brick: ASTM C902; Class SX, Type I.
 - 1. Manufacturing Tolerances: // Application PS // Application PX //

2.4 MORTAR

- A. ASTM C270, Type S, cement-lime proportion specification mix. Admixtures and Type N lime are not acceptable.
- B. Hydrated Lime: ASTM C207 Type S.
- C. Sand: ASTM C144.
- D. Portland cement: ASTM C150/C150M.

- E. Coloring Pigments: Pure mineral pigments, lime proof and non-fading; added to mortar by the manufacturer. Job colored mortar is not acceptable.

2.5 Jointing and Bedding Sand

- A. Provide jointing and bedding sand as follows:

1. Clean, well graded, sand free from soluble salts and other deleterious or foreign matter. Sand shall be natural silica sand or sand manufactured from crushed rock.
2. Do not use screenings or stone dust for jointing sand or bedding sand.

- B. Jointing Sand Material Requirements:

1. Comply with ASTM C 144 requirements

ASTM C 144 Grading Requirements		
Sieve Size	Percent Passing, by Weight	
	Natural Sand	Manufactured Sand
No. 4 (4.75mm)	100	100
No. 8 (2.36mm)	95 to 100	95 to 100
No. 16 (1.18mm)	70 to 100	70 to 100
No. 30 (0.600mm)	40 to 75	40 to 75
No. 50 (0.300mm)	10 to 35	20 to 40
No. 100 (0.150mm)	2 to 15	10 to 25
No. 200 (0.075mm)	0 to 5	0 to 10

- C. Bedding Sand Material Requirements:

1. Comply with ASTM C33 requirements for fine aggregate.

ASTM C 33 Grading Requirements	
Sieve Size	Percent Passing
3/8 in (9.5mm)	100
No. 4 (4.75mm)	95 to 100
No. 8 (2.36mm)	80 to 100
No. 16 (1.18mm)	50 to 85
No. 30 (0.600mm)	25 to 60
No. 50 (0.300mm)	5 to 30
No. 100 (0.150mm)	0 to 10
No. 200 (0.075mm)	0 to 3

2. Do not use Mason's sand, or sand conforming to ASTM C 144 for bedding sand.

2.6 Aggregate Base Course

- A. Base course complying with AASHTO M147 Grade D
 1. Granular material composed of sand, sand-gravel, crushed stone, crushed or granulated slag, with or without soil binder, or combination of these materials.

ASTM M147 Grading Requirements	
Sieve Size	Percent Passing
1 in (25mm)	100
3/8 in (9.5mm)	60 to 100
No. 4 (4.75mm)	50 to 85
No. 10 (2mm)	40 to 70
No. 40 (0.425mm)	25 to 45
No. 200 (0.075mm)	5 to 20

2. Other acceptable Gradations: Materials within three to five percent plus or minus, of specified graduation, or as recommended by a registered geotechnical engineer and approved by the Contracting Officer's Representative.

2.7 Geotextiles

- A. Class 3 or higher woven slit-film geotextile for stabilization and separation.
- B. Other acceptable geotextile fabrics as recommended by a registered geotechnical engineer and approved by the Contracting Officer Representative (COR)

2.8 Edge Restraints

- A. Flexible or rigid edge restraints made from either Poly vinyl chloride (PVC), Aluminum, or galvanized steel in minimum lengths of 8 feet with a minimum height of 1 5/8 inches. Staking to be provided to a depth of at least 10 inches no less than every 2 feet for rigid restraints or every 12 inches for flexible restraints.

PART 3 - EXECUTION**3.1 GENERAL**

- A. Install products according to manufacturer's instructions and approved submittal drawings.

3.2 INSTALLATION**A. Subgrade**

1. Remove all tree stumps and roots larger than 2 inches in diameter to a depth 2 feet and all roots 2 inches or diameter to a depth of 1 foot.
2. As necessary backfill any areas below the required subgrade elevation with the largest base course stone being used on the project. The stone should be laid in 6 inch lifts.
3. Compact to not less than 95% Proctor Density in accordance with ASTM 698.

B. Geotextile Fabric

1. Regardless of subgrade strength, the site must be cleared of all sharp objects, tree stumps, and large stones that could puncture the fabric.
2. Fabric panels to be overlapped a minimum of 2 feet side to side and end to end.

C. Base Course

1. Base course aggregate shall be dumped on one end of the geotextile fabric and spread from this point over the fabric to avoid causing vehicle ruts in the subgrade.
2. The base course shall extend 6 inches beyond the area to be paved or direct to curbing or suitable established structures
3. The base course shall be compacted with hand tamping equipment to at least 95% of maximum density as determined by AASHTO T 180-D.
4. The surface of the base course, when testing using a ten foot straightedge shall not show any deviation in excess of 3/8 inch between two contact points. The finish surface shall not vary more than 3/8 inch from established grade.

D. Edge Restraints.

1. Place edging on compacted base. Verify location based on COR approved brick pattern. Do not place edging on bedding sand.
2. Spike edging in to place at minimum distances apart.

E. Mortared Paver Edge

1. Place Do not use or reset bricks with chips, cracks, discoloration, or other visible defects.
2. Mortar together edge laid brick pavers ensuring that mortar fills the entire joint between brick pavers. Remove excess mortar. Strike joints flush with top surface of brick and tool top joint slightly concave.
3. Cure mortar by maintaining damp condition for seven days.

F. Bedding Sand

1. Spread bedding sand evenly over base course and screed rails. Screed to 1 inch (25mm) thickness, not exceeding 1 3/8 (34.5mm) in thickness, including variations in base course surface.
2. Do not spread bedding sand beyond area to be covered by pavers the same day.

G. Mortarless Pavers

1. Do not use or reset bricks with chips, cracks, discoloration, or other visible defects.
2. Layout brick paving according to existing pattern or as indicated on pattern drawings approved by the COR.
3. Mix pavers from at least two pallets to produce uniform color blends.
4. Place pavers by hand without hammering providing 1/16 to 3/16 (2 to 5 mm) wide joint between pavers; with 1/8 inch being optimal.
5. Adjust pavers to form straight bong lines and appropriate joint widths. Maximum bond line variation shall be plus or minus 1/2 inch (13mm) over a 50 foot(15m) string line.
6. Do not permit traffic, including construction equipment, on pavers before initial compaction and joint filling
7. Vibrate pavers into sand using a high frequency/low-amplitude plate compactor capable of 3,000 lbf to 5,000 lbf (13 to 22 kN) at a 75 to 100 Hz frequency. Protect pavers from chipping during compaction by using a plate compactor with a rubber matt, rubber rollers or other approved materials placed over pavers. Do not compact within 6 feet (2 m) of unrestrained edges. Remove cracked or damaged pavers and replace with new units.

H. Jointing Sand

1. After pavers are fully settled and free from movement simultaneously spread, sweep and compact dry jointing sand into joints until they are completely filled and sand no longer falls into joints.
2. Discontinue laying operations, align and compact pavers prior to work suspension when weather conditions are such that pavement, performance may be compromised.
3. On laying operations recommencement, verify acceptable setting bed condition before further pavers are laid. If water has entered bedding sand, remove pavers and saturated bedding sand, install unsaturated sand, replace, and compact.
4. Sweep excess sand from pavement when installation is complete

3.3 Quality Control

A. Installation Tolerances:

1. Finished pavement shall not deviate more than plus or minus 3/8 inch (10mm) from specified elevation.
2. Pavement surface elevation shall be flush with adjacent construction and 1/8 to 1/4 inch (3 to 6 mm) above adjacent drainage inlets.
3. Maximum variation from specified surface profile shall be plus or minus 3/16 inch (5mm) in 10 feet.
4. Height difference between adjacent pavers shall not exceed 1/8 inch (3mm).

3.4 CLEANING

- #### **A. Clean exposed brick and mortar surfaces. Remove contaminants and stains.**

3.5 PROTECTION

- A. Protect brick paving from traffic and construction operations.
- B. Cover brick paving with reinforced craft paper, and plywood or hardboard.
- C. Remove protective materials immediately before acceptance.
- D. Repair damage.

- - - E N D - - -