

Statement of Work

Environmentally Controlled Space to Store Reusable Medical Equipment (RME)

A. GENERAL INFORMATION

1. Title of Project: Sterile temp controlled storage unit
2. Type of Contract Contemplated: Firm Fixed Price

B. SCOPE

The purchase of this storage cabinet will allow Sterile Processing Service (SPS) to store RME at satellite locations, i.e. Podiatry, Derm Surg., while storing the RME in appropriate environmental conditions as stipulated by the National Program Office for Sterile Processing (NPOSP).

C. REQUIREMENT/SALIENT CHARACTERISTICS/SPECIFICATIONS:

The cabinet is a self-contained environment that maintains temperature, humidity, and the required number of air exchanges. The cabinet is portable with an uninterruptible power supply (UPS), the cabinet runs on a common 110v power from the wall. The cabinet can fit through typical 36 inch doors found in most clinical areas. Therefore the cabinet can be moved at will with no considerations to construction, lease agreements, major impacts on clinical space, and no interruption to patient care.

Common Nomenclature: (specs below)

- Stainless steel Cabinet
- Solid state cooling unit
- HEPA Filter and recirculation fans
- Pull out shelving
- Battery back-up UPS system
- Access door with hasp for locking
- Wheels
- Controls
- Humidifier
- Condensate pump
- Hospital grade plug
- Leveling casters

Kind of material: SPS satellite storage

Electrical Data: 110v, with UPS. Must meet or exceed OSHA hospital regulations/standards in regards to electrical leakage current. Not to exceed 500 micro amps in a non-patient contact application or 300 micro amps in a direct patient contact application.

Dimensions, size, capacity: size 24"X60", capacity 6.4 ft³

Restrictive environmental conditions: indoor use with the exception of transportation

Intended use: SPS satellite storage

Equipment with which the item is used: RME

End item application: N/A

Original equipment manufacturer part number:

Other pertinent information that describes the item, material or service required: The design of this cabinet is a result of multiple audit findings; of an inability for facilities to maintain a proper RME storage environment. Audit findings have been local, VISN, and national. This is a common challenge for VA facilities

D. SECURITY: N/A

E. SPECIAL MATERIAL REQUIREMENT: N/A

F. PLACE OF PERFORMANCE: VA Medical Center, Canandaigua, NY / Rochester, NY Community Based Outpatient Clinic

G. PERIOD OF PERFORMANCE: N/A

H. BILLING/INVOICING: Upon Shipment

I. CUSTOMER INFORMATION

VA MEDICAL CENTER CANANDAIGUA
VA Canandaigua Logistics Warehouse
Attn: Roger Dilcher
400 Fort Hill Rd Canandaigua, NY 14424
Or

VA MEDICAL CENTER CANANDAIGUA
VA Canandaigua SPS
Attn: Cassidy Mincer
400 Fort Hill Rd Canandaigua, NY 14424

J. DRAWINGS/ASBUILTS/CONSTRUCTION FLOOR PLANS: Attached

K. Shipping: Standard FOB destination shipping must be included.

