

Bath VA Medical Center,
76 Veterans Avenue
Bath, NY 14810
POC: Julie Monagan Barnard, Interior Designer

Statement of Work Building 78, CLC2 Dining and Resident Room Chairs

I. INTENT

This is a Statement of Work for the acquisition of freestanding, upholstered dining chairs for Building 78 Community Living Center 2nd Floor, for use in their Dining Rooms, Multi-Purpose Family Dining Room and in the Resident Bedrooms. This will accomplish the facilities continuing effort to provide an aesthetically pleasing and therapeutic environment, while providing safe and durable seating in a style that coordinates with the themes of the two planned neighborhoods (Greek Revival and Queen Anne).

II. PROJECT SCOPE AND DESCRIPTION

A. Overview

This project will consist primarily of delivery and installation of freestanding, upholstered chairs for the 2nd floor of Building 78.

All work is to be completed during business hours.

The Contractor shall submit an estimated schedule for delivery and installation.

The Contractor shall be responsible for any damage to the furniture that occurs due to Contractor/freight error or neglect. The Contractor will be responsible for the coordination for delivery, receiving and installation to the VAMC.

B. Scope

The project consists of delivery and installation of 40 "Greek Revival" chairs, 40 "Queen Anne" chairs and 5 bariatric chairs as follows:

Chairs:

"Queen Anne" Chairs - (40 each) 38" high x 25" wide x 26.5" deep Kwalu Bellasari Dining Chair with Anti-Microbial Option "or equal" dining chairs.



“Queen Anne” Chair

Chair Frame Color: *Medium Cherry CCMC2014*

Chair Seat Upholstery: *Grade 12 Vinyl*

Chair Inside & Outside Back: *Grade 12 Vinyl*

“Greek Revival” Chairs - (40 each) 38” high x 25” wide x 26.5” deep Kwalu Torretta Dining Chair with Anti Microbial Option “or equal” dining chairs.



“Greek Revival” Chair

Chair Frame Color: *Medium Cherry CCMC2014*

Chair Seat Upholstery: *Grade 12 Vinyl*

Chair Inside & Outside Back: *Grade 12 Vinyl*

Bariatric Chairs - (5 each) 36" high x 34.5" wide x 27" deep Kwalu Valentia Bariatric Chair with Anti Microbial Option "or equal" dining chairs.



Bariatric Chair

Chair Frame Color: *Medium Cherry CCMC2014*

Chair Seat Upholstery: *Grade 12 Vinyl*

Chair Inside & Outside Back: *Grade 12 Vinyl*

All above chairs shall be of the quality and style type of Kwalu or equal chair, vinyl upholstered seat and back. Chairs (standard and bariatric) shall have the ability to be re-upholstered as needed in our on-site upholstery shop. Chairs shall be rated for 24/7 healthcare use. Chairs shall be easy to clean and sanitize, light weight enough to move as needed for eating and floor cleaning purposes, and shall carry a 10-year performance warranty on construction, finish and anti-microbial product protection. Chairs shall have been NFPA 261 fire tested.

Frame Construction & Cleaning:



The chair frame shall be made up of high-density polyurethane with steel-reinforced joints and stress points. Bariatric chair frame shall be made of high-density polyurethane with solid steel frame that must be capable of safely holding 250lbs and up to 500 pounds of weight. The finish shall be 1/8" thick, patented high-impact resistant repairable polymer, that is scuff-, scratch-, and water resistant. Finish has an imbedded anti-microbial agent that permeates the entire product, not just a topical coating, to provide adequate product protection to inhibit the growth of a broad spectrum of odor-causing bacteria, and protect the chair framework from stains and product deterioration over time. Finish must have the ability to be thoroughly cleansed with most water-based or water-soluble cleaning system and sanitizing solutions commonly used in healthcare and senior living environments, without compromising the antimicrobial product protection properties or damaging the finish. (US Patent No. 5,067,842).

Chair frame shall be resistant to most organic solvents or compounds such as ammonia, gasoline, white spirits, paraffin, both mineral and vegetable oils, animal fats, fruit pulp, grape acid, castor oil, blood, all body waste, lipstick, shoe polish, and salt water. Chair frame shall demonstrate an excellent resistance to acids, bases and oils.

Legs/Glides:

Legs shall have metal knock-in Teflon cap glides.

Seat:

Features cleanout

All upholstery materials meet the requirements of California Technical Bulletin #117

Seat frame is constructed of 3/4" plywood with elastic webbing band.

Back:

Back frame constructed of 3/4" plywood covered with cardboard. Back is attached to the arms using 1" screw flat square.

Cushioning:

Seat and back cushion shall be plywood frame upholstered with 2" hard foam (1st layer), 1/2" hard foam (2nd layer) and 1/2" hard foam on the band sides and top.

Testing:

Shall be capable of safely holding up to 250 pounds/500 pounds of weight for the bariatric chair and endure the most rigorous testing standards to provide supreme strength and safety for each user.

*****Manufacturer is Kwalu Designed to Last Furniture or Equal- FAR 52.211-6 Brand Name or Equal*****
FOR ALL PRODUCTS: Must meet salient characteristics outlined above when quoting an "or equal" item – FAR 52.211-6 Brand Name or Equal. "Or equal" items quoted should be similar to the requested dimensions, color scheme, function, and quality. "Or equal" products must include manufacturer's product brochure including specification information and all proposed finish selections. Actual finish samples if quoting an "or equal" item must be submitted for review by VA Interior Design for technical

*and aesthetic review. **FAILURE TO CLEARLY NOTE THAT THE PRODUCTS BEING QUOTED ARE THE REQUESTED BRAND NAME, OR FAILURE TO SUPPLY "OR EQUAL" PRODUCTS' SPECIFICATIONS AND INFORMATIONAL LITERATURE SHALL CONSTITUTE A "NON-RESPONSIVE" BID AND WILL NOT BE FURTHER EVALUATED FOR AWARD.***

III. PROJECT DELIVERY/INSTALLATION

A. Project installation

1. The Contractor shall submit an installation schedule for approval.
2. The Contractor shall coordinate with facility on staging needs and parking prior to installation dates.
3. Protect adjacent existing and newly placed construction, equipment and finishes as much as possible during installation to limit damage. The Contractor shall be responsible for any damage to the building that occurs due to contractor error or neglect.
4. The Contractor is responsible for the clean-up of each work area and for proper disposal of all packing/crating materials and will have limited access to cardboard recycling, metal recycling and garbage dumpsters.
5. The Contractor shall furnish all supplies, equipment, facilities and services required to perform the service under this contract.
6. Any painting and patching, if required, will be performed by the Bath VAMC paint department.

B. Delivery.

1. The Vendor shall provide up to 45 days free storage if needed.
2. Deliver materials to job in manufacturer's original sealed containers with brand name marked thereon. Protect materials from damage.
3. Package to prevent damage or deterioration during shipment, handling, storage and installation. Maintain protective covering in place and in good repair until removal is necessary.
4. Deliver only when the site is ready for installation work to proceed.
5. Store products in dry condition inside enclosed facilities.
6. Preferred delivery of product to be coordinated with Interior Designer.

C. Period of Performance.

Contract shall be completed as corresponding renovation of CLC2 is completed, projected for Fall 2017. Product shall not be put into production without the approval to do so from the P.O.C. Interior Designer.

D. PLACE OF PERFORMANCE.

Bath VAMC
76 Veterans Avenue
Bath, NY 14810

E. OPERATIONAL HOURS. Facility will be available for deliveries and installation between the hours of 0830 and 1600 M-F, excluding Federal Holidays.

F. GOVERNMENT-FURNISHED EQUIPMENT, BADGE, KEYS AND/OR FACILITIES PROVIDED. N/A

G. CONTRACTOR FURNISHED ITEMS AND RESPONSIBILITIES. The Contractor shall furnish all supplies, equipment, facilities and services required to perform the service under this contract. The Contractor shall perform all work in accordance with this Performance Work Statement to include the additional new/ refurbished furniture.

H. SECURITY REQUIREMENTS.

a. Installation passes. The contractor will coordinate for the issuance of required installation passes to contractor personnel. Contract personnel shall wear a badge that clearly identifies them as a contract employee. The badge will contain a picture, name of employee, and Contractor's name. Badges shall be worn on the outer garment in full view at all times, attached to the outer shirt or jacket pocket by a button or clip or worn around the neck secured by an appropriate identification card lanyard.

b. The Contractor shall not disclose and must safeguard procurement sensitive information, computer systems and data, Privacy Act data, and Government personnel work products that are obtained or generated in the performance of this contract. This includes dissemination of protocols and papers not generally available through the public literature.

c. Company will return all issued US Government installation badges and passes when the contract is completed.

d. In addition to the changes otherwise authorized by the changes clause of this contract, should the security condition change at any facility, the Government may require changes in contractor security requirements.

I. NON-PERSONAL SERVICE STATEMENT. Contractor employees performing services under this order will be controlled, directed and supervised at all times by management personnel of the contractor. Contractor employees will perform independent of and without the supervision of any Government official. Actions of contractor employees may not be interpreted or implemented in any manner that results in any contractor employee creating or modifying Federal policy, obligating the appropriated funds of the U.S. Government, overseeing the work of Federal employees, providing direct personal services to any Federal employee or otherwise violating the prohibitions set forth in Parts 7.5 and 37.1 of the Federal Acquisition Regulation (FAR). The Government will control access to the facility and perform the inspection and acceptance of the completed work.

J. Contract Officer Representative (COR). The COR monitors all technical aspects of the contract and assists in contract administration. The COR is authorized to perform the following functions: assure that the Contractor performs the technical requirements of the contract: perform inspections necessary in connection with contract performance: maintain written and oral communications with the Contractor concerning technical aspects of the contract: issue written interpretations of technical requirements, including Government drawings, designs, specifications: monitor Contractor's performance and notifies both the Contracting Officer and Contractor of any deficiencies; coordinate availability of government furnished property, and provide site entry of Contractor personnel. **The COR is not authorized to change any of the terms and conditions of the resulting order.**