

1 / 4-SS 1.01 FIRST FLOOR FRAMING PLAN – NORTH MODULE
1/8" = 1'-0"

SHEET NOTES:

1) SEE SHEET 4-SS 0.00 FOR GENERAL NOTES, ABBREVIATIONS AND SCHEDULES.
2) VERIFY ALL DIMENSIONS AND ELEVATIONS WITH EXISTING CONDITIONS, ARCHITECTURAL, PLUMBING AND MECHANICAL DRAWINGS.
3) SEE SHEET 4-SS 1.01 & 4-SS 1.02 FOR COLUMN DESIGNATIONS.
4) TYPICAL CONSTRUCTION NOTATION:
   k = INDICATES VERTICAL BEAM END REACTION
5) GENERAL CONTRACTOR: THIS STRUCTURE RELIES UPON NON-STRUCTURAL STEEL BUILDING COMPONENTS FOR FINAL LATERAL STRENGTH AND STABILITY.
6) T/STEEL EL = +11'-6" UNLESS NOTED THUS (X'-X").
7) JOIST BEARING ELEVATION = T/STEEL UNLESS NOTED THUS <X'-X">.
8) FLOOR CONSTRUCTION: 3" NORMAL WEIGHT CONCRETE W/6x6 – W2.9xW2.9 WELDED WIRE REINFORCEMENT ABOVE 9/16"x 22 GAUGE TYPE C FORM DECK. PROVIDE DECK CONTINUOUS OVER (3) SPANS MINIMUM. TOTAL DEPTH OF SYSTEM = 3 1/2". T/CONCRETE ELEVATION = +12'-0" U.N.O.
9) LASER SCREEDING OF ELEVATED SLABS SHALL NOT BE ALLOWED UNLESS SCREEDING PROCEDURE IS REVIEWED BY ENGINEER.
10) GENERAL CONTRACTOR SHALL COORDINATE ALL LOCATIONS AND SIZES OF FLOOR OPENINGS W/ARCHITECTURAL AND MECHANICAL DRAWINGS. NOT ALL OPENINGS ARE INDICATED ON PLAN. SEE DETAIL 15/4-SS 2.01.
11) COORDINATE T/STEEL BEAM ELEVATION AND LENGTH W/FOLDING PARTITION MANUFACTURER AND ARCHITECTURAL DRAWINGS.
12) L"X" INDICATES LINTEL. SEE LINTEL SCHEDULE ON SHEET 4-SS 0.00. NON-LOAD BRG LINTELS NOT SPECIFIED ON PLAN ARE PER LINTEL NOTES ON SHEET 4-SS 0.00. SEE ARCHITECTURAL AND MECHANICAL DRAWINGS FOR OPENING SIZES AND LOCATIONS.
13) PROVIDE DETAIL 13/4-SS2.01 AT ALL NON-LOAD BEARING MASONRY PARTITION WALLS. COORDINATE MASONRY PARTITION LOCATIONS W/ARCHITECTURAL DRAWINGS.
14) ▨ INDICATES LOAD BEARING MASONRY.
15) COORDINATE FLOOR DRAIN LOCATIONS WITH ARCHITECTURAL AND PLUMBING DRAWINGS. COORDINATE FLOOR SLOPE TO DRAIN WITH ARCHITECTURAL DRAWINGS.
16) GENERAL CONTRACTOR SHALL COORDINATE AND PROVIDE ALL MISCELLANEOUS STEEL PIECES AS INDICATED ON THE STRUCTURAL AND ARCHITECTURAL DRAWINGS.
17) RD INDICATES ROOF DRAIN. SEE ARCH AND PLUMBING DRAWINGS.
18) ROOF DECK 1 1/2"x22 GAUGE TYPE B, WIDE RIB, METAL DECK CONTINUOUS OVER (3) SPANS. WELD PATTERN SIDELAPS TO BE PER GENERAL NOTES, UNLESS NOTED OTHERWISE ON PLAN.

Revisions:	Date

CONSULTANTS:

MEP / FP
Metro Design Associates
1707 N. Randall Road Ste. 390
Elgin, Illinois 60123

Structral Engineering
Larson Engineering
1488 Bond St. Ste. 100
Naperville, Illinois 60563

Acoustical/AV Consultant
Shen Milson and Wilke
2 North Riverside Plaza, Ste. 1460
Chicago, Illinois 60606

Cost Estimating
Construction Cost Systems (CCS)
1815 S. Meyers Road, Ste. 200
Oak Brook Terrace, Illinois 60181

N

ARCHITECT/ENGINEERS:

LEGATARCHITECTS sustainability performance design

24 North Chapel Street
Waukegan, Illinois 60085–4107
Tel 847.662.3535 Fax 847.249.0398
www.legat.com

Drawing Title: FIRST FLOOR FRAMING PLAN - NORTH MODULE

Approved: Project Director

Project Title: FY2012 - BUILDING 4

Location: 3001 North Green Bay RD, North Chicago, IL 60064

Date: 03-30-2012 | Checked: CF | Drawn: VC

Project Number: 211097.00

Building Number: 4

Drawing Number: 4-SS 1.03

Dwg. of –

Office of Construction and Facilities Management

Department of Veterans Affairs

VA FORM 08-6231