

Question:

Reference Bid Item III (Alternate Deduct II) – specifically – the words “dormers” added to the roof.

Based upon the drawing sheet # 26-H2-Attic Plan – Ductwork – Coded Note #39 refers to relief air ductwork, plenums and louvers in two (2) areas which are not associated with “dormers”. They are at East/West elev. The “dormers” are associated with outside air ductwork and louvers in a north elev in two (2) locations and according to the attic plan...are required whether or not Alternate Deduct #2 is accepted or not.

Answer: Bid Item III is revised to say:

(Alternate Deduct II) Same as bid Item II except also delete the relief air ductwork and louvers in the attic. This includes ductwork, insulation, plenums, control dampers and new louvers installed at the east and west end of the building. Work to be accomplished within 152 calendar days after receipt of Notice to Proceed.

1. Sheet A303: Added details for Louver and wall replacement at attic of east and west elevations. See attached sheet.
2. Sheet 26-E3, “ATTIC PLAN-NEW WORK-POWER”
  - a. Provide 120V-20A connection to 26-AHU3 and 26-AHU4 (for lights within AHU) and connect to dedicated receptacle immediately adjacent to each unit (circuited to Panel AP).