MATCHLINE SEE SHEET L-5

REMOVE & REPLACE SIDEWALK 4" PCC, 36 SF

REMOVE & REPLACE SIDEWALK 4" PCC, 80 SF

STA 124+05 = STA 600+00

REMOVE & REPLACE SIDEWALK, 4" PCC, 36 SF STA 124+83 to STA 124+89

REMOVE SIDEWALK, 465 SF RE-GRADE PARKWAY, 4" TOPSOIL & SEEDING

REMOVE & REPLACE CURB & GUTTER, 10 LF

CLASS D PATCH, TYPE II, 14 SY STA 125+30 to STA 123+60

REMOVE & REPLACE SIDEWALK, 4" PCC, 110 SF STA 123+76 to STA 123+94

REMOVE & REPLACE STORM MANHOLE TYPE A, 4' DIAMETER TYPE 1 FRAME & OPEN LID STA 122+78

12" RCP STORM SEWER, 28 LF

REMOVE & REPLACE CATCH BASIN TYPE A, 4' DIAMETER TYPE 1 FRAME & OPEN LID STA 122+50

CLASS D PATCH, TYPE IV, 145 SY

CONSTRUCT NEW CURB & GUTTER TYPE B-6.12, 95 LF

12" RCP STORM SEWER, 27 LF

REMOVE & REPLACE INLET TYPE A, 2' DIAMETER TYPE 11 FRAME & GRATE

REMOVE & REPLACE SIDEWALK, 4" PCC, 30 SF INSTALL DETECTABLE WARNINGS, 8 SF

35

12" SOLID WHITE TRAFFIC PAINT MINIMUM 6' WIDE CROSSWALK

REMOVE & REPLACE SIDEWALK, 4" PCC, 250 SF RECONSTRUCT RAMP TO MEET ADA REQUIREMENTS INSTALL DETECTABLE WARNINGS, 8 SF

REMOVE & REPLACE SIDEWALK, 4" PCC, 44 SF STA 121+96 to STA 122+04

12" RCP STORM SEWER, 215 LF

REMOVE & REPLACE SIDEWALK, 4" PCC, 193 SF STA 121+08 to STA 121+42

REMOVE & REPLACE CURB & GUTTER, 6 LF STA 120+26 to STA 120+32

LIMITS OF ASPHALT SURFACE REMOVAL, 1-1/2" ASPHALT RESURFACING, MIX "C", N50, 1-3/4"

4" SOLID DOUBLE YELLOW TRAFFIC PAINT

CLASS D PATCH, TYPE IV, 270 SY STA 120+32 to STA 122+39

INLET, TYPE A, 2' DIA TYPE 11 FRAME & GRATE STA 120+40

REMOVE & REPLACE CURB & GUTTER, 15 LF STA 120+30 to STA 120+45

REMOVE & REPLACE SIDEWALK, 4" PCC, 55 SF STA 120+20 to STA 120+30

CLASS D PATCH, TYPE IV, 115 SY STA 117+90 to STA 119+17

REMOVE & REPLACE SIDEWALK, 4" PCC, 44 SF STA 119+66 to STA 19+74

REMOVE & REPLACE CURB & GUTTER, 35 LF STA 119+25 to STA 119+60

REMOVE & REPLACE CURB & GUTTER, 50 LF STA 116+52 to STA 117+02

CLASS D PATCH, TYPE IV, 35 SY STA 118+25 to STA 118+75

REMOVE & REPLACE SIDEWALK, 4" PCC, 200 SF STA 118+03 to STA 118+38

REMOVE & REPLACE SIDEWALK, 4" PCC, 82 SF STA 117+73 to STA 117+88

REMOVE & REPLACE CURB & GUTTER, 50 LF STA 117+34 to STA 117+84

REMOVE & REPLACE SIDEWALK, 4" PCC, 42 SF STA 117+01 to STA 117+08

60

DANVILLE AREA COMMUNITY COLLEGE

PARKING LOT "K"

PARKING LOT "L"

PARKING LOT "L"

MATCHLINE SEE SHEET L-3

1"=20' SCALE 20 0 20 40 FEET

PRINTED DATE: 2/18/2011
FILE NAME: C:\Projects\Danville VA Projects\10-553 Infrastructure Maintenance Improvements\cadd\Drawings\Sheets\06_L-4_P.dgn

LEGEND

- ASPHALT SURFACE REMOVAL & HMA RESURFACING LIMITS
- HMA RESURFACING LIMITS
- CLASS D PAVEMENT PATCH 6" HOT-MIX ASPHALT (HMA)
- CONCRETE PAVEMENT, 8"
- P.C.C. SIDEWALK, 4" TYPICAL (UNLESS NOTED OTHERWISE)
- P.C.C. SIDEWALK RAMP MAX SLOPE = 1:20 (5%)
- CURB & GUTTER, TYPE B-6.12 COMBINATION CONCRETE
- CROSSWALK, BY OTHERS 12" SOLID WHITE TRAFFIC PAINT, MINIMUM 6' WIDE

Drawing Title: **IMPROVEMENTS PLAN**

Project Title: **FCA REMOVE AND REPLACE ASPHALT ROADWAY AND CONCRETE WALKS STATION WIDE**

Location: VA ILLIANA HEALTH CARE SYSTEM DANVILLE, ILLINOIS

Building Number | Checked: P.T. | Drawn: M.D.

Date: 2/18/2011

Project No.: 550-10-119

DRAWING NO.: **L-4** 6 of 24

Office of Facilities

Department of Veteran Affairs