PRINTED DATE: 2/18/2011
FILE PATH: H:\projects\danville va hospital\10-353 Infrastructure maintenance improvements\cadd\drawings\Sheets\15_L-13_Plan.dgn

LEGEND

- ASPHALT SURFACE REMOVAL & HMA RESURFACING LIMITS
- HMA RESURFACING LIMITS
- CLASS D PAVEMENT PATCH 6" HOT-MIX ASPHALT (HMA)
- CONCRETE PAVEMENT, 8"
- P.C.C. SIDEWALK, 4" TYPICAL (UNLESS NOTED OTHERWISE)
- P.C.C. SIDEWALK RAMP MAX SLOPE = 1:20 (5%)
- CURB & GUTTER, TYPE B-6.12 COMBINATION CONCRETE
- CROSSWALK, BY OTHERS 12" SOLID WHITE TRAFFIC PAINT, MINIMUM 6' WIDE

Drawing Title: **IMPROVEMENTS PLAN**	Project Title: **FCA REMOVE AND REPLACE ASPHALT ROADWAY AND CONCRETE WALKS STATION WIDE**		Date: 2/18/2011
			Project No.: 550-10-119
	Building Number	Checked: P.T. / Drawn: M.D.	DRAWING NO.: **L-13** 15 of 24
	Location: VA ILLIANA HEALTH CARE SYSTEM DANVILLE, ILLINOIS		

Office of Facilities

Department of Veteran Affairs