



DEMOLITION PLAN HISTOLOGY LABORATORY

SCALE: 1/4" = 1'-0"



DEMOLITION NOTES

- 1 REMOVE EXISTING CARPET & VCT FLOORING. PATCH FLOOR & WALLS AS REQUIRED FOR NEW FINISH. REMOVE EXISTING CEILING GRID & TILE AS NEEDED TO PERFORM WORK. INTERIOR WALL HAS EXISTING FELT COVERING TO BE REMOVED.
- 2 REMOVE EXISTING CASEWORK, PLUMBING FIXTURES, POWER/LIGHTING, DATA, FLOOR FINISHES & CEILING TILES. PATCH FLOORS & WALLS AS REQUIRED FOR NEW FINISH. PLUMBING CONTRACTOR TO REMOVE EXIST. PLUMBING FIXTURES. REFER TO PLUMBING DRAWING FOR DETAILS.
- 3 HVAC CONTRACTOR TO REMOVE EXIST. VENTILATOR HOOD. EXHAUST DUCT ABOVE CEILING TO REMAIN FOR INSTALLATION OF NEW RETURN BY CONTRACTOR. REFER TO MECH DRAWING FOR DETAILS.
- 4 REMOVE EXISTING SUSPENDED TILE CEILING & GRID, V.C.T. FLOORING & COVE BASE ENTIRELY. PREPARE SURFACES TO RECEIVE NEW FINISHES.
- 5 REMOVE SECTIONS OF DRYWALL CEILING T.B.D. TO INSTALL NEW HATCH AND NEW EXHAUST VENT. PATCH & PAINT AS REQUIRED FOR NEW FINISH.
- 6 PATCH AND PAINT ALL INTERIOR WALLS IN ROOM 1B108. REMOVE WALL HUNG ITEMS AND STORE APPROPRIATELY AS DIRECTED BY COR FOR RE-INSTALLATION AS REQUIRED FOR NEW FINISH. SEE ROOM FINISH SCHEDULE.



UNITED STATES DEPARTMENT OF VETERANS AFFAIRS
VA MEDICAL CENTER - 1540 SPRING VALLEY DRIVE - HUNTINGTON WV 25704

DRAWING TITLE: DEMOLITION PLAN		PROJECT TITLE: RENOVATE HISTOLOGY LAB	
APPROVED: CHRIS ECKLES ASST CHIEF, ENGINEERING	BUILDING: 1S	PROJECT NUMBER: 12-104	DRAWING NUMBER: A1
APPROVED: JOHN KLIM CHIEF, ENGINEERING	DRAWN: STEVE ELROD	DATE: FEB '12	DWG.