

NOTES:

General Notes:

1. REFER TO SHEET TC-001 FOR PROJECT TELECOMMUNICATIONS ABBREVIATIONS, GENERAL NOTES, LEGENDS AND SYMBOLS.
2. ALL POKE-THRU DEVICE CONDUIT SHALL BE ROUTED BELOW FLOOR AND RISE UP INTO MEDICAL LIBRARY CEILING SPACE FOR CABLE TERMINATION WITHIN IRM TELECOMM ROOM 1-F515.
3. FIRE PROOF ALL WALL AND FLOOR PENETRATIONS AS REQUIRED PER CODE.
4. EC TO COORDINATE TELECOMMUNICATIONS BACK BOX LOCATION WITH ADJACENT ELECTRICAL BOX AS REQUIRED.

Legend:

(1) → INDICATES KEY NOTE ON THIS DRAWING, SEE BELOW.

Key Notes:

1. POKE-THRU CONDUIT RISER LOCATION. CONDUIT SHALL RISE UP WITHIN FRAMED COLUMN SPACE AND STUB UP INTO MEDICAL LIBRARY CEILING SPACE.
2. COORDINATE CABLE TRAY AND (2) 4" CONDUIT WITH EXISTING DUCT WORK IN THIS AREA. (DUCT WORK SHOWN FOR REFERENCE ONLY.)
3. CONTRACTOR SHALL PROVIDE SUPPORTS AND SUPPORT ALL EXISTING LOW VOLTAGE CABLE IN THIS AREA IN ACCORDANCE WITH THE DIV. 27 REQUIREMENTS AND EIA/TIA STANDARDS.

KEY PLAN NTS NORTH



100% CD
FULLY SPRINKLERED

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot

Revisions	Date

CONSULTANTS:

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
RAYMOND E. HEINTZ
REG. No. 121144
EXPIRES 10-01-12
RCDD

ARCHITECT/ENGINEERS:

Westlake Reed Leskosky

925 Euclid Avenue, Suite 1900, Cleveland, Ohio 44115
216.522.1350
Phoenix - Washington - Cleveland
WRL Commission #09017.00

Drawing Title: **TECHNOLOGY CEILING PLAN**
Approved Project Director:
Project Title: Wade Park Renovate Medical Library - CARES
Location: Cleveland, Ohio
Date: April 25, 2012
Checked:
Drawn:
Project Number: 541-12-103
Building Number: 1
Drawing Number: **TE-111**
Dwg. of

Office of Facilities Management
Department of Veterans Affairs

VA FORM 08-6231, OCT 1978