

ARCHITECTS BEAZLEY MOLIERE
A Professional Architectural Corporation
P. O. Box 51877
Lafayette, Louisiana 70505

RE: VA MEDICAL CENTER - ALEXANDRIA
RENOVATION FOR SUPPLY, PROCESSING &
DISTRIBUTION (SPD) DEPARTMENT
CONTRACT NO. VA256-C-1135
TASK ORDER NO. V502-C14133
VA PROJECT: 502-11-122
ABM PROJECT NO. 201101.7B

Issued May 5, 2012

AMENDMENT NO. 4

This amendment shall become a permanent part of the above referenced Project and shall alter the plans and specifications as follows:

ITEM NO. 1 – SHEET P101 - MECHANICAL ITEMS:

As a point of clarification P101 was not part of the original set therefore the contractor shall include the additional work as shown on P101 from Amendment No. 3.

ITEM NO. 2 – SHEET P201R - MECHANICAL ITEMS:

As a point of clarification, the FD's indicated on this sheet shall be a FB-A flush mounted floor drain. Refer to specification section 22 13 00 attached.

The FS indicated in Mech. Rm 33A shall be a FD-B recessed type floor drain in lieu of floor sink as indicated. Refer to specification section 22 13 00 attached.

Contractor shall provide Hospital Grade Acrylic shower and valve per the following information:

36"x36" White Acrylic shower, 1-1/2" self caulking brass shower drain, 1" O.D. gauge 304 stainless steel curtain rod with commercial grade white shower curtain and stainless steel rings. Shower valve shall be single handle thermostatic and pressure balancing mixing shower valve, vacuum breaker, with a commercial grade shower head.

ITEM NO. 3 – SHEET P301 - MECHANICAL ITEMS:

As a point of clarification, the electric water heater EWH-SPD1 shall be 120 Gallon, 54KW @ 208 Volt-3 Phase in lieu of 480 Volt- 3 phase as indicated.

ITEM NO. 4 – SPEC. SECTION 22 13 00 – FACILITY SANITARY AND VENT PIPING:

As a point of clarification, delete 2.5 Traps and add 2.5 Floor Drains attached.

End Amendment No. 4