



VETERANS ADMINISTRATION
WASHINGTON, D. C.

APPROVED *George E. Davis* Assistant Administrator
W. C. J. Davis Chief, Technical Division

NOTE: ALL RADIATORS SHALL BE CAST IRON, CONVECTOR TYPE WITH COMPLETE ENCLOSURE RECESSED IN WALL. RECESSES TO BE SHOWN ON ARCHITECTURAL DRAWINGS AND SCHEDULE ON THIS SHEET. CONNECTIONS AND PIPING CONNECTIONS TO BE SHOWN ON THIS SHEET. SEE OTHER DRAWINGS.

FLOOR	50 FT. RAD. SIZE	VALVE SIZE
FIRST FLOOR	UP TO 30	3/4"
SECOND FLOOR	UP TO 40	1"
THIRD FLOOR	UP TO 50	1 1/4"

HEATING
OFFICER'S DUPLEX QUARTERS #19
VETERANS ADMINISTRATION FACILITY
MURFREESBORO, TENN.

Drawn by: *W. C. J. Davis*
Checked by: *W. C. J. Davis*
Date: 3/31/38
Sheet: 5 of 6

Project No. 1419
Sub-division Chief: *W. C. J. Davis*

ROOMS	50 FT. RAD. SIZE	VALVE SIZE
BED ROOM NO. 1 & NO. 2	26	3/4"
BED ROOM NO. 3	34	1"
BATH ROOMS	24	3/4"
LIVING ROOM	39	1 1/4"
HALL	34	1"
DINING ROOM	32	3/4"
KITCHEN	30	3/4"

DIAGRAMMATIC SKETCH SHOWING CONNECTIONS TO HEATING BOILER

BASEMENT FLOOR PLAN
Scale 1/4" = 1'-0"

FIRST FLOOR PLAN
Scale 1/4" = 1'-0"

SECOND FLOOR PLAN
Scale 1/4" = 1'-0"

RETURN TRACINGS TO PLAN FILES

FILE FOLDER NO. 3

TOTAL E.D.R. EACH UNIT 360 #