






- 12 EXCLUDE FC-2.8 & FC-2.9 AND ASSOCIATED DUCTWORK, PIPING CONTROLS, ETC. AS PART OF ALTERNATE BID #2. SEE ALTERNATE BID #2 ON M1.2 FOR WORK IN THESE ROOMS.
- 13 EXISTING EA GRILLE TO REMAIN. PROVIDE OPPOSED BLADE VOLUME DAMPER BEHIND EXISTING GRILLE. FIELD VERIFY EXISTING SIZE AND LOCATION. CLEARANCE TO 175 CFM. PROVIDE ADJUSTMENTS TO VOLUME DAMPERS AND EXHAUST FAN OPERATION AS REQUIRED.
- 14 REROUTE EXISTING 10/8 EXHAUST AIR FROM SECOND FLOOR TO FIRST FLOOR IN NEW CHASE. PROVIDE FIRE DAMPER AT FLOOR PENETRATION. FIELD VERIFY EXISTING SIZE AND LOCATION OF EA DUCT.
- 15 FAN COIL UNIT WITH ELECTRIC COIL. PROVIDE DUCT LENGTH AND CLEARANCES UPSTREAM AND DOWNSTREAM OF ELECTRIC COIL PER MANUFACTURER'S RECOMMENDATIONS. MAINTAIN SERVICE/ZONE CODE REQUIRED CLEARANCES AT ELECTRIC COIL.

1. EXISTING CONDITIONS ABOVE CEILINGS AND WITHIN VERTICAL CHASES ARE NOT FULLY KNOWN. FIELD VERIFY ACTUAL CONDITIONS AND ADJUST WORK AS REQUIRED. NOTIFY ENGINEER AND ARCHITECT IF EXISTING PIPING, DUCTWORK, OR EQUIPMENT TO REMAIN CONFLICTS WITH THE NEW DESIGN.
2. DURING CONSTRUCTION NO CEILING TILES IN PUBLIC AREAS CAN BE LEFT OPEN OVERNIGHT.
3. COORDINATE SCHEDULING OF ALL WORK REQUIRED OUTSIDE THE RENOVATION AREA INCLUDING FLOORS ABOVE AND BELOW THE RENOVATION AREA WITH OTHER SPACES ADJACENT TO THE RENOVATION WILL REMAIN OPERATIONAL DURING CONSTRUCTION.

		© 2000 Calvin L. Hinz Architects P.C. These plans are specifically designed for construction by Calvin L. Hinz Architects and are intended for no other purposes. Permission for use of this document in part or whole without written consent of Calvin L. Hinz Architects is prohibited.		IMPORTANT CONTRACTOR'S NOTE 1. ALL CONTRACTORS ARE RESPONSIBLE FOR REVIEWING ENTIRE SET OF DOCUMENTS TO DETERMINE THEIR FULL SCOPE OF WORK. CONTRACTOR SHALL NOT BE ALLOWED EXTRA COSTS DUE TO FAILURE TO REVIEW ENTIRE SET OF DOCUMENTS. 2. ANY USE OF THESE ELECTRONIC DRAWINGS OR SCALING OF THE PRINTED DOCUMENTS ARE DONE SO AT THE CONTRACTORS RISK.				ARCHITECT/ENGINEERS:  Calvin L. HINZ Architects, P.C. 3705 North 200th Street Rikihorn, Nebraska 68022 Phone: 402.291.0941 Fax: 402.291.9193		 11620 ARBOR STREET SUITE 100 OMAHA, NEBRASKA 68144 PHONE: 402.932.0100 FAX: 402.932.1000 www.krsengineering.com KRS E ■ COPYRIGHT 2012 121013 This document and the information contained may not be reproduced without the express written permission of KRS Engineering, LLC. Unauthorized copying, disclosure or construction use are prohibited by the copyright law.		Drawing Title - BASE BID HVAC PLAN - 1st FLOOR - BASE BID HVAC PLAN - 2nd FLOOR		Project Title RENOVAE BACKFILL CANTEN SPACE NWIHCS		Project Number 636-12-103		Office of Construction and Facilities Management	
Revisions:		Date						Location VAMC Grand Island, NE		Drawing Number M1.1		Building Number ONE		Department of Veterans Affairs					
								Approved Project Director KEVIN HUTSELL		CONSTRUCTION DOCUMENT (CD-3) SUBMITTAL 100Z APRIL 13, 2012		Date APRIL 13, 2012				Checked MKL		Drawn SFP	