


VA Northern Indiana Health Care System

FORT WAYNE CAMPUS
2121 Lake Avenue
Fort Wayne, Indiana 46805

MARION CAMPUS
1700 E 38th Street
Marion, Indiana 46953


GENERAL NOTES:

1. THE CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS, TOOLS, EQUIPMENT, AND COMPETENT SUPERVISION NECESSARY TO REPLACE, REPAIR, OR INSTALL VARIOUS DOORS AS SPECIFIED IN THIS PROJECT.
2. EXCEPT FOR THE B172/174 DOOR, ALL WORK SHALL BE PERFORMED DURING ADMINISTRATIVE HOURS (7:00AM - 3:30PM WEEKDAYS EXCLUDING FEDERAL HOLIDAYS). DUE TO DINING TIMES IN BUILDING 174, THE B172/174 DOOR SHALL BE PERFORMED BETWEEN THE HOURS OF 7:00PM AND 6:00AM (MONDAY NIGHT - FRIDAY MORNING) SO AS TO AVOID THE FLOW OF PATIENT TRAFFIC.
3. AT THE CONCLUSION OF EACH WORK DAY, SITES SHALL BE CLEAN AND FREE OF DEBRIS. ADDITIONALLY, THE AREAS MUST BE SAFELY TRAVERSABLE DURING ADMINISTRATIVE HOURS.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING ALL MEASUREMENTS.
5. ALL DEBRIS SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE MARKED OR NOTED BY THE VA.
6. THE CONTRACTOR SHALL KEEP THE WORK SITE CLEAN AND FREE FROM OBSTRUCTIONS AT ALL TIMES. UPON FINAL CLEAN-UP, THE CONTRACTOR SHALL REMOVE ALL DEBRIS, RUBBISH, AND EXCESS MATERIAL FROM THE STATION.
7. INSTALL SUFFICIENT WALL, FLOOR, AND CEILING PROTECTION TO EXISTING MATERIALS. IF EXISTING MATERIALS AND/OR FINISHES BECOME DAMAGED, CONTRACTOR SHALL REPAIR OR REPLACE AT HIS/HER OWN EXPENSE.
8. THE WORK PERFORMED SHALL MEET THE REQUIREMENTS OF THE LATEST EDITION OF NFPA 101 AND NFPA 80 AND DOCUMENTS REFERENCED THEREIN.
9. EACH CONTRACTOR IS RESPONSIBLE TO PERFORM THEIR WORK IN ACCORDANCE WITH ALL FEDERAL AND OSHA REGULATIONS.
10. CONTRACTOR TO ACCOMPLISH WORK IN A MANNER THAT WILL DISTURB ADJACENT SITE AREAS AS LITTLE AS POSSIBLE.
11. AT THE CONCLUSION OF EACH DOOR AREA, THE CONTRACTOR SHALL WIPE DOWN ALL SURFACES TO REMOVE DUST AND DIRT ASSOCIATED WITH DEMOLITION AND CONSTRUCTION.
12. WALL AND FLOOR PENETRATIONS THROUGH FIRE WALLS AND FLOORS ARE TO BE FIRE STOPPED.
13. THE TERMS PROJECT MANAGER, PROJECT ENGINEER, CONTRACTING OFFICER'S TECHNICAL REPRESENTATIVE (COTR), VA REPRESENTATIVE, AND RESIDENT ENGINEER (RE) ARE USED INTERCHANGEABLY THROUGHOUT THE SPECIFICATIONS AND DRAWINGS.



FW General Site Plan - Fort Wayne

Not To Scale



M General Site Plan - Marion

Not To Scale

INDEX OF SHEETS:

- | | |
|-------|-----------------------|
| GI001 | COVER SHEET |
| AS101 | DOOR REPLACEMENT PLAN |

610-10-109

REPLACE VARIOUS DOORS, B172/174 (PFI)
BUILDINGS 172/174 (M), 138 (M), AND 1 (FW)

Revisions:	Date

VA Northern Indiana Health Care System, Marion
1700 E 38th Street
Marion, IN 46953

Approved: Medical Center Director Daniel D. Hendee, FACHE
Approved: Associate Director for Operations Helen Rhodes
Approved: Engineering Service Charles Applewhite

Drawing Title COVER SHEET
Approved: Project Director

Project Title REPLACE VARIOUS DOORS B172/174 (PFI)
Location VA NIHCS, Marion, IN
Date 03/12/2012
Checked CDA
Drawn AJ HAWK

Project Number 610-10-109
Building Number VARIOUS
Drawing Number GI001
Dwg. 1 of 2



