



- GENERAL NOTES:**
- A. CONTRACTOR SHALL LIMIT ACCESS TO ACTIVE CONSTRUCTION AREAS THROUGH USE OF TEMPORARY FENCING (PORTABLE CHAIN LINK FENCE 6' IN HEIGHT WITH GATES FOR ACCESS).
 - B. UNLESS OTHERWISE NOTED, THE DEMOLITION SCOPE OF WORK CALLS FOR THE REMOVAL AND DISPOSAL OF ALL ELECTRICAL EQUIPMENT LOCATED WITHIN THE BOUNDARIES OF THE PROJECT AREA. THE ELECTRICAL DRAWINGS DO NOT NECESSARILY REFLECT ALL ACTUAL ELECTRICAL ITEMS TO BE DEMOLISHED AND/OR ACTUAL LOCATIONS OF ITEMS.
 - C. EXISTING LIGHTING FIXTURES AND ASSOCIATED COMPONENTS SHOWN OF PLANS ARE APPROXIMATE LOCATIONS AND IS PROVIDED FOR REFERENCE USE ONLY. FIELD VERIFY EXACT LOCATIONS, SIZES AND CONDITIONS OF EXISTING COMPONENTS.
 - D. CONTRACTOR SHALL OBTAIN ALL EXISTING ELECTRICAL DRAWINGS OF THE AREA FROM THE VA BEFORE STARTING THE DEMOLITION WORK. ALL EXISTING LIGHTING CIRCUITS SHALL BE TRACED BACK TO THEIR SOURCE.
 - E. COORDINATE ALL REQUIRED EQUIPMENT SHUTDOWNS WITH THE VA REPRESENTATIVE PRIOR TO PROCEEDING TO DISCONNECT EQUIPMENT.
 - F. CIRCUIT CONTINUITY SHALL BE MAINTAINED TO ALL AREAS NOT PART OF THE PROJECT DURING AND AFTER CONSTRUCTION. PROVIDE TEMPORARY POWER AND LIGHTING DURING CONSTRUCTION AS NEEDED.
- KEYED NOTES:** —
- 1. REMOVE EXISTING EMERGENCY COMMUNICATOR AND DISCARD.
 - 2. EXISTING 30 FT POLE LUMINAIRE.
 - 3. EXISTING VAPORTITE FLUORESCENT WITH (2) 32 WATT T8 LAMPS UNDER CANOPY.

<table border="1"><thead><tr><th>Number</th><th>Description</th><th>Date</th></tr></thead><tbody><tr><td>1</td><td>REVISED 100% CONSTRUCTION DRAWINGS</td><td>6/15/2016</td></tr><tr><td>2</td><td>REVISED 100% CONSTRUCTION DRAWINGS</td><td>6/24/2016</td></tr><tr><td>3</td><td>REVISED 100% CONSTRUCTION DRAWINGS</td><td>3/16/2017</td></tr></tbody></table>			Number	Description	Date	1	REVISED 100% CONSTRUCTION DRAWINGS	6/15/2016	2	REVISED 100% CONSTRUCTION DRAWINGS	6/24/2016	3	REVISED 100% CONSTRUCTION DRAWINGS	3/16/2017	MECHANICAL / ELECTRICAL ENGINEERS: MES GROUP MES GROUP 550 NORTH REO STREET, SUITE 203 TAMPA, FL 33609 PHONE: (813) 289-4700 FAX: (813) 289-1041 WWW.MESGROUPINC.COM			CIVIL ENGINEERS: Sprinkle Consulting Planners + Engineers 18115 U.S. HWY. 41 NORTH SUITE 600 LUTZ, FL 33549 PHONE: (813) 949-7449 FAX: (813) 909-9840 WWW.SPRINKLECONSULTING.COM BOARD OF ENGINEERS CERTIFICATE OF AUTHORIZATION #4548			Drawing Title AREAS 1A, 1B, 2, 3, AND 5 - DEMOLITION PLAN Approved Project Director Project Status: REVISED 100% CONSTRUCTION DRAWINGS			Project Title UPDATE SITE FOR COMPLIANCE WITH VA BARRIER FREE GUIDE Location GAINESVILLE, FL PROJECT #573-13-601 Date 06/15/2016 Checked Drawn 			Project Number 573-13-601 Building Number N/A Drawing Number ED-102 Dwg. 44 of 50			Office of Construction and Facilities Management Department of Veterans Affairs		
Number	Description	Date																														
1	REVISED 100% CONSTRUCTION DRAWINGS	6/15/2016																														
2	REVISED 100% CONSTRUCTION DRAWINGS	6/24/2016																														
3	REVISED 100% CONSTRUCTION DRAWINGS	3/16/2017																														

K:\2013537 va gainesville barrier free\2013537-E-101.dwg 3-16-17 09:41:06 AM Pmoody