



- GENERAL NOTES:**
- A. CONTRACTOR SHALL LIMIT ACCESS TO ACTIVE CONSTRUCTION AREAS THROUGH USE OF TEMPORARY FENCING (PORTABLE CHAIN LINK FENCE 6' IN HEIGHT WITH GATES FOR ACCESS).
  - B. UNLESS OTHERWISE NOTED, THE DEMOLITION SCOPE OF WORK CALLS FOR THE REMOVAL AND DISPOSAL OF ALL ELECTRICAL EQUIPMENT LOCATED WITHIN THE BOUNDARIES OF THE PROJECT AREA. THE ELECTRICAL DRAWINGS DO NOT NECESSARILY REFLECT ALL ACTUAL ELECTRICAL ITEMS TO BE DEMOLISHED AND/OR ACTUAL LOCATIONS OF ITEMS.
  - C. EXISTING LIGHTING FIXTURES AND ASSOCIATED COMPONENTS SHOWN ON PLANS ARE APPROXIMATE LOCATIONS AND IS PROVIDED FOR REFERENCE USE ONLY. FIELD VERIFY EXACT LOCATIONS, SIZES AND CONDITIONS OF EXISTING COMPONENTS.
  - D. CONTRACTOR SHALL OBTAIN ALL EXISTING ELECTRICAL DRAWINGS OF THE AREA FROM THE VA BEFORE STARTING THE DEMOLITION WORK. ALL EXISTING LIGHTING CIRCUITS SHALL BE TRACED BACK TO THEIR SOURCE.
  - E. COORDINATE ALL REQUIRED EQUIPMENT SHUTDOWNS WITH THE VA REPRESENTATIVE PRIOR TO PROCEEDING TO DISCONNECT EQUIPMENT.
  - F. CIRCUIT CONTINUITY SHALL BE MAINTAINED TO ALL AREAS NOT PART OF THE PROJECT DURING AND AFTER CONSTRUCTION. PROVIDE TEMPORARY POWER AND LIGHTING DURING CONSTRUCTION AS NEEDED.
- KEYED NOTES:** (○)
- 1. EXISTING FLAG FLOOD LIGHTS.
  - 2. EXISTING 30 FT POLE MOUNTED LUMINAIRE WITH METAL HALIDE SOURCE.
  - 3. EXISTING CANOPY DOWNLIGHT TO BE REMOVED. EXISTING LIGHTING CIRCUIT SHALL REMAIN AND BE REUSED. SEE DRAWING E-204 FOR MORE INFORMATION.
  - 4. EXISTING METAL HALIDE WALL PACK ABOVE DOOR.
  - 5. EXISTING 30 FT POLE MOUNTED LUMINAIRE TO BE REMOVED. EXISTING LIGHTING CIRCUIT SHALL REMAIN AND BE REUSED. SEE DRAWING E-204 FOR MORE INFORMATION.
  - 6. EXISTING DOWNLIGHTING UNDER CANOPY.

K:\2013537 va gainesville barrier free\2013537-E-101.dwg 3-16-17 09:41:11 AM Pmoody

Number	Description	Date
1	REVISED 100% CONSTRUCTION DRAWINGS	6/15/2016
2	REVISED 100% CONSTRUCTION DRAWINGS	6/24/2016
3	REVISED 100% CONSTRUCTION DRAWINGS	3/6/2017

MECHANICAL / ELECTRICAL ENGINEERS:

**MES GROUP**

MES GROUP  
550 NORTH REO STREET, SUITE 203  
TAMPA, FL 33609  
PHONE: (813) 289-4700  
FAX: (813) 289-1041  
WWW.MESGROUPINC.COM

DALE A. BACIK, P.E.  
36564

CIVIL ENGINEERS:

**Sprinkle CONSULTING**  
Planners + Engineers  
18115 U.S. HWY. 41 NORTH SUITE 600  
LUTZ, FL 33549  
PHONE: (813) 949-7449 FAX: (813) 909-9840  
WWW.SPRINKLECONSULTING.COM  
BOARD OF ENGINEERS CERTIFICATE OF AUTHORIZATION #4548

Drawing Title  
AREA 8 - DEMOLITION PLAN

Approved Project Director

Project Status: REVISED 100% CONSTRUCTION DRAWINGS

Project Title  
UPDATE SITE FOR COMPLIANCE  
WITH VA BARRIER FREE GUIDE

Location  
GAINESVILLE, FL  
PROJECT #573-13-601

Date  
06/15/2016

Checked

Drawn

Project Number  
573-13-601

Building Number  
N/A

Drawing Number  
ED-104

Dwg. 46 of 50

Office of  
Construction  
and Facilities  
Management

Department of  
Veterans Affairs