

VA786-17-Q-0321 ATTACHMENT A - PRODUCT SPECIFICATIONS

[SHARE](#)

Bobcat MT85 Mini Track Loader

No need for wheelbarrows, shovels or other hand tools when you roll onto tight jobsites with the Bobcat® MT85 mini track loader. The MT85 goes through gates, doorways or other narrow spaces with ease.

The MT85 offers a performance boost with its improved rated operating capacity, increased breakout force and a 14 percent increase in lift height. The smoother ride leads to less spillage of material during transportation, allowing for faster cleanup at the end of your job. The MT85 increases top travel speeds by 23 percent to help you complete tasks faster.

Using the ergonomically-designed ISO joystick controls, it's easy to maneuver the MT85. The dedicated ride-on platform keeps you above the surface conditions at all times.

Equip the MT85 with either the Common Industry Interface (CII) or the exclusive Bob-Tach® mounting system. The Common Industry Interface design allows you to pair the MT85 with many attachments you may already own and use, while the Bob-Tach mounting system delivers rapid attachment changes and superior attachment fitment. Use your MT85 for trenching, digging, carrying materials, demolition, site preparation, snow removal, utility installation, sweeping, stump grinding and more.

Performance Features

Unmatched power to help you push through your toughest jobs.

Attachment Features

Comfort Features

Serviceability Features

Performance Features



Performance Advantages



Compact Size



Simple Operation



Minimal Ground Disturbance



Improved Maneuverability



Ride-On/Walk-Behind Convenience



Safety Features

[Back to the top](#)

[SHARE](#)

Mini Track Loaders / MT85 Mini Track Loader

Specifications & Options

Standard	Optional	Not Applicable	Units	US
Engine			Bobcat MT85	
Emissions Tier (EPA)			Tier 4	
Engine Cooling			Liquid	
Engine Fuel			Diesel	
Displacement			55 in³	
Number of Cylinders			3	
Performance				
Rated Operating Capacity (SAE)			850 lb	
Tipping Load			2458 lb	
Operating Weight			3110 lb	
Ground Pressure (Rubber)			4.9 psi	
Travel Speed			4 mph	
Travel Speed - Reverse			2.4 mph	
Capacities				
Fuel Tank			7 gal	
Hydraulic System				
Pump Capacity			12 gal/min	
System Relief @ Quick Couplers			2,900 psi	
Auxiliary Std Flow			n/a	

Dimension

Length	106.2 in
Width	35.6 in
Height	54.6 in
Height to Bucket Hinge Pin	80.9 in
Length of track on ground	40.6 in
Reach @ Maximum Height	18.6 in

Features

Lift-Arm Support

Auxiliary Hydraulics

Spark Arrestor Muffler

Bob-Tach Attachment System

Reverse Travel Stop Panel

Wide Track

Neutral Start Interlocks

Lift Arm Lockout With Manual Bypass

Tilt Lockout

Built-In Tie Down & Crane/Lift Locations

Ride-on Platform

Certain specification(s) are based on engineering calculations and are not actual measurements. Specification(s) are provided for comparison purposes only and are subject to change without notice. Specification(s) for your individual equipment will vary based on normal variations in design, manufacturing, operating conditions, and other factors.

[SHARE](#)

Attachments / Snowblower

Specifications

Units US

	Snowblower, SB200 - 78"	Snowblower, SB240 - 72"	Snowblower, SB240 - 84"	Snowblower, SBX240 - 72"	Snowblower, SBX240 - 84"
General					
Operating Weight	860 lb	1010 lb	1070 lb	1010 lb	1105 lb
Length	38.5 in	43.3 in	43.3 in	44.4 in	44.4 in
Width	80.5 in	74.5 in	86.5 in	74.5 in	86.5 in
Height	61 in	65.5 in	65.5 in	65.4 in	65.4 in
Steel Cutting Edge	.5x4.0 in. (13x102mm)	.5x4.0 in. (13x102mm)	.5x4.0 in. (13x102mm)	.5x4.0 in. (13x102mm)	.5x4.0 in. (13x102mm)
Intake Height	25 in	33.8 in	33.8 in	34.5 in	33.8 in
Fan Diameter	20 in	24 in	24 in	24 in	24 in
Auger Diameter	14 in	18 in	18 in	18.5 in	18.5 in
Discharge Chute	Hydraulically Controlled	Hydraulically Controlled	Hydraulically Controlled	Hydraulically Controlled	Hydraulically Controlled
Discharge Chute Angle	270°	270°	270°	270°	270°
Throw Distance	Up to 40 feet (12.2 M)	Up to 40 feet (12.2 M)	Up to 45 feet (13.7 M)	Up to 45 feet (13.7 M)	Up to 45 feet (13.7 M)
Flow Required Min	14.5 gal/min	25 gal/min	25 gal/min	35 gal/min	35 gal/min
Flow Required Max	32 gal/min	32 gal/min	32 gal/min	42 gal/min	42 gal/min

Compatible Carriers

Skid-Steer Loaders

[Bobcat A770](#)

Bobcat S70

Bobcat S450

Bobcat S510

Bobcat S530

Bobcat S550

Bobcat S570

Bobcat S590

Bobcat S595

Bobcat S630

Bobcat S650

Bobcat S740

Bobcat S750

Bobcat S770

Bobcat S850 T4

Compact Track Loaders

Bobcat T450

Bobcat T550

Bobcat T590

Bobcat T595

Bobcat T630

Bobcat T650

Bobcat T740

Bobcat T750

Bobcat T770

Bobcat T870

Mini Track Loaders

Bobcat MT55

Bobcat MT85

Toolcat™ Work Machine

Bobcat 5600

Bobcat 5610

Telehandler

Bobcat V519

Certain specification(s) are based on engineering calculations and are not actual measurements. Specification(s) are provided for comparison purposes only and are subject to change without notice. Specification(s) for your individual equipment will vary based on normal variations in design, manufacturing, operating conditions, and other factors.