



KEYED NOTES

- 1 1/4" COPPER TYPE INSULATED CONDENSATE DRAIN LINE DOWN THRU ROOF. ROUTE TO MOP SINK IN H.A.C. X210 ROOM
- CHILLED WATER SUPPLY AND RETURN PIPES DOWN THRU ROOF. REFER TO SECOND FLOOR (SHEET MH2.2) FOR CONTINUATION. HEAT TRACE NOT REQUIRED. INSULATED AND INSTALLED WITH METAL JACKETS.
- PROVIDE 1/4" PER FOOT SLOPE
- ROUTE CONDENSATE PIPE ABOVE ROOF. MAINTAIN MINIMUM 1/4" PER LINEAR FOOT SLOPE. ROUTE TO ROOF DRAIN. REL TO D.1.
- 3" RVC WATER-HEATER EXHAUST/INTAKE VENT UNDER SLOPING ROOF. RISE ALONG MEZZANINE WALL. OFFSET HORIZONTALLY APPROXIMATELY 8' ABOVE MEZZANINE LEVEL. TERMINATE WITH 3" CONCENTRIC VENT THRU MEZZANINE WALL.

CONTROL VALVES AND CABINET SHALL BE INSTALLED ON THE ROOF AS PER RFI 046.1

CONDENSATE DRAIN ROUTING
NOT TO SCALE

MECHANICAL AND PLUMBING ROOF PLAN

SCALE: 1/8"=1'-0"

RECORD DRAWINGS
DATE: NOVEMBER 16, 2012
THESE AS-BUILT DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED BY THE CONTRACTOR LARSEN GENERAL CONTRACTORS, LTD. THE ARCHITECT/ENGINEER HAS NOT VERIFIED THE ACCURACY AND/OR COMPLETENESS OF THIS INFORMATION AND SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS RESULT OF INCORRECT INFORMATION PROVIDED BY THE CONTRACTOR.

ASI #3	04/04/11
RFI #96	11/04/11
RFI #46	07/07/11
RFI #109.1	12/20/11
RFI #113	01/19/12
Revisions	Date

CONSULTANTS:

TEXAS REGISTERED
ENGINEERING FIRM P-10487
700 N. ST. MARY'S
SUITE 1225
SAN ANTONIO, TX 78205
WWW.RDMENGINEERING.NET
PHONE: 210.299.4522
FAX: 210.299.4525

Approved: Assistant Director	Approved: Chief of Staff	Approved: Chief, Engineering
Approved: Service Chief	Approved: Service Chief	Approved: Service Chief
Approved: Chief, Biomed	Approved: Chief, EMS	Approved: Chief, Infection Control
Approved: Chief, IT	Approved: Chief, M & O	Approved: Chief, Police
Approved: Chief, Safety	Approved: Chief	Approved: Chief

ARCHITECT:

WESTEAST DESIGN GROUP

1617 E. COMMERCE ST., SUITE 7102, SAN ANTONIO, TEXAS 78205 USA
210.530.0755 FAX 210.530.9427

These documents can not be copied or reproduced without written consent from WestEast Design Group

Drawing Title

MECHANICAL AND PLUMBING ROOF PLAN

Approved: Project Director

Project Title

POLYTRAUMA TRANSITIONAL HOUSING

Location
Audie L. Murphy Memorial Veterans Hospital
San Antonio, Texas
Date
28 JULY 2010
Checked
Drawn

Project Number
671-237
Building Number
1
Drawing Number
MP1.2
Dwg. 2 of 2

Office of Facilities Management

Department of Veterans Affairs