



KEYED NOTES

- 1 30 X 14 SUPPLY DUCT UP IN CHASE.
- 2 36 X 18 RETURN AIR DUCT UP IN CHASE.
- 3 14 X 14 EXHAUST DUCT UP IN CHASE.
- 4 26 X 16 SUPPLY AIR DUCT UP IN CHASE.
- 5 28 X 16 SUPPLY AIR UP IN CHASE.
- 6 38 X 18 RETURN AIR DUCT UP IN CHASE.
- 7 BOTTOM OF GRILLE TO MOUNT AT 11'-0" A.F.F.
- 8 30"x30" CEILING ACCESS FOR EQUIPMENT SERVICE.
- 9 DRYER VENT WALL CAP WITH BACKDRAFT DAMPER. TYPICAL FOR 2. BOTTOM OF VENT TO BE MOUNTED 24" A.F.F.
- 10 3" ROUND ALUMINUM DRYER VENT DUCT TO EXTERIOR WALL. ROUTE ONE VENT ON TOP OF THE OTHER. CONNECT TO DRYER VENT WALL CAP.
- 11 12x12" WALL OPENING. TOP OF OPENING TO BE AT 24" BELOW STRUCTURE. PROVIDE RETURN AIR GRILLE AT EACH SIDE OF WALL.

RECORD DRAWINGS

DATE: NOVEMBER 16, 2012

THESE AD-DULT DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED BY THE CONTRACTOR LORIS GENERAL CONTRACTORS, LTD. THE ARCHITECT/ENGINEER HAS NOT VERIFIED THE ACCURACY AND/OR COMPLETENESS OF THIS INFORMATION AND SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS RESULT OF INCORRECT INFORMATION PROVIDED BY THE CONTRACTOR.

1 FIRST FLOOR MECHANICAL PLAN
SCALE: 1/8" = 1'-0"

AMENDMENT NO. 02	31/08/2010
ASI #2	04/04/11
ASI #4	04/04/11
RFI #106	12/05/11
RFI #50	06/27/11
RFI #76	08/29/11
Revisions	Date

CONSULTANTS:

TEXAS REGISTERED
ENGINEERING FIRM F-10487
700 N. ST. MARY'S
SUITE 1225
SAN ANTONIO, TX 78205
WWW.RDMENGINEERING.NET
PHONE: 210.299.4522
FAX: 210.299.4525

Approved: Assistant Director	Approved: Chief of Staff	Approved: Chief, Engineering
Approved: Service Chief	Approved: Service Chief	Approved: Service Chief
Approved: Chief, Biomed	Approved: Chief, EMS	Approved: Chief, Infection Control
Approved: Chief, IT	Approved: Chief, M & O	Approved: Chief, Police
Approved: Chief, Safety	Approved: Chief	Approved: Chief

ARCHITECT:

WESTEAST DESIGN GROUP

1617 E. COMMERCE ST., SUITE 7102, SAN ANTONIO, TEXAS 78205 USA
210.530.0755 FAX 210.530.9427

These documents can not be copied or reproduced without written consent from WestEast Design Group

Drawing Title

FIRST FLOOR MECHANICAL PLAN

Approved: Project Director

Project Title

POLYTRAUMA
TRANSITIONAL
HOUSING

Location
Audie L. Murphy Memorial Veterans Hospital
San Antonio, Texas
Date
28 JULY 2010
Checked
Drawn

Project Number
671-237
Building Number
1
Drawing Number
MH1.1
Dwg. 2 of 10

Office of
Facilities
Management

Department of
Veterans Affairs