

<b>Manufacturer</b>	<b>John Deere</b>
<b>Model</b>	<b>X300 series (X370)</b>
<b>Engine</b>	
Power	18.5 hp 13.8 kW
Displacement	36.8 cu in. 603 cc
Manufacturer/model	FS600V
Type	OHV, oil filter
Cylinders	V-twin, cast-iron liners
Governor	Mechanical
Choke/speed control	Separate levers, automatic choke return
Cooling method	Air
Air cleaner	Dry, replaceable with foam precleaner
Oil drain	No tools
<b>Fuel system</b>	
Type	Gasoline
Fuel delivery	Pulse pump, carburetor
Fuel gauge	No, translucent fuel tank
Fuel tank location	Rear
Fuel fill opening	On left fender, 3 in. 7.6 cm
Fuel tank capacity	3.3 U.S. gal. 12.5 L
<b>Electrical system</b>	
Battery	12 V 340 CCA
Charging system	Flywheel alternator, regulated, 15 amp
Engine starter	---
Hourmeter	Yes
Headlights	Yes
Taillights or reflector	No
Backup lights	No
Rear work lights	No
12-V outlet	Optional
<b>Transaxle</b>	
Type	K58 hydrostatic integrated with transmission
Control	Twin Touch™ pedals
Cruise control	Standard
Oil cooler	Fins and fan on transaxle

Oil filter	Yes, internal
Differential lock	No
Forward speed	0-5.8 mph 0-9.3 km/h
Reverse speed	0-3.5 mph 0-5.6 km/h
Brakes	Internal wet disc
<b>Chassis</b>	
Frame	Welded heavy-duty
Primer/paint	E-coat/powder
Weight bracket	Standard rear, optional front
Receiver hitch	No
Front axle	Cast iron
Spindle bushings	Metal, replaceable
Front tires	15x6-6
Rear tires	20x10-8
Hood material	Molded-in color
Fender deck material	Stamped steel
Floor mats	Sure-grip rubber
Storage	On fender and under seat
Service interval decal	Yes
Fender handles/grips	No
Cup holder	Yes
Equipment mounting	Yes, heavy duty
<b>Steering</b>	
Type	Power, hydraulic
All-wheel steer	Not available on this model
Steering wheel	---
Tilt steering wheel	No
Turning radius	22 in. 55.9 cm
Uncut circle radius	31.6 in. 80.3 cm
<b>Seat</b>	
Type	Open-back
Seat back height	15 in. 38.1 cm
Armrests	No
Fore-aft adjustment	While seated, 7 in. 17.8 cm
Seat suspension	Two coil springs, three-position no-tools adjustment for operator weight
<b>Lift system</b>	
Type	Hydraulic

Hydraulic outlets	No
Mower cut height	13 positions, 1-4 in. 2.5-10.2 cm
Cut height increments	0.25 in. 0.64 cm
Preset cut height	Yes
<b>Mower deck</b>	
Type	Side discharge
Cutting width	42 in. 107 cm
Construction	Stamped steel deck shell
Mower deck material	12 gauge 0.105 in. 2.7 mm
Mower wash port	Yes
Mower drive system	In-line belt, electric PTO
Mower wheels	Two
Mower wheel adjustment	Four-position, tool required
Mower level adjustment	Exact Adjust ports and onboard deck-leveling gauge
<b>Mower attachability</b>	
Type	Slide under tractor
Front draft arms	Two-point mounting
Rear draft arms	Two pins and spring clips
Mower wheels rotate	No
Drive system	Single belt
<b>Safety</b>	
Meets ANSI standard	Yes
Meets OPEI standard	Yes
Backup protection	Reverse Implement Option (RIO)
Safety video	Yes
<b>Buyer's notes</b>	
Notes	Hydraulic power lift for superior convenience and ease of use Power steering for exceptional maneuverability and comfort
Warranty	4 year/300 hour bumper-to-bumper* (*Term limited to years or hours used, whichever comes first, and varies by model. See the LIMITED WARRANTY FOR NEW JOHN DEERE TURF AND UTILITY EQUIPMENT at JohnDeere.com or JohnDeere.ca/TUWarranty for details.)

Other equipment	---
Tow-behind tools	16
Dimensions	
Height	43 in. 109.2 cm
Overall length	72 in. 182.9 cm
Wheelbase	49.4 in. 125.5 cm
Width with mower	53 in. 134.6 cm
Width with mower (deflector raised for storage)	44 in. 111.8 cm
Width without mower	38 in. 96.5 cm
Weight	Mower, no fuel, 576 lb 261.3 kg
Date collected	04-May-2015

Specifications are based on published information at the time of publication. Specifications are subject to change without notice.

Prices are subject to change without notice. Prices are in dollars and only applicable to products sold in the United States. In all cases, current published price lists and incentive program bulletins will take precedence. All trademarked terms, including John Deere, the leaping deer symbol and the colors green and yellow used herein are the property of Deere & Company, unless otherwise noted.