

## Salient Characteristics

CLIN	Description
0001 – 4001, 0002 – 4002, 0004 – 4004, 0012 – 4012, 0015 – 4015	<p>Salient Characteristics:</p> <ul style="list-style-type: none"> <li>• Modes of Operation <ul style="list-style-type: none"> <li>○ Low Air Loss</li> <li>○ Alternating (1-2 alternation)</li> <li>○ Alternating with Low air loss</li> <li>○ Immersion Mode</li> <li>○ Auto Firm</li> </ul> </li> <li>• Cycle time adjustments of 5, 10, and 15 minutes</li> <li>• Must have control lockout button</li> <li>• Must be able to adjust treatment to Height/Weight of patient (weight range should be 100-900 lbs)</li> <li>• Must be able to adjust cell pressure manually (with range of at least 15mmHg to 50mmHg) <ul style="list-style-type: none"> <li>○ Must have digital read out of current pressure</li> </ul> </li> <li>• Minimum of 20 air cells with at least 2 zones</li> <li>• Power failure and Low Pressure alarms</li> <li>• Airflow of 25LPM minimum</li> <li>• 9" height (no taller, current fitted hospital sheets will not accommodate anything taller)</li> <li>• Quick release CPR Valve</li> <li>• Transport mode (prevents air loss)</li> <li>• Foam base layer minimum 2" thickness (in case of power failure or low pressure)</li> </ul>
0003 – 4003 & 0014 - 4014	<p>Salient Characteristics:</p> <ul style="list-style-type: none"> <li>• Must have Expandable Deck Width 39" – 42" - 48"</li> </ul>
0005 – 4005, 0016 – 4016, 0006 – 4006, 0017 - 4017	<p>Salient Characteristics:</p> <ul style="list-style-type: none"> <li>• Surface width must be 48" in width</li> <li>• 1000lb patient weight capacity</li> <li>• Following therapy modes must be available <ul style="list-style-type: none"> <li>○ Zoned low air loss</li> <li>○ Pulsating low air loss (3,5 or 10minuteinterval settings)</li> <li>○ Continuous lateral rotation (1-30</li> </ul> </li> </ul>

## Salient Characteristics

	<ul style="list-style-type: none"> <li>interval setting) <ul style="list-style-type: none"> <li>○ 40 degree rotation</li> <li>○ Position hold assist</li> </ul> </li> <li>• Alarms for low pressure or power failure</li> <li>• Quick release CPR valve</li> </ul>
0007 – 4007 & 0018 - 4018	<p>Salient Characteristics:</p> <ul style="list-style-type: none"> <li>• Must have Automatic Base Width Adjustability</li> <li>• Must be Battery Powered with Internal Charger</li> <li>• Minimum 750/1,000 lb. Weight Capacity</li> <li>• Desired Extra-long Mast System for Higher Lift Capacity <ul style="list-style-type: none"> <li>• Height max must be at least 90”</li> <li>• Emergency release</li> <li>• Integrated scale</li> <li>• Must accommodate loop based slings</li> <li>• Lift base must have adjustable width</li> <li>• Front legs of base must have dual casters on both sides</li> </ul> </li> </ul>
0008 – 4008 & 0019 - 4019	<p>Salient Characteristics:</p> <ul style="list-style-type: none"> <li>• Must have Swivel Locking Casters in Rear <ul style="list-style-type: none"> <li>• Seat width: at least 29”</li> <li>• Seat depth: at least 21”</li> </ul> </li> <li>• Desired Two Rigid Locking Casters in Front</li> <li>• Required Removable Back</li> <li>• Must have Breakaway Foot Rest</li> <li>• Required Pushbar for Caregiver Safety</li> <li>• Available IV Poles, O2 Tank Holders &amp; Drainage Bag Holders</li> <li>• Required 750 lb. Weight Capacity</li> </ul>
0009 – 4009 & 0020 - 4020	<p>Salient Characteristics:</p> <ul style="list-style-type: none"> <li>• Wheels Must allow for Easy Transport to Shower, Over Toilet or at Bedside</li> <li>• Required Removable Back &amp; Arm Rest</li> <li>• Must have Locking Front Casters</li> <li>• Desired Stainless Steel Construction</li> <li>• Required Commode Pail</li> <li>• Must have Seat Depth of at least 20”</li> </ul>
0010 – 4010 & 0021 - 4021	<p>Salient Characteristics:</p> <ul style="list-style-type: none"> <li>• Required Adjustable Height from 31” to 39” in one Inch Increments</li> <li>• Minimum of 37” Width between Grips/Support</li> <li>• Desired 750 lb. Minimum Weight Capacity</li> </ul>
0011 – 4011	<p>Salient Characteristics:</p>

## Salient Characteristics

<p>&amp; 0022 - 4022</p>	<ul style="list-style-type: none"><li>• Must Transform from Chair to Stretcher</li><li>• Required AC and Fully Powered Articulation with Electrical Hand Control</li><li>• Must have Adjustable Arm Rests</li><li>• Must have Independent and Elevating Leg Supports</li><li>• Required Self-Retracting Foot Rests</li><li>• Must have All-swivel Wheels</li><li>• Required Trendelenburg/Reverse Trendelenburg with at least 15 degrees of tilt</li><li>• Desired Stand/Seat Assist</li><li>• Desired Storable IV Pole and Transport Basket Included</li><li>• Must have Radiolucent Back</li><li>• Must have Rechargeable Battery and O2 Holder</li><li>• Required Chair Position, Stretcher Position, Adjustable Length</li><li>• Required 1,000 lb. Weight Capacity<ul style="list-style-type: none"><li>• Minimum seat width: 31"</li><li>• Minimum seat depth: 19"</li></ul></li></ul>
------------------------------	--