

**SECTION 32 31 13**  
**CHAIN LINK FENCES AND GATES**

**PART 1 - GENERAL****1.1 DESCRIPTION**

This work consists of all labor, materials, and equipment necessary for furnishing and installing chain link fence, gates and accessories in conformance with the lines, grades, and details as shown.

**1.2 RELATED WORK**

- A. Temporary Construction Fence: Section 01 00 00, GENERAL REQUIREMENTS.
- B. Finish Grading: Section 31 20 11, EARTH MOVING, and Section 32 90 00, PLANTING.
- C. Security fences: Section 32 31 53, PERIMETER SECURITY FENCES AND GATES.

**1.3 MANUFACTURER'S QUALIFICATIONS**

Fence, gates, and accessories shall be products of manufacturers' regularly engaged in manufacturing items of type specified.

**1.4 SUBMITTALS**

- A. In accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES, furnish the following:
  - 1. Manufacturer's Literature and Data: Chain link fencing, gates and all accessories.
  - 2. Manufacturer's Certificates: Zinc-coating complies with specifications.
- B. Shop Drawings for fencing components and appurtenances.

**1.5 APPLICABLE PUBLICATIONS**

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American Society for Testing and Materials (ASTM):
  - A392-07.....Zinc-Coated Steel Chain-Link Fence Fabric
  - C94/C94M-07.....Ready-Mixed Concrete
  - F567-07.....Installation of Chain-Link Fence
  - F626-(R2003).....Fence Fittings
  - F900-05.....Industrial and Commercial Swing Gates
  - F1043-06.....Strength and Protective Coatings on Metal  
Industrial Chain-Link Fence Framework
  - F1083-08.....Pipe, Steel, Hot-Dipped Zinc-Coated  
(Galvanized) Welded, for Fence Structures.
- C. Federal Specifications (Fed. Spec.):

FF-P-110J.....Padlock, Changeable Combination

## **PART 2 - PRODUCTS**

### **2.1 GENERAL**

Materials shall conform to ASTM F1083 and ASTM A392 ferrous metals, zinc-coated; and detailed specifications forming the various parts thereto; and other requirements specified herein. Zinc-coat metal members (including fabric, gates, posts, rails, hardware and other ferrous metal items) after fabrication shall be reasonably free of excessive roughness, blisters and sal-ammoniac spots.

### **2.2 CHAIN-LINK FABRIC**

ASTM A392 vinyl coated 9 gauge wire woven in a 45 mm (1 3/4 inch) mesh. Top and bottom selvage shall have twisted and barbed finish.

### **2.3 POST, FOR GATES AND FENCING**

ASTM F1083, Grade SK-40A, round, zinc-coated steel. Dimensions and weights of posts shall conform to the tables in the ASTM Specification. Provide post braces and truss rods for each gate, corner, pull or end post. Provide truss rods with turnbuckles or other equivalent provisions for adjustment.

### **2.4 TOP RAIL, INTERMEDIATE RAIL AND BOTTOM RAIL**

ASTM F1083, Grade SK-40A, round, zinc-coated steel. Dimensions and weights of posts shall conform to the tables in the ASTM Specification; fitted with suitable expansion sleeves and means for securing rail to each gate, corner, and end posts.

### **2.5 TOP AND BOTTOM TENSION WIRE**

This section is not applicable for this project.

### **2.6 ACCESSORIES**

Accessories as necessary caps, rail and brace ends, wire ties or clips, braces and tension bands, tension bars, truss rods, and miscellaneous accessories conforming to ASTM F626

### **2.7 RAZOR WIRE SUPPORT ARMS**

ASTM F626, single arm type, steel or malleable iron.

### **2.8 RAZOR WIRE**

ASTM A121, zinc-coated steel wire and barbs; standard size and construction: 2.51 mm (0.099 inch) diameter line wire with 2.03 cm (0.080 inch) diameter, 2-point barbs.

### **2.9 GATES**

ASTM F900, type as shown. Gate framing, bracing, latches, and other hardware zinc-coating weight shall be the same as the FABRIC. Gates

less than 2400 mm (8 feet) wide shall have truss rods or intermediate braces. Attach gate fabric to the gate frame by method standard with the manufacturer, except that welding will not be permitted. Arrange latches for padlocking so that padlock will be accessible from both sides of the gate regardless of the latching arrangement. Provide supports at top of gate to accommodate razor wire. Gates shall swing inward.

#### **2.10 GATE HARDWARE**

- A. Manufacturer's standard products, installed complete. The type of hinges shall allow gates to swing through 180 degrees, from closed to open position. Hang and secure gates in such a manner that, when locked, they cannot be lifted off hinges.
- B. Provide stops and keepers for all double gates. Latches shall have a plunger-bar arranged to engage the center stop. Arrange latches for locking. Center stops shall consist of a device arranged to be set in concrete and to engage a plunger bar. Keepers shall consist of a mechanical device for securing the free end of the gate when in full open position.
- C. Equip gate openings with padlock conforming to Fed Spec FF-P-110H, Type EPC, size 50 mm (2 inch). Padlocks shall have chains that are securely attached to the gate or gate post. Before padlocks are delivered to project, submit sample to Resident Engineer for approval. Approved sample may be incorporated in work. Key padlock as directed by the Resident Engineer.

#### **2.11 CONCRETE**

ASTM C94/C94M, using 19 mm (3/4 inch) maximum-size aggregate, and having minimum compressive strength of 25 mPa (3000 psig) at 28 days. Non-shrinking grout shall consist of one part Portland cement to three parts clean, well-graded sand, non-shrinking grout additive and the minimum amount of water to produce a workable mix.

### **PART 3 - EXECUTION**

#### **3.1 INSTALLATION**

- A. Install fence by properly trained crew, on previously prepared surfaces, to line and grade as shown. Install fence in accordance with ASTM F567 and with the manufacturer's printed installation instructions, except as modified herein or as shown. Maintain all equipment, tools, and machinery while on the project in sufficient

quantities and capacities for proper installation of posts, chain links and accessories.

### **3.2 EXCAVATION**

Excavation for concrete-embedded items shall be of the dimensions shown, except in bedrock. If bedrock is encountered before reaching the required depth, continue the excavation to the depth shown or 450 mm (18 inches) into the bedrock, whichever is less, and provide a minimum of 50 mm (2 inches) larger diameter than the outside diameter of the post. Clear loose material from post holes. Grade area around finished concrete footings as shown and dispose of excess earth as directed by the Resident Engineer.

### **3.3 POST SETTING**

Install posts plumb and in alignment. Set post in concrete footings of dimensions as shown, except in bedrock. Thoroughly compact concrete so as it to be free of voids and finished in a slope or dome to divert water running down the post away from the footing. Install posts in bedrock with a minimum of 25 mm (one inch) of non-shrinking grout around each post. Thoroughly work non-shrinking grout into the hole so as to be free of voids and finished in a slope or dome. Cure concrete and grout a minimum of 72 hours before any further work is done on the posts.

### **3.4 POST CAPS**

Fit all exposed ends of post with caps. Provide caps that fit snugly and are weathertight. Where top rail is used, provide caps to accommodate the top rail. Install post caps as recommended by the manufacturer and as shown.

### **3.5 SUPPORTING ARMS**

Design supporting arms, when required, to be weathertight. Where top rail is used, provide arms to accommodate the top rail. Install supporting arms as recommended by the manufacturer and as shown.

### **3.6 TOP RAILS AND BOTTOM RAILS**

Install rails before installing chain link fabric. Provide suitable means for securing rail ends to terminal and intermediate post. Top rails shall pass through intermediate post supporting arms or caps as shown. The rails shall have expansion couplings (rail sleeves) spaced as recommended by the manufacturer.

**3.7 ACCESSORIES**

Supply accessories (posts braces, tension bands, tension bars, truss rods, and miscellaneous accessories), as required and recommended by the manufacturer, to accommodate the installation of a complete fence, with fabric that is taut and attached properly to posts, rails, and tension wire.

**3.8 FABRIC**

Pull fabric taut and secured with wire ties or clips to the top rail, bottom rail, and intermediate rail close to both sides of each post and at intervals of not more than 600 mm (24 inches) on centers. Secure fabric to posts using stretcher bars and ties or clips.

**3.9 RAZOR WIRE**

Install razor wire, when required, on supporting arms above the fence posts. Extend each end member of gate frames sufficiently above the top member to carry razor wire in horizontal alignment with razor wire on the fence.

**3.10 GATES**

Install gates plumb, level, and secure for full opening without interference. Set keepers, stops and other accessories into concrete as required by the manufacturer and as shown. Adjust hardware for smooth operation and lubricate where necessary.

**3.11 REPAIR OF GALVANIZED SURFACES**

Use galvanized repair compound, stick form, or other method, where galvanized surfaces need field or shop repair. Repair surfaces in accordance with the manufacturer's printed directions.

**3.12 FINAL CLEAN-UP**

Remove all debris, rubbish and excess material from the station.

- - - E N D - - -