

DEPARTMENT OF VETERANS AFFAIRS

LEBANON HEALTH CARE SYSTEM

1700 SOUTH LINCOLN AVENUE LEBANON, PA 17042



STORMWATER
MANAGEMENT
IMPROVEMENTS
PROJECT #595-11-133



DRAWING INDEX

- CS-1 COVER SHEET
- SP-1 OVERALL SITE PLAN
- C-1 PARTIAL STORMWATER IMPROVEMENT PLAN
- C-2 PARTIAL STORMWATER IMPROVEMENT PLAN
- C-3 PARTIAL STORMWATER IMPROVEMENT PLAN
- C-4 PARTIAL STORMWATER IMPROVEMENT PLAN
- C-5 PARTIAL STORMWATER IMPROVEMENT PLAN
- C-6 PARTIAL STORMWATER IMPROVEMENT PLAN
- C-7 PARTIAL STORMWATER IMPROVEMENT PLAN

- CG-1 RETENTION BASIN GRADING AND LANDSCAPING
- CG-2 RETENTION BASIN GRADING AND LANDSCAPING
- D-1 SITE DETAILS
- D-2 E&S NOTES AND DETAILS
- D-3 PIPE PROFILE AND ROADWAY SECTIONS
- D-4 DRAINAGE DETAILS
- D-5 RETENTION BASIN DETAILS






BID DOCUMENTS








4114COVR


| Drawing Title COVER SHEET | Medica STORMWATER | NON VA 1 Center 2 MANAGE VEMENTS | |
|----------------------------|----------------------|---|-------------|
| | Lebar | non, PA | |
| | Date 04-20-12 | Checked DK | Drawn LB |
































GENERAL DESCRIPTION

 THE DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP) OF THE COMMONWEALTH OF PENNSYLVANIA REQUIRES THE PREPARATION AND IMPLEMENTATION OF A PLAN FOR THE PREVENTION OF ACCELERATED SOIL EROSION AND SEDIMENTATION OF THE STREAMS OF THE COMMONWEALTH UNDER TITLE 25, CHAPTER 102 OF THEIR REGULATIONS. SUCH PLANS ARE REQUIRED FOR ALL EARTHMOVING ACTIVITIES AND IT IS INTENDED THAT THIS PLAN WILL FULFILL THIS DEP

2. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IMPLEMENT THIS PLAN IN THE FIELD AND MEET ALL STATE AND LOCAL REGULATIONS. THE CONTRACTOR SHALL ASSIGN THIS RESPONSIBILITY TO A PERSON EXPERIENCED IN SEDIMENT AND EROSION CONTROL PROCEDURES. MODIFICATIONS OR DEVIATIONS FROM THIS PLAN WILL BE ALLOWED ONLY IF THE CONTRACTOR FIRST OBTAINS WRITTEN APPROVAL FROM DEP.

APPLICABLE STANDARDS

SOIL EROSION AND SEDIMENTATION CONTROL MANUAL: 1. PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL

REQUIREMENT AND PREVENT SEDIMENTATION.

STANDARD CONDITIONS RELATING TO DEP WATER QUALITY MANAGEMENT PERMITS

THE CONTRACTOR SHALL FAMILIARIZE HIMSELF AND SHALL BE RESPONSIBLE FOR CARRYING OUT ALL REQUIREMENTS STATED IN THE STANDARD CONDITIONS RELATING TO EROSION CONTROL WHICH ARE ATTACHED TO THE DEP WATER MANAGEMENT PERMIT ISSUED THE OWNER FOR THE CONSTRUCTION OF THIS PROJECT.

PRODUCTS

PROTECTION.

ALL PRODUCTS AND MATERIALS SHALL MEET THE REQUIREMENTS OF THE LOCAL CONSERVATION DISTRICT OR AS SPECIFIED ELSEWHERE IN THESE SPECIFICATIONS.

PROJECT DESCRIPTION

1. THE PROJECT IS LOCATED ON THE VA LEBANON CAMPUS OFF STATE DRIVE. THE PROJECT WILL INVOLVE THE UPGRADING OF EXISTING STORMWATER FACILITIES AND PLACEMENT OF BIO RETENTION PONDS WITH PLANTINGS.

2. THIS PROJECT INCLUDES AN EROSION AND SEDIMENT POLLUTION CONTROL PLAN.

THE PROPOSED EROSION AND SEDIMENT POLLUTION CONTROL PLAN HAS BEEN DESIGNED TO PREVENT THE LOSS OF SOIL COVER DURING THE SITE CONSTRUCTION AND DEVELOPMENT PHASE OF THIS PROJECT. THE PLAN INCLUDES A SEQUENCE OF CONSTRUCTION ACTIVITIES, TEMPORARY AND PERMANENT EROSION CONTROL MEASURES, AND A MAINTENANCE PLAN TO INSURE THE PROPER OPERATION OF THE TEMPORARY AND PERMANENT CONTROLS PROPOSED FOR THIS PROJECT.

4. CONSTRUCTION OF THIS PROJECT IS SCHEDULED TO BEGIN IN AUGUST, 2012 WITH COMPLETION PLANNED FOR NOVEMBER. 2012. THE SEQUENCING OF CONSTRUCTION ACTIVITIES PROVIDES THAT AS AREAS ARE BROUGHT TO PROPOSED GRADE, FINAL SOIL STABILIZATION MEASURES WILL BE INITIATED. THROUGHOUT THE DURATION OF THE PROJECT, CONSTRUCTION AREAS LEFT EXPOSED WILL BE SEEDED AND MULCHED IMMEDIATELY.

5. RECEIVING WATERSHED IS A TRIBUTARY TO SNITZ CREEK: CHAPTER 93 RECEIVING WATER CLASSIFICATION IS "CWF" COLD WATER FISH.

6. ANY AND ALL WASTE FROM THIS PROJECT WILL BE DISPOSED OF PER D.E.P. SOLID WASTE REGULATIONS.

TOPOGRAPHIC FEATURES OF THE AREA

THE EROSION AND SEDIMENT POLLUTION CONTROL PLAN DESCRIBES THE PROJECT AREA. CONTOURS AT 2 FOOT INTERVALS ARE SHOWN ON THE PLAN AS WELL AS PROPERTY BOUNDARY LINES AND OTHER PHYSICAL FEATURES. SOIL TYPES ARE ALSO INDICATED IN THIS REPORT.

DESIGN CRITERIA

THE METHOD USED IN DESIGNING SEDIMENT CONTROL MEASURE WAS TAKEN FROM EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL DATED 2000.

STAGE OF CONSTRUCTION ACTIVITIES

1. WORK AREAS ARE DISIGNATED ON DRAWING SP-1.

2. THE BIO-RETENTION PONDS CAN BE CONSTRUCTED SIMULTANEOUSLY OR SEQUENTIALLY AT THE CONTRACTORS

3. THE SWALE LEADING TO BIO-RETENTION POND NO. 1 SHALL BE DONE CONCURRENTLY WITH THE POND.

4. THERE ARE FOUR LOCATIONS OF STORMWATER PIPING SYSTEM REPLACEMENT. THESE LOCATIONS ARE IN WORK AREA NO. 1 AND ARE EACH IN WORK AREA'S NO. 2 AND NO. 3. THESE FOUR LOCATIONS MUST BE COMPLETED SEQUENTIALLY. THE ORDER IN WHICH THE CONSTRUCTION IS SEQUENCED SHALL BE APPROVED BY THE V.A. ONE LOCATION MUST BE COMPLETED BEFORE WORK ON THE NEXT LOCATION

COMMENCES. 5. ANY WORK THAT AFFECTS THE MAIN ACCESS DRIVE OFF STATE ROAD OR THE CAMPUS LOOP ROAD MUST BE DONE IN NON-TRADITIONAL WEEKDAY HOURS OR ON THE WEEKEND, ONE

LANE MUST BE ACCESSIBLE FOR PASSAGE AT ALL TIMES.

TEMPORARY CONTROL MEASURES

MAINTENANCE PROGRAM

1. ALL TEMPORARY MEASURES IN THIS PLAN ARE TO BE USED TO MINIMIZE EROSION OF THE CONSTRUCTION AREAS AND TO REDUCE SILTATION DOWNSTREAM FROM THE WORK AREAS.

2. AREAS DISTURBED BY CONSTRUCTION WHICH CANNOT BE BROUGHT TO FINAL GRADE WILL BE IMMEDIATELY STABILIZED USING A TEMPORARY COVER.

3. THIS TEMPORARY COVER IS TO BE AN ANNUAL RYE GRASS SEEDED AT THE RATE OF 50 POUNDS PER ACRE AND MULCHED WITH HAY OR STRAW AT THE RATE OF 3 TONS PER ACRE.

1. MAINTENANCE OF BOTH THE TEMPORARY AND PERMANENT EROSION CONTROL MEASURES IS NECESSARY TO MAINTAIN

THEIR EFFECTIVENESS. THE FILTER FABRIC IS TO BE CHECKED AFTER EACH RUNOFF FOR STRUCTURAL PROBLEMS AND SILTATION. BARRIERS SHOULD BE CLEARED WHEN THE DEPTH OF SEDIMENT REACHES ONE-THIRD THE HEIGHT OF THE

2. AREAS WHERE PERMANENT VEGETATION HAS BEEN INSTALLED MUST BE CHECKED MONTHLY THROUGH THE GROWING SEASON TO INSURE THAT AN ADEQUATE STAND IS DEVELOPING. MAINTENANCE COULD INCLUDE RESEEDING, REMULCHING, AND MATTING OF POORLY DEVELOPED SECTION.

3. ALL AREAS THAT REQUIRE STONE PROTECTION TO REDUCE EROSION SHOULD BE CHECKED AFTER EACH RUNOFF. AREAS WHERE STONE HAS BEEN DISPLACED OF DISLODGED FROM ITS ORIGINAL POSITION SHOULD BE REPLACED WITHIN A WEEK BETWEEN THE TIME OF THE EVENT AND THE TIME OF RESTORATION.

4. ANY AREAS TO BE SEEDED, THAT CANNOT BE SEEDED BY NOVEMBER 15TH WILL BE MULCHED WITH HAY OR STRAW AT THE RATE OF 3.0 TONS PER ACRE AND ALL INTERIM EROSION AND SEDIMENT POLLUTION CONTROLS SHALL BE MAINTAINED UNTIL THE FOLLOWING SUITABLE SEEDING SEASON. ALL AREAS MUST HAVE ALL CONTROLS MAINTAINED UNTIL THE SITE IS PERMANENTLY STABILIZED.

STABILIZED ROCK ENTRANCE ROAD PAD

1. CONSTRUCT STABILIZED CONSTRUCTION PADS AT THE LOCATIONS SHOWN ON THE PLANS, AND/OR DESIGNATED IN THE SEQUENCE OF CONSTRUCTION ACTIVITIES.

2. EXCAVATE THE AREA SHOWN ON THE PLANS TO A DEPTH OF 6" AT THE ENTRANCE POINT TO THE CONSTRUCTION AREA. REMOVE EXCAVATED MATERIAL AND TRANSPORT TO A PREPARED SUBGRADE.

3. PLACE A BARRIER MAT OF CLASS 4 GEOTEXTILE ON THE PREPARED SUBGRADE.

4. PROVIDE A SIX INCH DEPTH OF 3 INCH DIAMETER ROCK.

5. PERIODICALLY INSPECT THE ROCK TO DETERMINE WHETHER CLOGGING OF MATERIAL HAS REDUCED THE EFFICIENCY OF THE STABILIZED CONSTRUCTION ENTRANCE PAD.

6. REPLACE ROCK MATERIAL WHEN MATERIAL DOES NOT ADEQUATELY REMOVE MUD FROM VEHICLE WHEELS. ALSO REMOVE SEDIMENT FROM LOCAL ROADWAY AS IT BECOMES

INSTALLATION OF CLASS 4 GEOTEXTILE MATERIAL (S.Y.) (AS PER PG. 212, PENNSYLVANIA DEPARTMENT OF TRANSPORTATION STANDARD 408 AND APPLICABLE ROADWAY CONSTRUCTION

TEMPORARY SEEDING

1. ALL AREAS TO BE PREPARED AND SEEDED ACCORDING TO THE FOLLOWING RATES. ANY AREA RECEIVING TEMPORARY SEEDING WHICH WILL BE LEFT FOR A PERIOD LONGER THAN ONE YEAR SHALL BE SEEDED WITH THE PERMANENT SEEDING

A. FERTILIZER: FERTILIZE AT THE FOLLOWING RATES: 50 LB. OF N PER ACRE 50 LB. OF P205 PER ACRE 50 LB. OF K20 PER ACRE

B. LIME: AGRICULTURAL GRADE LIME AT RATE OF 1 TON PER

C. SEED: SEED WEIGHTS GIVEN BELOW ARE PLS (PURE LIVE

1. FOR SPRING SEEDING (UP TO JUNE 15) ANNUAL RYEGRASS 40 #/ACRE OR WINTER RYE 168 #/ACRE OR SPRING OATS PLUS

OR WINTER RYE 168 #/ACRE

ANNUAL RYEGRASS 64 #/ACRE OATS 20 #/ACRE RYEGRASS 2. FOR LATE SPRING AND SUMMER SEEDING (JUNE 16 TO

SUDANGRASS 40 #/ACRE OR ANNUAL RYEGRASS 40 #/AREA 3. FOR LATE SUMMER AND FALL (BEYOND AUGUST 15) ANNUAL RYEGRASS 40 #/ACRE

OR WINTER WHEAT 180 #/ACRE D. MULCH: STRAW OR HAY AT RATE OF 3 TONS PER ACRE.

PERMANENT SEEDING

AUGUST 15)

1. ALL AREAS TO BE SEEDED ACCORDING TO THE FOLLOWING RATES. MULCH IS TO BE USED AS NECESSARY FOR EROSION PROTECTION UNTIL SEEDING IS ESTABLISHED.

A. TOPSOIL: FREE OF SUBSOIL, CLAY OR IMPURITIES, PLANTS, WEEDS AND ROOTS: pH VALUE MINIMUM 5.4 AND MAXIMUM 7.0. B. FERTILIZER: TYPE 1, GRADE A AS REQUIRED TO ELIMINATE ANY DEFICIENCIES OF TOPSOIL AS INDICATED BY SOIL

ANALYSIS. MINIMUM FERTILIZER APPLICATION RATE: 100 LB. OF N PER ACRE 200 LB. OF P205 PER ACRE

200 LB. OF K20 PER ACRE

REDTOP: 3 LB PER ACRE

C. PERMANENT SEED: SEED WEIGHTS GIVEN BELOW ARE PLS (PURE LIVE SEED)

MOWABLE AREA: KENTUCKY BLUE GRASS: 25 LB PER ACRE RED TOP: 3 LB PER ACRE NORLEA PERENNIAL RYE: 15 LB PER ACRE

BIRDSFOOT TREFOIL: 6 LBS PER ACER EMBANKMENT AREAS (DIVERSIONS AND SLOPES GREATER THAN BÍRDSFOOT TREFOIL: 6 LB PER ACRE REED CANARYGRASS: 10 LB PER ACRE

D. MULCH: OAT OR WHEAT STRAW, FREE FROM WEEDS, FOREIGN MATTER DETRIMENTAL TO PLANT LIFE AT A RATE OF 3 TONS

E. LIME: AGRICULTURAL GRADE LIME AT A RATE CALCULATED FROM THE SOILS TEST TO BRING THE SOIL pH WITHIN 5.5 TO 6.0 APPLY AGRICULTURAL GRADE LIME AT A RATE OF 6 TONS

STANDARD EROSION AND SEDIMENT CONTROL PLAN NOTES 102.2(A) "THIS CHAPTER REQUIRES PERSONS PROPOSING OR CONDUCTING EARTH DISTURBANCE ACTIVITIES TO DEVELOP, IMPLEMENT AND MAINTAIN BMP'S TO MINIMIZE THE POTENTIAL

PER ACRE IN THE ABSENCE OF A SOILS TEST.

FOR ACCELERATED EROSION AND SEDIMENTATION." 102.4(B)(3) "THE EROSION AND SEDIMENT CONTROL PLAN SHALL BE PREPARED BY A PERSON TRAINED AND EXPERIENCED IN EROSION AND SEDIMENT CONTROL METHODS AND

TECHNIQUES, AND SHALL BE DESIGNED TO MINIMIZE THE POTENTIAL FOR ACCELERATED EROSION AND SEDIMENTATION." 1. VEHICLES AND EQUIPMENT MAY ONLY ENTER THE PROJECT

SITE AT THE ROCK CONSTRUCTION ENTRANCE LOCATION. 2. THE OPERATOR SHALL ASSURE THAT THE APPROVED

EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND

COMPLETELY IMPLEMENTED.

3. UNTIL THE SITE ACHIEVES FINAL STABILIZATION, THE OPERATOR SHALL ASSURE THAT THE BEST MANAGEMENT PRACTICES ARE IMPLEMENTED, OPERATED, AND MAINTAINED PROPERLY AND COMPLETELY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL BEST MANAGEMENT PRACTICE FACILITIES AND MAINTAIN AND MAKE AVAILABLE TO LACKAWANNA COUNTY CONSERVATION DISTRICT COMPLETE, WRITTEN INSPECTION LOGS OF ALL THOSE INSPECTIONS. ALL MAINTENANCE WORK, INCLUDING CLEANING, REPAIR, REPLACEMENT, REGARDING, AND RESTABILIZATION SHALL BE PERFORMED IMMEDIATELY.

4. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.

5. BEFORE INITIATING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE LACKAWANNA CONSERVATION DISTRICT.

6. THE OPERATOR SHALL ASSURE THAT AN EROSION AND SEDIMENT CONTROL PAN HAS BEEN PREPARED, APPROVED BY THE LACKAWANNA CONSERVATION DISTRICT, AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL SOIL AND/OR ROCK SPOIL AND BORROW AREAS, REGARDLESS OF THEIR LOCATIONS.

7. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS SO THE APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1 DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUBPART C. PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL.

8. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT

102.4(B)(5)(I) "THE EXISTING TOPOGRAPHIC FEATURES OF THE PROJECT SITE AND THE IMMEDIATE SURROUNDING AREA."

9. THE E&S CONTROL PLAN MAPPING MUST DISPLAY A PA ONE CALL SYSTEM INCORPORATED SYMBOL INCLUDING THE SITE IDENTIFICATION NUMBER. (THIS IS A NUMBERED SYMBOL NOT A

102.4(B)(5)(VII) "A SEQUENCE OF BMP INSTALLATION AND REMOVAL IN RELATION TO THE SCHEDULING OF EARTH DISTURBANCE ACTIVITIES, PRIOR TO, DURING, AND AFTER EARTH DISTURBANCE ACTIVITIES."

102.4(B)(4) "EARTH DISTURBANCE ACTIVITIES SHALL BE PLANNED AND CONDUCTED TO MINIMIZE THE EXTENT AND DURATION OF EARTH DISTURBANCE."

102.22(A) "UPON COMPLETION OF AN EARTH DISTURBANCE ACTIVITY OR ANY STAGE OR PHASE OF AN ACTIVITY, THE SITE SHALL BE IMMEDIATELY SEEDED, MULCHED OR OTHERWISE PROTECTED FROM ACCELERATED EROSION AND SEDIMENTATION.

10. EROSION AND SEDIMENT BMP MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMPS. E&SPCPM P168

11. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF BMPS MUST BE STABILIZED IMMEDIATELY. E&SPCPM P168

12. AT LEAST 7 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL INVITE ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LANDOWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENT CONTROL PLAN PREPARER, AND THE LACKAWANNA CONSERVATION DISTRICT TO AN ON-SITE MEETING. ALSO, AT LEAST 3 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INCORPORATED AT 1-800-242-1776 FOR BURIED UTILITIES LOCATIONS.

13. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE.

14. IMMEDIATELY AFTER EACH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.

15. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER

TEMPORARY STABILIZATION & PERMANENT STABILIZATION

16. HAY OR STRAW MULCH MUST BE APPLIED AT 3.0 TONS PER ACRE.

17. MULCH WITH MULCH CONTROL NETTING OR EROSION CONTROL BLANKETS MUST BE INSTALLED ON ALL SLOPES 3:1

AND STEEPER. 18. STRAW MULCH SHALL BE APPLIED IN LONG STRANDS, NOT CHOPPED OR FINELY BROKEN.


102.4(B)(5)(X) "A MAINTENANCE PROGRAM WHICH PROVIDES FOR INSPECTION OF BMPS ON A WEEKLY BASIS AND AFTER EACH MEASURABLE RAINFALL EVENT, INCLUDING THE REPAIR OF THE BMPS TO ENSURE EFFECTIVE AND EFFICIENT OPERATION."

19. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT CONTROL BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING, MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENT CONTROL BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED. E&SPCPM P168

20. SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED OR PLACED IN TOPSOIL STOCKPILES.

102.4(B)(5)(XII) "PROCEDURES WHICH ENSURE THAT THE PROPER MEASURES FOR THE RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THE PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH THIS TITLE."

21. THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1, AND 287.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP, OR DISCHARGE ANY BUILDING MATERIAL OR WASTES AT THE SITE.



1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED PREPARE AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.

2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP x 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE BLANKET.


3. ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM IM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE


4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2" - 5" OVERLAP DEPENDING ON BLANKET TYPE.

5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART ACROSS ENTIRE BLANKET WIDTH.

*IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.

> INSTALLATION OF EROSION CONTROL MATTING FOR SLOPE PROTECTION NOT TO SCALE





MESH**


* STAKES SPACED @ 8' MAX. USE 2" x 2" WOOD OR EQUIVALENT STEEL STAKES. **EITHER INDUSTRIAL POLYPROPOLENE OR STEEL MESH WITH 6" MAX. OPENING STEEL MESH SHALL BE 14 GA. MIN.


FILTER FABRIC FENCE MUST BE INSTALLED AT EXISTING LEVEL GRADE. BOTH ENDS OF EACH FENCE SECTION MUST BE EXTENDED AT LEAST 8 FEET UPSLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.

SEDIMENT MUST BE REMOVED WHERE ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF THE FENCE.

ANY FENCE SECTION WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. NOTE: SHOW ALL DETAILS AND CONSTRUCTION DIMENSIONS ON PLAN DRAWINGS.

STANDARD CONSTRUCTION DETAIL #20 (30" HIGH) REINFORCED FILTER FABRIC FENCE






UP-SLOPE FACE SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET, OR REPLACED WITH NEW ROCK.

ROCK FILTER OUTLET

* INSTALL ROCK FILTER OUTLETS AS DIRECTED WHERE SILT FENCING CANNOT HANDLE THE CONDITIONS OF THE SITE, AS DIRECTED IN NOTE OF THE SILT BARRIER FENCE DETAIL.



roject Number

VA PROJ. NO. 595-11-133


D-2

uilding Number(s)


Lamereaux Consulting, LLC Building Construction & Site Design Services 25 South Washington Avenue (570) 876-5350 Jermyn, Pennsylvania 18433 Service Disabled Veteran Owned Small Business














| LOCATION | DESIGN FLOW (CFS) | VELOCITY (FPS) | NORMAL DEPTH (FT) | LINING HEIGHT (FT) | CHANNEL SIDESLOPE (Z) | TRIM AREA (SF) | TURF REINFORCED MAT |
|------------------------|--|-------------------|----------------------|-----------------------|--------------------------|----------------|-----------------------------|
| DA1 EMERGENCY SPILLWAY | 9 | 7.8 | 0.1 | 1 | 4 | 2000 | * NORTH AMERICAN GREEN C350 |
| DA2 EMERGENCY SPILLWAY | 45 | 8.3 | 0.4 | 1 | 4 | 3300 | * NORTH AMERICAN GREEN C350 |
| CH-1 | 20 | 7.5 | 0.5 | 1 | 4 | 5100 | * NORTH AMERICAN GREEN C350 |
| CH-2 | 8 | 2.9 | 0.4 | 1 | 10 | 3325 | * NORTH AMERICAN GREEN C350 |
| CH-3 | NORTH AMERICAN GREEN C125BN OR AN APPROVED BIOPREFFERED EQUIVALENT | | | | | | |
| CH-4 | 19 | 3.2 | 0.7 | 1 | 6 | 1410 | * NORTH AMERICAN GREEN C350 |

DRAINAGE CHANNEL DETAIL

∽6"ø PVC SCH. 40 UNDERDRAIN



BALL OR

CONTAINER

McFarland Johnson

49 COURT STREET, METROCENTER BINGHAMTON, NEW YORK 13901

TEL (607)723-9421 FAX (607)723-4979

CLAY LINER DETAIL

NOT TO SCALE

GENERAL NOTES:

- 1. COMPACTED SOILS SHOULD BE FREE OF ROCK LARGER THAN 2" AND SHOULD BE COMPACTED TO 95%.
- 2. CLAY SOILS SHALL MEET THE FOLLOWING: PERMEABILTY OF 1x10-6. PLASTICITY INDEX OF NOT LESS THAN 15%, LIQUID LIMIT OF NOT LESS THAN 30% AND CLAY COMPACTION NOT LESS THAN 95%. CONTRACTOR MAY SUBSTITUE BENTONITE FOR CLAY.

Lamereaux Consulting, LLC



- LEVEL SHOULDER OF BALL W/ EXISTING GRADE AFTER PLANT HAS FULLY SETTLED, SCARIFY SIDES OF HOLE

-BACKFILL W/ AMENDED PLANTING MIXTURE AS DETERMINED BY SOIL ANALYSIS, SOIL AT BOTTOM HOLE TO BE COMPACTED LOAM BACKFILL

DECIDUOUS TREE PLANTING

SHRUB PLANTING

SCARIFY EXISTING SOIL &

BLEND WITH PLANTING

BARK MULCH

- UNTIE AND ROLL BACK BURLAP

IF SYNTHETIC WRAP IS USED,

REMOVE COMPLETELY

- SLOPE TO FORM SAUCER

— PLANT BACKFILL MIXTURE

MIX 1:1 AND COMPACT

FROM 1/3 OF ROOT BALL (MIN.);

PLAN VIEW


SECTION Y-Y


- GEOTEXTILE

WIDTH

16


(FT)







Service Disabled Veteran Owned Small Business









RETENTION BASIN GENERAL CONSTRUCTION NOTES:

- . CONTRACTOR SHALL PROVIDE PROOF OF PRIOR EXPERIENCE CONSTRUCTING RETENTION BASIN GRADING AND LANDSCAPING ELEMENTS. A MINIMUM OF THREE (3) REFERENCES IS REQUIRED WITH THE PROPOSAL SUBMISSION.
- 2. A "QUALIFIED ENVIRONMENTAL SUPERVISOR" WILL BE PRESENT ON SITE WHILE WORK IS BEING PERFORMED IN SUPERVISOR" SHALL BE AN INDIVIDUAL, REPRESENTING THE OWNER, WHO IS EDUCATED IN OR HAS RECEIVED SPECIALIZED TRAINING IN THE CONSTRUCTION OF RETENTION BASIN GRADING AND LANDSCAPING.
- CONTRACTOR SHALL INSTALL VEGETATION PROTECTION BARRIER PRIOR TO COMMENCING CLEARING AND GRADING ACTIVITIES AND SHALL NOT ENTER THE PROTECTED SITE DURING CONSTRUCTION.
- INSTALL TEMPORARY EROSION AND SEDIMENT CONTROL BMP'S AS SHOWN ON DRAWING NO. D-2.
- CONTRACTOR SHALL STAKE OFF THE BOTTOM OF THE RETENTION BASINS AND FIELD MARK. EXCAVATE RETENTION BASINS TO PROPOSED DEPTH.
- INSTALL PERMEABLE LINER IF REQUIRED.
- BACKFILL THE RETENTION BASINS WITH AMENDED SOILS AS SHOWN ON PLANS AND SPECIFICATIONS. OVERFILLING IS RECOMMENDED TO ACCOUNT FOR SETTLEMENT.
- 9. PRESOAK THE PLANTING SOILS PRIOR TO PLANTING VEGETATION TO AID IN SETTLEMENT.
- 10. PLANT THE BOTTOM AND INTERIOR EMBANKMENTS OF THE RETENTION BASINS WITH ERNST CONSERVATION SEED MIX ERNMX-127 (RETENTION BASIN FLOOR SEEDING FOR WILDLIFE & PLANT DIVERSITY MIX) @ 20
- LBS/ACRE. 11. PLANT THE EXTERIOR EMBANKMENTS AND ADDITIONAL DISTURBED AREAS WITH ERNST CONSERVATION SEED MIX ERNMX-174 (VIRGINIA GENTLEMEN MIX) @ 20 LBS/ACRE.
- 12. MULCH DISTURBED AREAS WITH STRAW @ 2 TONS/ACRE.

