

**SECTION 22 13 00
FACILITY SANITARY SEWERAGE**

PART 1 - GENERAL

1.1 DESCRIPTION

Sanitary sewerage systems, including piping, equipment and all necessary accessories as designated in this section.

1.2 RELATED WORK

- A. Penetrations in rated enclosures: Section 07 84 00, FIRESTOPPING.
- B. Preparation and finish painting and identification of piping systems: Section 09 91 00, PAINTING.
- C. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.
- D. Pipe Insulation: Section 23 07 11, HVAC, PLUMBING, AND BOILER PLANT INSULATION.

1.3 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
 - 1. Piping.
 - 2. Floor Drains.
 - 3. Grease Removal Unit.
 - 4. Cleanouts.
 - 5. All items listed in Part 2 - Products.
- C. Detailed shop drawing of clamping device and extensions when required in connection with the waterproofing membrane or the floor drain.

1.4 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American National Standards Institute (ANSI):
 - American Society of Mechanical Engineers (ASME): (Copyrighted Society)
 - A112.1.1M-91.....Floor Drains ANSI/ASME
 - A13.1-96.....Scheme for Identification of Piping Systems
 - B16.3-98.....Malleable Iron Threaded Fittings ANSI/ASME
 - B16.4-98.....Cast Iron Threaded Fittings Classes 125 and 250
ANSI/ASME
 - B16.12-98.....Cast Iron Threaded Drainage Fittings ANSI/ASME
 - B16.15-85(R 1994).....Cast Bronze Threaded Fittings ANSI/ASME
Element ANSI/ASME

C. American Society for Testing and Materials (ASTM):

A47-99.....Ferritic Malleable Iron Castings Revision 1989
 A53-02.....Pipe, Steel, Black And Hot-Dipped, Zinc-coated
 Welded and Seamless
 A74-03.....Cast Iron Soil Pipe and Fittings
 A183-83(R1998).....Carbon Steel Track Bolts and Nuts
 A536-84(R1999) E1.....Ductile Iron Castings
 B32-03.....Solder Metal
 B75-99(Rev A).....Seamless Copper Tube
 B306-02.....Copper Drainage Tube (DWV)
 B584-00.....Copper Alloy Sand Castings for General
 Applications Revision A
 C564-03.....Rubber Gaskets for Cast Iron Soil Pipe and
 Fittings
 D2000-01.....Rubber Products in Automotive Applications
 D2564-94.....Solvent Cements for Poly (Vinyl Chloride) (PVC)
 Plastic Pipe and Fittings
 D2665-94 Revision A.....Poly (Vinyl Chloride) (PVC) Plastic Drain,
 Waste, and Vent Pipe and Fittings

D. National Association of Plumbing - Heating - Cooling Contractors
(PHCC):

National Standard Plumbing Code - 1996

E. Cast Iron Soil Pipe Institute (CISPI):

301-04.....Hubless Cast Iron Soil and Fittings

F. International Association of Plumbing and Mechanical Officials (IAPMO):
Uniform Plumbing Code - 2000

IS6-93.....Installation Standard

G. American Society of Sanitary Engineers (ASSE):

1018-01.....Performance for trap seal primer valve-water
 supply fed

H. Factory Mutual (FM):

a. Coupling Used in Hubless Cast Iron Systems for Drains, Waste and
 Vent Systems.

I. Plumbing and Drainage Institute (PDI):

PDI WH-201.....Water Hammer Arrestor

PART 2 - PRODUCTS

2.1 SANITARY PIPING

- A. Steel Pipe and Fittings: May be used for vent piping above grade.
 - 1. Pipe Galvanized: ASTM A53, standard weight.
 - 2. Fittings:
 - a. Soil, Waste and Drain Piping: Cast iron, ANSI B16.12, threaded, galvanized.
 - b. Sanitary and Exhaust Vent Piping: Malleable iron, ANSI B16.3, or cast iron, ANSI B16.4. All piping shall be of the same kind. Couplings of vent piping may be standard couplings furnished with pipe.
 - c. Unions: Tucker connection or equivalent type throughout.
 - d. Mechanical Grooved Couplings: Shall consist of ductile iron (ASTM A536, Grade 65-45-12), or malleable iron (ASTM A47, Grade 32510) housings, a pressure responsive elastomeric gasket (ASTM D2000), and steel track head bolts. Shall be for use on pipe and fittings grooved to the manufacturer's specifications. Couplings and fittings to be of the same manufacturer.
- B. Copper Tube, (DWV): May be used for piping above ground, except for urinal drains.
 - 1. Tube: ASTM B306.
 - 2. Fittings:
 - a. Solder type.
 - b. Grooved fittings, 50 to 150 mm (2 to 6 inch) wrought copper conforming to ASTM B75 C12200, 125 to 150 mm (5 to 6 inch) bronze casting conforming to ASTM B584, CDA 844(81-3-7-9). Mechanical grooved couplings, ductile iron, ASTM A536 (Grade 65-45-12), or malleable iron, ASTM A47 (Grade 32510) housings, with EPDM gasket, steel track head bolts, ASTM A183, coated with copper colored alkyd enamel.
 - 3. Joints: ASTM B32, 50/50, special alloy, lead free. Solder using non-corrosive flux.
- C. Polyvinyl Chloride (PVC): Schedule 40. Shall not be used where waste temperature may exceed 60°C (140°F), such as mechanical equipment rooms, and kitchen, SPD, and sterilizer areas. In nursing homes, restrict PVC to patient toilet areas and use other specified material for trunk sewer. PVC shall not be used in waste risers due to higher noise than other specified material.

1. Pipe: Shall be manufactured from Type I normal impact resins in conformance with ASTM D2665 and ASTM B16.12.
2. Fittings:
 - a. Solvent Welded Socket Type: Use solvent cement, ASTM D2564.
 - b. Threaded Type: Molded threads only. Use tape or lubricant specifically intended for use with PVC plastic pipe.

2.2 EXPOSED WASTE PIPING

- A. Finished Room: Use full iron pipe size chrome plated brass piping for exposed waste piping connecting fixtures, casework, cabinets, equipment and reagent racks when not concealed by apron including those furnished by the Government or specified in other sections.
 1. Pipe: Fed. Spec. WW-P-351, standard weight.
 2. Fittings: ANSI B16.15 cast bronze threaded fittings with chrome finish, (125 and 250).
 3. Nipples: ASTM B 687, Chromium-plated.
 4. Unions: Brass or Bronze with chrome finish. Unions 65 mm (2-1/2 inches) and larger shall be flange type with approved gaskets.
- B. Unfinished Rooms, Mechanical Rooms and Kitchens: Chrome-plated brass piping is not required. Paint piping systems as specified in Section 09 91 00, PAINTING.

2.3 CLEANOUTS

- A. Same size as the pipe, up to 100 mm (4 inches); not less than 100 mm (4 inches) for larger pipe. Cleanouts shall be easily accessible and shall be gastight and watertight. Provide a minimum clearance of 600 mm (24 inches) for the rodding.
- B. In Floors: Floor cleanouts shall have cast iron body and frame with square adjustable scoriated secured nickel bronze top. Unit shall be vertically adjustable for a minimum of 50 mm (2 inches). When a waterproof membrane is used in the floor system, provide clamping collars on the cleanouts. Cleanouts shall consist of "Y" fittings and 3 mm (1/8 inch) bends with brass or bronze screw plugs. Cleanouts in the resilient tile floors, quarry tile and ceramic tile floors shall be provided with square top covers recessed for tile insertion. In the carpeted areas, provide carpet cleanout markers. Provide two way cleanouts where indicated on drawings.
- C. Provide cleanouts at or near the base of the vertical stacks with the cleanout plug located approximately 600 mm (24 inches) above the floor. If there are no fixtures installed on the lowest floor, the cleanout

shall be installed at the base of the stack. Extend the cleanouts to the wall access cover. Cleanout shall consist of sanitary tees. Furnish nickel-bronze square frame and stainless steel cover with minimum opening of 150 by 150 mm (6 by 6 inches) at each wall cleanout. Where the piping is concealed, a fixture trap or a fixture with integral trap, readily removable without disturbing concealed roughing work, shall be accepted as a cleanout equivalent providing the opening to be used as a cleanout opening is the size required by the NPHCC National Standard Plumbing Code.

- D. In horizontal runs above grade, cleanouts shall consist of cast brass tapered screw plug in fitting or caulked/no hub cast iron ferrule. Plain end (no-hub) piping in interstitial space or above ceiling may use plain end (no-hub) blind plug and clamp.

2.4 FLOOR DRAINS

- A. ANSI A112.21.1. Provide a caulking flange for connection to cast iron pipe, screwed or no hub outlets for connection to steel pipe, and side outlet when shown. Provide membrane clamp and extensions if required, where installed in connection with waterproof membrane. Puncturing membrane other than for drain opening will not be permitted. Double drainage pattern floor drains shall have integral seepage pan for embedding into floor construction, and weep holes to provide adequate drainage from pan to drain pipe. For drains not installed in connection with a waterproof membrane, provide a 2.2 kg (16-ounce) soft copper membrane, 600 mm (24 inches) square.
- B. Type C: Cast iron body, double drainage pattern, clamping device, light duty square or round nickel bronze adjustable strainer and grate with vandal proof screws. One hundred fifty millimeter (6 inch) minimum square grate.

2.5 TRAPS

Provide on all sanitary branch waste connections from fixtures or equipment not provided with traps. Exposed brass shall be polished brass chromium plated with nipple and set screw escutcheons. Concealed traps may be rough cast brass or same material as pipe connected to. Slip joints not permitted on sewer side of trap. Traps shall correspond to fittings on cast iron soil pipe or steel pipe respectively, and size shall be as required by connected service or fixture.

2.6 TRAP PRIMERS

- A. Trap Primer (TP-1): Electronic type.

1. Controller: Programmable, solid state, 6 zone, minimum adjustable run time of 1 minute for each zone, 12 hour program battery backup, 120VAC to 24VAC internal transformer, fuse protected circuitry, UL listed, 120VAC input-24VAC output, constructed of enameled steel or plastic, equal to Toro Model Vision.
2. Solenoid Valve: Brass body, Buna "N" seats, normally closed, 125 psi rated, 24VAC, equal to ASCO model 8210.
3. Control Wiring: Control wiring to be copper in accordance with NEC 1990, Article 725 and not less than 18 gauge. All wiring shall be in conduit and in accordance with Division 26 of the specifications.

B. Trap Primer (TP-2): Hydraulic.

1. Fifteen millimeter (1/2 inch) Inlet/ fifteen millimeter (1/2 inch) Outlet fully automatic, all brass trap primer valve, activated by a drop in building water pressure, no adjustment required. Model for one (1) to four (4) traps with distribution unit, may be located anywhere in an active cold water line, as indicated on the drawings or as required by code. ASSE Standard 1018. Omit distribution unit when serving a single trap.

2.7 DIELECTRIC FITTINGS

Provide dielectric couplings or unions between ferrous and non-ferrous pipe.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Comply with the PHCC National Standard Plumbing Code and the following:
1. Install branch piping for waste from the respective piping systems and connect to all fixtures, valves, cocks, outlets, casework, cabinets and equipment, including those furnished by the Government or specified in other sections.
 2. Pipe shall be round and straight. Cutting shall be done with proper tools. Pipe, except for plastic and glass, shall be reamed to full size after cutting.
 3. All pipe runs shall be laid out to avoid interference with other work.
 4. Install valves with stem in horizontal position whenever possible. All valves shall be easily accessible. Install valve in each water connection to fixture.

5. All gravity waste drain lines inside the building with vertical drops over 6 m (20 feet) shall be provided with joint restraint on the vertical drop and horizontal offset or branch below the vertical drop. Joint restraint shall be accomplished by threaded, soldered, lead and oakum or grooved joints or a combination of pipe clamps and tie-rods as detailed in NFPA 24. Vertical joint restraint shall be provided from the fitting at the bottom of the vertical drop through every joint up to the riser clamp at the floor penetration of the floor above. Horizontal joint restraint shall be provided from the same fitting at the bottom of the vertical drop through every joint on the horizontal offset or branch for a minimum of 18 m (60 feet) or to anchoring point from the building structure. Joint restraint below ground shall be accomplished by thrust blocks detailed in NFPA 24.
6. Pipe Hangers, Supports and Accessories:
 - a. All piping shall be supported per of the National Standard Plumbing Code, Chapter No. 8.
 - b. Shop Painting and Plating: Hangers, supports, rods, inserts and accessories used for Pipe supports shall be shop coated with red lead or zinc Chromate primer paint. Electroplated copper hanger rods, hangers and accessories may be used with copper tubing.
 - c. Floor, Wall and Ceiling Plates, Supports, Hangers:
 - 1) Solid or split unplated cast iron.
 - 2) All plates shall be provided with set screws.
 - 3) Pipe Hangers: Height adjustable clevis type.
 - 4) Adjustable Floor Rests and Base Flanges: Steel.
 - 5) Concrete Inserts: "Universal" or continuous slotted type.
 - 6) Hanger Rods: Mild, low carbon steel, fully threaded or Threaded at each end with two removable nuts at each end for positioning rod and hanger and locking each in place.
 - 7) Riser Clamps: Malleable iron or steel.
 - 8) Rollers: Cast iron.
 - 9) Self-drilling type expansion shields shall be "Phillips" type, with case hardened steel expander plugs.
 - 10) Hangers and supports utilized with insulated pipe and tubing shall have 180 degree (min.) metal protection shield Centered on and welded to the hanger and support. The shield shall be 4

inches in length and be 16 gauge steel. The shield shall be sized for the insulation.

- 11) Miscellaneous Materials: As specified, required, directed or as noted on the drawings for proper installation of hangers, supports and accessories. If the vertical distance exceeds 6 m (20 feet) for cast iron pipe additional support shall be provided in the center of that span. Provide all necessary auxiliary steel to provide that support.
7. Install cast escutcheon with set screw at each wall, floor and ceiling penetration in exposed finished locations and within cabinets and millwork.
8. Penetrations:
 - a. Fire Stopping: Where pipes pass through fire partitions, fire walls, smoke partitions, or floors, install a fire stop that provides an effective barrier against the spread of fire, smoke and gases as specified in Section 07 84 00, FIRESTOPPING. Completely fill and seal clearances between raceways and openings with the fire stopping materials.
 - b. Waterproofing: At floor penetrations, completely seal clearances around the pipe and make watertight with sealant as specified in Section 07 92 00, JOINT SEALANTS.
- B. Piping shall conform to the following:
 1. Waste and Vent Drain to main stacks:

Pipe Size	Minimum Pitch
80 mm (3 inches) and smaller	1 : 50 (1/4" to the foot).
80 mm (4 inches) and larger	1 : 100 (1/8" to the foot).

2. Exhaust Vent: Extend separately through roof. Sanitary vents shall not connect to exhaust vents.

3.2 TESTS

- A. General: Test system either in its entirety or in sections.
- B. Waste Systems: Conduct before trenches are backfilled or fixtures are connected. Conduct water test or air test, as directed.
 1. Water Test: If entire system is tested, tightly close all openings in pipes except highest opening, and fill system with water to point

- of overflow. If system is tested in sections, tightly plug each opening except highest opening of section under test, fill each section with water and test with at least a 3 m (10 foot) head of water. In testing successive sections, test at least upper 3 m (10 feet) of next preceding section so that each joint or pipe except upper most 3 m (10 feet) of system has been submitted to a test of at least a 3 m (10 foot) head of water. Keep water in system, or in portion under test, for at least 15 minutes before inspection starts. System shall then be tight at all joints.
2. Air Test: Maintain air pressure of 35 kPa (5 psi) gage for at least 15 minutes without leakage. Use force pump and mercury column gage.
 3. Final Tests: Either one of the following tests may be used.
 - a. Smoke Test: After fixtures are permanently connected and traps are filled with water, fill entire drainage and vent systems with smoke under pressure of 1.3 kPa (one inch of water) with a smoke machine. Chemical smoke is prohibited.
 - b. Peppermint Test: Introduce (two ounces) of peppermint into each line or stack.

- - - E N D - - -