

SECTION 23 25 00
HVAC WATER TREATMENT

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section specifies cleaning and treatment of circulating HVAC water systems, including the following.
1. Cleaning compounds.
 2. Chemical treatment for closed loop heat transfer systems.
 3. Chemical treatment for open loop systems.
 4. Glycol-water heat transfer systems.

1.2 RELATED WORK

- A. Test requirements and instructions on use of equipment/system: Section 01 00 00, GENERAL REQUIREMENTS.
- B. General mechanical requirements and items, which are common to more than one section of Division 23: Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- C. Piping and valves: Section 23 21 13, HYDRONIC PIPING and Section 23 22 13, STEAM AND CONDENSATE HEATING PIPING.

1.3 QUALITY ASSURANCE

- A. Refer to paragraph, QUALITY ASSURANCE in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Technical Services: Provide the services of an experienced water treatment chemical engineer or technical representative to direct flushing, cleaning, pre-treatment, training, debugging, and acceptance testing operations; direct and perform chemical limit control during construction period and monitor systems for a period of 12 months after acceptance, including not less than 4 service calls and written status reports. During this period perform monthly tests of the cooling tower for Legionella pneumophila and submit reports stating Legionella bacteria count per millimeter. These tests shall be conducted in a certified laboratory and not by a technician in the field. Minimum service during construction/start-up shall be 4 hours.
- C. Field Quality Control and Certified Laboratory Reports: During the one year guarantee period, the water treatment laboratory shall provide not less than 4 reports based on on-site periodic visits, as stated in paragraph 1.3.B, sample taking and testing, and review with VA personnel, of water treatment control for the previous period. In addition to field tests, the water treatment laboratory shall provide

certified laboratory test reports. These monitoring reports shall assess chemical treatment accuracy, scale formation, fouling and corrosion control, and shall contain instructions for the correction of any out-of-control condition.

- D. Log Forms: Provide one year supply of preprinted water treatment test log forms.

1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data including:
1. Cleaning compounds and recommended procedures for their use.
 2. Chemical treatment for closed systems, including installation and operating instructions.
 3. Chemical treatment for open loop systems, including installation and operating instructions.
 4. Glycol-water system materials, equipment, and installation.
- C. Water analysis verification.
- D. Materials Safety Data Sheet for all proposed chemical compounds, based on U.S. Department of Labor Form No. L5B-005-4.
- E. Maintenance and operating instructions in accordance with Section 01 00 00, GENERAL REQUIREMENTS.

1.5 APPLICABLE PUBLICATIONS

- A. The publication listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. National Fire Protection Association (NFPA):
70-05.....National Electric Code (NEC)

PART 2 - PRODUCTS

2.1 CLEANING COMPOUNDS

- A. Alkaline phosphate or non-phosphate detergent/surfactant/specific to remove organic soil, hydrocarbons, flux, pipe mill varnish, pipe compounds, iron oxide, and like deleterious substances, with or without inhibitor, suitable for system wetted metals without deleterious effects.
- B. All chemicals to be acceptable for discharge to sanitary sewer.
- C. Refer to Section 23 21 13, HYDRONIC PIPING and Section 23 22 13, STEAM AND CONDENSATE HEATING PIPING, PART 3, for flushing and cleaning procedures.

2.2 CHEMICAL TREATMENT FOR OPEN LOOP SYSTEM(S)

- A. General: Provide a factory fabricated and tested packaged, self-contained, chemical feed/blowdown monitoring, controlling and alarming system, containing all except specified or indicated remote components, and requiring only terminal sample stream and chemical piping/tubing connections, remote component electrical connection and power supply. System shall be suitable for a broad spectrum make-up water supply and chemical treatment program. Components, except those specified or indicated otherwise, shall be housed in one or more joined or divided steel enclosures. Provide equipment to treat each cooling tower or evaporative condenser individually.
- B. System Functions:
1. Automatically maintain a predetermined, selectable, total dissolved solids concentration through a continuously monitoring conductivity controller, maintain a predetermined, selectable, scale/corrosion inhibitor and dispersant residual, through a continuously make-up monitoring meter/counter/timer and inhibitor/dispersant ratio controller; achieve a predetermined, selectable, peak concentration of one or two microbiocides as needed on an alternating basis, through a programmable timer controller. De-energize controller or stagger feed chemicals that would degrade or could be incompatible if fed simultaneously.
 2. Automatically maintain a predetermined, selectable, pH level through a continuously monitoring pH controller. For systems with make up water alkalinity in excess of 125 PPM or hardness above 300 PPM, provide acid feed limit timer and audible/visual alarm actuated on low pH.
- C. Main control panel and accessories:
1. Housed in a NEMA Type 4X enclosure:
 - a. Hinged key lock door with viewing window.
 - b. Hard wire connected to power source.
 - c. Provide minimum of three (3) 115V, 1 Ph, 60 Hz receptacles located on enclosure for electrical connection and control of chemical pumps.
 - d. Prewired for ease of installation.

2. Provide an external combination mounted flow switch with transparent sight tube.
 - a. Disable control outputs upon loss of water flow to prevent chemical feeding.
 - b. Provide complete with 3/4 IN connections and combination conductivity and temperature electrode.
3. Keypad or remote control: Access all measurements and setpoints through chemical resistant key pad or remote.
 - a. Security code to prevent unauthorized access.
4. Utilize microprocessor technology.
5. Menu driver programs.
6. Liquid crystal display (LCD).
7. Provide temperature corrected measurements by reading water temperature and adjusting conductivity values according to known temperature curve.
 - a. Range: 0-100 degC (32-212 degF) with an adjustable high alarm.
8. Provide real-time clock.
9. Conductivity monitor:
 - a. Provide linear measurements of full range.
 - b. Provide two scales for selection of high and low in field to assure accurate measurements.
 - c. Provide increments of 1 microohm/cm with adjustable hysteresis.
 - d. Provide bleed-off control in following manner:
 - 1) Standard operation-controller actuates a bleed off solenoid valve when dissolved solids level is exceeded by trip point.
 - 2) Provide an adjustable bleed limit timer to prevent excessive bleed off.
 - 3) An alarm contact shall close when timer has timed out.
10. Biocide operation:
 - a. Provide a programmable 28 day biocide timer for accurate addition of algaecide.
 - b. Provide a secondary bleed off timer to lower conductivity in system prior to biocide feed.
 - c. Lock out cooling water bleed-off during biocide feed period.

11. Chemical feed control: Provide three timers that are capable of operating in one of following field programmable modes.
 - a. Counter-timer-chemical feed proportioned to make-up water rate.
 - 1) Controller shall send low voltage signal to a contacting head water meter.
 - 2) Low voltage signal will ensure long contact life.
 - 3) Water meter shall read in gallons.
12. Alarms:
 - a. Provide alarm LEDs with silence button for high and low conductivity, 10-60 minute bleed-off, chemical feed limit timers, and chemical drum level. Provide remote output relay to indicate alarm condition to Building Control System specified under Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC.
13. Controller operating data history:
 - a. Retain in memory all operating data for following parameters:
 - 1) Standard memory shall allow acquisition and storage of all analog inputs for a one-week period.
 - 2) A three (3) hour minimum, maximum average of all conditions shall be stored for a one-week period.
 - 3) A minute-by-minute account of operating conditions shall be available for latest three-hour period.
14. Electrode: Combination temperature and conductivity type.
 - a. Quick disconnect.
 - b. Supplied in flow switch assembly.
15. Ph monitor:
 - a. Sensor for monitoring purposes only.
 - b. Acid shall not be used to control pH.
- D. Impulse water meter:
 1. General:
 - a. Measure in gallons.
 - b. Sized to meter peak make up rates.
 - c. Equipped with an electrical contacting register.
 - d. Totalize flow at main control panel.
 2. Provide at following locations:
 - a. Cooling tower make up line.
- E. Provide PVC injection nozzles with corporation stop to inject chemical into main circulating water line.
 1. Pressure rating: 700kPa (100 PSI)

2. Size: DN20 (3/4 IN) NPT.
 3. Quantity: Three (3).
- F. Provide chemical feed pumps operated by a 115V, 60 cycle, single PH motor.
1. Provide separate stroke and stroke frequency setting capabilities.
 2. Positive displacement type pump
 - a. Provide with anti-siphon/pressure relief valve installed on pump head which provides anti-siphon protection and aids in priming under pressure.
 - b. Capacity: As determined by Water Treatment Vendor.
 - c. Complete with discharge check valves, foot valves, polyethylene suction and discharge tubing.
 3. Quantity: three (3).
- G. Bleed-off piping assembly:
1. Inlet shut-off valve.
 2. Wye strainer.
 3. Strainer blowdown valve.
 4. Throttling valve.
 5. Brass solenoid valve compatible with main control panel.
 6. Assembly shall be sized by Water Treatment Vendor.
- H. Secondary containment spill pallets for chemical drums:
1. Material: Polyethylene.
 2. Capacity: 250 L (66 GAL) each.
 3. Dimensions each: DN135 (53 IN) length x DN74 (29 IN) wide X DN43 (17 IN) high.
 4. Provide each pallet with grating and drain plug.
 5. Provide one portable loading ramp.
 6. Quantity: Two (2).
- I. Provide liquid level switch assemblies with a PVC bung hole adapter to mount directly into 200 L (55 GAL) chemical drum bung hole.
1. Interface with main control panel.
 2. Quantity: Three (3).
- J. Corrosion monitor rack:
1. Materials: Corrosion resistant.
 2. Construction: ASME specifications.
 3. Number of coupons: four (4).
 4. Coupon holders: quick disconnect type.

- K. Provide test kits for monitoring inhibitor levels, total dissolved solids, chlorides, alkalinity and closed system inhibitors.
- L. Provide one (1) year's supply of chemical treatment including quantity of chemicals necessary to chemically treat system to control scale, corrosion and biological fouling. Provide water treatment products that perform the following:
1. Inhibitor to protect against corrosion and scale formation.
 2. Two liquid biocides for prevention of slime, bacteria and algae.
 3. Chromate based chemical are unacceptable.
 4. Water treatment chemicals to remain stable throughout operating temperature range.
 5. Are compatible with pump seals and other elements in the systems.
- M. Chemicals: P provide sufficient chemicals for start-up and testing and twelve months operation from date of project acceptance.
1. Scale/corrosion inhibitor: Provide a concentrated liquid organic corrosion/scale/ fouling inhibiting formation without phosphates, chromates, zinc and other materials in excess of allowable, local, effluent limits. Feed automatically. Maintain residual as determined by water treatment laboratory.
 2. Dispersant: Provide a concentrated liquid organic/polyelectrolyte formulation. Feed automatically. Maintain residual as determined by water treatment laboratory.
 3. Microbiocides: Provide two different, one oxidizing and one non-oxidizing, concentrated algaecide-biocide formations containing no heavy metals and which are effective at maximum encountered pH. Alternate solutions as needed to effectuate selective kill without build-up of immunity. Period treatment with a chlorine releasing agent is permissible within allowable, local, effluent limits. Feed automatically. Develop peak concentration and maintain for minimum period as determined by water treatment laboratory.
 4. All chemicals to be acceptable for discharge to sanitary sewer.
- N. Water Analysis: Confirm raw water analysis or provide analysis if none is furnished.
- O. Conduct performance test to prove capacity and performance of treatment system.
1. Raw water total hardness, PPM
 2. Concentration cycles
 3. Raw water, pH

4. System water, pH
5. Chemical solution used
6. Acid solution used
7. Quantity of chemical solution injected into system per cycle
8. Quantity of acid injected into system per cycle
9. Make up water required
10. Waste to drain requirement

2.3 GLYCOL-WATER SYSTEM

- A. Propylene glycol shall be inhibited with 1.75 percent dipotassium phosphate. Do not use automotive anti-freeze because the inhibitors used are not needed and can cause sludge precipitate that interferes with heat transfer.
- B. Provide required amount of glycol to obtain the percent by volume for glycol-water systems as follows and to provide one-half tank reserve supply: 40 percent propylene-glycol for run-around coil systems and the chilled water system.
- C. Pot Feeder Make-up Unit: By pass type for chemical treatment, schedule 3.5 mm (10 gauge) heads, 20 mm (3/4-inch) system connections and large neck opening for chemical addition. Feeders shall be five gallon minimum size.

2.4 EQUIPMENT AND MATERIALS IDENTIFICATION

Refer to Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Delivery and Storage: Deliver all chemicals in manufacturer's sealed shipping containers. Store in designated space and protect from deleterious exposure and hazardous spills.
- B. Install equipment furnished by the chemical treatment supplier and charge systems according to the manufacturer's instructions and as directed by the Technical Representative.
 1. Provide a by-pass line around water meters and bleed off piping assembly. Provide ball valves to allow for bypassing, isolation, and servicing of components.
 2. Bleed off water piping with bleed off piping assembly shall be piped from pressure side of circulating water piping to a convenient drain. Bleed off connection to main circulating water piping shall be upstream of chemical injection nozzles.

3. Provide DN 25 (1 IN) Schedule 80 PVC piping for the flow assembly piping to the main control panel and accessories.
 - a. The inlet piping shall connect to the discharge side of the circulating water pump.
 - b. The outlet piping shall connect to the water piping serving the cooling tower downstream of the heat source.
 - c. Provide inlet PVC wye strainer and PVC ball valves to isolate and service main control panel and accessories.
 4. Install PVC injection nozzles with corporation stops in the water piping serving the cooling tower downstream of the heat source.
 5. Provide Schedule 80 PVC piping for corrosion monitor rack per manufacturer's installation instructions. Provide PVC ball valves to isolate and service rack.
 6. Provide Schedule 80 PVC piping for erosion chemical feeder per manufacturer's installation instructions. Provide PVC ball valves to isolate and service feeder.
 7. Provide installation supervision, start-up and operating instruction by manufacturer's technical representative.
- C. Before adding cleaning chemical to the closed system, all air handling coils and fan coil units should be isolated by closing the inlet and outlet valves and opening the bypass valves. This is done to prevent dirt and solids from lodging the coils.
- D. Do not valve in or operate system pumps until after system has been cleaned.
- E. After chemical cleaning is satisfactorily completed, open the inlet and outlet valves to each coil and close the by-pass valves. Also, clean all strainers.
- F. Perform tests and report results in accordance with Section 01 00 00, GENERAL REQUIREMENTS.
- G. After cleaning is complete, and water PH is acceptable to manufacturer of water treatment chemical, add manufacturer-recommended amount of chemicals to systems.
- H. Instruct VA personnel in system maintenance and operation in accordance with Section 01 00 00, GENERAL REQUIREMENTS.

- - - E N D - - -