


1 SECOND FLOOR PLAN
1/8" = 1'-0"



DEMOLITION NOTES



1. DISCONNECT AND REMOVE ALL AFFECTED WIRES, CONDUITS, ETC. AND CAP OFF SERVICES UNTIL NEEDED.
2. DISCONNECT AND REMOVE EXISTING LIGHTING FIXTURES COMPLETELY, INCLUDING ALL ASSOCIATED CONDUIT WIRING AND BOXES BACK TO PANEL. REMOVE, SAVE AND RETURN TO OWNER ALL LIGHTING FIXTURE BALLASTS.
3. DISCONNECT AND REMOVE EXISTING HVAC CONTROL WIRING AND CONDUIT. COORDINATE WITH MECHANICAL DEMOLITION.
4. DISCONNECT AND REMOVE ALL EXISTING SMOKE DETECTORS AND RETURN TO OWNER.
5. REMOVE ANY EXISTING CABLE TRAY, SAVE AND REINSTALL WITH NEW CABLE TRAY.
6. DISCONNECT TO EXTENT REQUIRED, WANDERGUARD SYSTEM AT WARD ENTRY. SYSTEM TO BE RE-INSTALLED AFTER REPLACEMENT OF DOOR AND FRAME. COORDINATE WITH OWNER AND ARCHITECTURAL DEMOLITION.

GENERAL NOTES

1. CONTRACTOR SHALL REVIEW THE HAZARDOUS SUBSTANCE SURVEY REPORT BY DECOMMISSIONING CONSULTING SERVICES, LIMITED, & THE HAZARDOUS SUBSTANCE ABATEMENT REPORT BY DCS AND TAKE ALL REQUIRED PRECAUTIONS DURING DEMOLITION & DISPOSAL OF CONSTRUCTION WASTES.
2. THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL FLOOR PLANS SHOWING NEW CONSTRUCTION, THE FULL DRAWING SET AND THE SPECIFICATIONS TO FORM THE FULL DEMOLITION DOCUMENTATION.
3. SCOPE OF DEMOLITION WORKS INCLUDES ALL DEMOLITION REQUIRED TO ACCOMPLISH THE WORKS INDICATED IN THE CONTRACT DOCUMENTS. STRUCTURAL AND MECHANICAL DEMOLITION WORK, PATCH AND MAKE GOOD ALL AREAS TO REMAIN AFTER DEMOLITION.
4. ALL MECHANICAL AND ELECTRICAL DEMOLITION WORK ARE TO BE REMOVED COMPLETE WITH ALL ASSOCIATED FIXTURES, APPLIANCES, CONDUITS, DUCTS, HANGERS, ETC. AND THE AFFECTED SERVICES CAPPED OFF.
5. NO EXTRAS WILL BE CONSIDERED FOR WORKS REQUIRED TO COMPLETE ALL ASPECTS OF THE CONTRACT WORK AFFECTED BY REMOVAL OF EXISTING WORKS.
6. ANY OPENINGS(S) IN WALLS, FLOORS, ROOFS OR BULKHEAD, NO LONGER REQUIRED AND/OR CAUSED BY DEMOLITION ARE TO BE FILLED AND MADE GOOD WITH SAME CONSTRUCTION AS ADJACENT TO ACCOMPLISH A NEAT CLEAN FINISH FOR THE CONSULTANT'S APPROVAL.
7. ALL DEMOLITION/CONSTRUCTION WASTE ARE TO BE REMOVED FROM SITE AND DISPOSED OF OFF SITE.
8. PRESERVE & PROTECT FROM DAMAGE DURING DEMOLITION AND CONSTRUCTION ALL EXISTING SURFACES TO REMAIN.
9. REMOVE EXISTING ABANDONED SERVICES, PATCH AND MAKE GOOD WALLS TO RECEIVE NEW SCHEDULED FINISHES.
10. PROTECT ALL EXISTING EQUIPMENT (ELECTRICAL & MECHANICAL) & WIRING TO REMAIN DURING DEMOLITION & CONSTRUCTION.



KEY PLAN
N



100% Submission	7/02/10
90% Submission	5/27/10
60% Submission	4/22/10
Revisions	Date

VA WESTERN NEW YORK HEALTHCARE SYSTEM
3495 BAILEY AVENUE
BUFFALO, NEW YORK 14215

URS
BUFFALO, NY,
77 GOODELL ST
716-856-5636

Architect

CARDIOLOGY	DATE
INFECTIOUS CONTROL	DATE


ENGINEERING MANAGER	DATE
CARELINE MANAGER	DATE

ASSOCIATE MEDICAL CENTER DIRECTOR	DATE
-----------------------------------	------

SECOND FLOOR ("WARD B") DEMOLITION PLAN	DATE
---	------

RENOVATION OF BLDG. #1, 2ND FLOOR, B-WARD	Location
Building Number	Checked
	Drawn

Date	July 2, 2010 (UPDATED 10/07/10)
Station No.	528
09-352 ED-002	



Department of Veterans Affairs