



- ### KEYED NOTES - PLAN
- FLOOR DRAIN - (SEE DETAIL A7/AE11 & PLBG DWGS)
 - EXPANSION JOINT & COVER - WALL - LIMITS THE PASSAGE OF SMOKE - SEE FS & EA/E530
 - CAST-IN-PLACE CONCRETE VAULT - (SEE STRUCT DWGS)
 - PROVIDE LEAD LINING ON WALLS INDICATED IN RADIATION PROTECTION SCHEDULE SHT AE702
 - PROVIDE 3/4" FIRE RETARDANT TREATED PLYWOOD ON EACH WALL FROM TOP OF BASE TO 8'-0" AFF.
 - T&G WOOD SIDING - (SEE B1/F1/AE530 & SCHEDULE OF FINISHES 090600)
 - STONE VENEER - (SEE B6&B8/AE530 & SCHEDULE OF FINISHES 090600)
 - BRICK VENEER - (SEE D4/AE531 & SCHEDULE OF FINISHES 090600 SIM)
 - PROVIDE SOLID SURFACE PANELING ALL WALLS (JOINT WELDED - SEE SCHEDULE OF FINISHES 090600)
 - LOCATE & SIZE ROUGH OPENINGS AS NOTED ON ELEVATOR DRAWINGS FOR HOISTWAY & HALL DOOR SCHEDULES (SEE ALSO F1/AE729)
 - GLASS PARTITION (SEE D4&F4/AE730) (SEE SCHED OF FINISHES 090600 FOR GLASS COLOR)
 - SLIDING GLASS SERVICE WINDOW (SEE BORROW LIGHT SCHEDULE SHT AE613)
 - SPECIMEN PASS THRU COMPARTMENT - (SEE D9/AE15)
 - PACKAGE TRANSFER COMPARTMENT - (SEE B6/AE15)
 - TELLER WINDOW & DEAL TRAY - (SEE B8/AE15 & BORROW LIGHT SCHEDULE SHT AE613)
 - ALUMINUM SECURITY GRILLE - (SEE DOOR SCHEDULE SHT AE610)
 - CENTERLINES INDICATE MISC STEEL BEAMS FOR PROCEDURE LIGHT SUPPORT ABOVE CEILING
 - MISC STL (STL TUBE SUPPORT) (SEE DOOR SCHEDULE SHT AE610)
 - MISC STL (STL ANGLE SUPPORT) - AT PARTIAL HEIGHT WALL (SEE PH WALL TYPE ON AE701)
 - MISC STL (STL TUBE SUPPORT) AT SECURITY GRILL (SEE DOOR SCHEDULE)
 - MISC STL (STL ANGLE SUPPORT) AT KNEE WALL BELOW STOREFRONT (SEE PH WALL TYPE ON AE 701) (SEE F1/AE530)
 - RATED CLOSURE BY ELEVATOR CONTRACTOR. (SEE ELEVATOR DWGS)
 - SLIDING SMOKE SEALS: NO GAPS LARGER THAN 1/8" WHEN SLIDE DOOR IS CLOSED
 - EYE WASH STATION (SEE PLBG DWGS)
 - EXPANSION JOINT & COVER - WALL - NON-RATED - SEE FS & EA/E530
 - EXPANSION JOINT & COVER - WOOD FURRING - ALL RATINGS - SEE B7/AE531
 - EXPANSION JOINT & COVER - EXTERIOR WALL - SEE D6 & F2/AE500
 - EXPANSION JOINT & COVER - EXTERIOR WALL - SEE FS & F6/AE500
 - FIRE & SMOKE RATED CURTAIN (SEE D6/E8 & EA/E615)
 - CENTER LINE OF FIRE & SMOKE RATED CURTAIN
 - INTEGRAL SINK IS-3 STAINLESS STEEL (SEE INTEGRAL SINK SCHEDULE SHT AE720 & SCHED OF FINISHES 090600), VV CASEWORK. SEE INTERIOR ELEVATIONS, VV
 - INTEGRAL SINK IS-4 STAINLESS STEEL (SEE INTEGRAL SINK SCHEDULE SHT AE720 & SCHED OF FINISHES 090600), VV
 - FLOOR DRAIN - (SEE DETAIL A7/AE11 & PLBG DWGS)
 - DOWNSPOUT FROM CANOPY ROOF DRAIN

- ### GENERAL NOTES:
- FINISH FLOOR SLAB ELEVATION IS 512'-0" U.N.O.
 - EXTERIOR DIMENSIONS ARE TO THE FACE OF BRICK
 - FOR CLINIC COURTYARD HARDSCAPE SEE LANDSCAPE DWGS

FULLY SPRINKLERED

FIRST FLOOR PLAN - AREA A
1/8" = 1'-0"

CONSULTANTS: STRUCTURAL ENGINEER: KPFF CONSULTING ENGINEERS 1600 DES PERES ROAD, SUITE 100 ST. LOUIS, MO 63141 PHONE: (314) 835-0524 MECHANICAL/ELECTRICAL/PLUMBING: KJWW ENGINEERING CONSULTANTS #15 SUNNEN DRIVE, SUITE 104 ST. LOUIS, MO 63143 PHONE: (314) 645-1132 CODE CONSULTANT/FIRE PROTECTION: CODE CONSULTANTS, INC. 2043 WOODLAND PARKWAY, SUITE 300 LITTLETON, CO 80122 PHONE: (314) 991-2633 CIVIL ENGINEER: KWAME BUILDING GROUP, INC. 257 CHESTERFIELD BUSINESS PARKWAY CHESTERFIELD, MO 63005 PHONE: (314) 530-9100 AUTOMATIC TRANSPORT: LERCH BATES INC. 8389 S. LINCOLN STREET, SUITE 207 SHREVEPORT, LA 71138-0867 PHONE: (720) 283-8182 ESTIMATING: KWAME BUILDING GROUP, INC. 1204 WASHINGTON AVENUE, SUITE 200 ST. LOUIS, MO 63126 PHONE: (314) 862-9344 HAZARDOUS MATERIALS: ALTEC ENVIRONMENTAL CONSULTING, LLC P.O. BOX 17867 SHREVEPORT, LA 71138-0867 PHONE: (318) 687-3771 IRRIGATION CONSULTANT: RIM 9502 BANYON TREE ST. LOUIS, MO 63126 PHONE: (314) 610-4200			CERTIFICATE OF AUTHORITY: 000842 	ARCHITECT: CHRISTNER ARCHITECTS DESIGNERS PLANNERS LANDSCAPE ARCHITECTS 168 N. MERAMEC AVENUE ST. LOUIS, MISSOURI 63105 TEL 314 725 2927 FAX 314 725 2928 CHRISTNERINC.COM THE SEAL (S) AND SIGNATURE(S) APPLY ONLY TO THE DOCUMENT TO WHICH THEY ARE AFFIXED, AND WE EXPRESSLY DISCLAIM ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS RELATING TO OR INTENDED TO BE USED FOR ANY PART OF PARTS OF THE PROJECT. ©COPYRIGHT 2012 CHRISTNER INC.	Drawing Title: PARTIAL FIRST FLOOR PLAN - AREA A Approved: Project Director 	Project Title: CLINIC BUILDING Location: JEFFERSON BARRACKS DIVISION Date: 20 JANUARY 2012 Checked: WAS Drawn: JLG	Project Number: 657-313D Building Number: 55 Drawing Number: AE401A DWG 119 OF 219	Office of Construction and Facilities Management
--	--	--	---	--	--	--	---	--

one eighth inch = one foot
 one quarter inch = one foot
 one half inch = one foot
 three eighths inch = one foot
 three quarters inch = one foot
 one inch = one foot
 one and one half inches = one foot
 three inches = one foot