



DEMOLITION & EROSION CONTROL PLAN

SCALE: 1"=10'-0"

- EROSION CONTROL NOTES**
- ALL WORK ASSOCIATED WITH STABILIZING THE DISTURBED AREAS SHALL BE IN ACCORDANCE WITH THE CITY OF BOISE CONSTRUCTION SITE EROSION CONTROL & SEDIMENT CONTROL PROGRAM AND FIELD MANUAL.
  - CONTRACTOR OR DESIGNATED PERSON SHALL BE RESPONSIBLE FOR PROPER INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL MEASURES, IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS.
  - THE IMPLEMENTATION OF THESE EROSION AND SEDIMENT CONTROL PLANS AND MEASURES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE EROSION AND SEDIMENT CONTROL PLAN FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED BY THE LOCAL JURISDICTION, AND VEGETATION/LANDSCAPING IS ESTABLISHED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE AFTER THE PROJECT IS APPROVED.
  - THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY MARKED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE CLEARING LIMITS SHALL BE PERMITTED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF THE DURATION OF CONSTRUCTION.
  - THE EROSION AND SEDIMENT CONTROL FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO INSURE THAT SEDIMENT AND SEDIMENT LADEN WATER SURFACES OR VOLATILE APPLICABLE WATER STANDARDS.
  - THE EROSION AND SEDIMENT CONTROL FACILITIES SHOWN ON THIS PLAN ARE TO BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD. THESE EROSION AND SEDIMENT CONTROL FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DOES NOT LEAVE THE SITE.
  - ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAINTING. THE CONTRACTOR SHALL NOT FLUSH SEDIMENT-LADEN WATER INTO THE DRAINAGE SYSTEM.
  - STORM DRAIN INLETS, BASINS, AND AREA DRAINS SHALL BE PROTECTED UNTIL PAVEMENT SURFACES ARE COMPLETED AND/OR VEGETATION IS RE-ESTABLISHED.
  - PAVEMENT SURFACES AND VEGETATION ARE TO BE PLACED AS RAPIDLY AS POSSIBLE.

- STORM WATER NOTES:**
- ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE CITY OF BOISE STANDARDS AND THE CITY OF BOISE CONSTRUCTION SITE EROSION AND SEDIMENT CONTROL PROGRAM AND FIELD MANUAL.
  - SHOULD THE TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES AS SHOWN ON THIS PLAN BE DAMAGED OR DESTROYED BY ANY MEANS, THE CONTRACTOR SHALL REPAIR OR REPLACE THE SAME TO PROTECT ADJACENT PROPERTIES, SENSITIVE AREAS, NATURAL WATER COURSES, AND/OR STORM DRAINAGE SYSTEMS.
  - THE CONTRACTOR SHALL CALL DOWNE (1-208-342-1585) AND HAVE THE LOCATION OF EXISTING UTILITIES MARKED A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATIONS.
  - ALL EROSION CONTROL AND STORM WATER FACILITIES SHALL BE REGULARLY INSPECTED AND MAINTAINED BY THE CONTRACTOR DURING CONSTRUCTION.
  - IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN STREET USE AND OTHER RELATED OR REQUIRED PERMITS PRIOR TO ANY CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS PRIOR TO ANY CONSTRUCTION. THE CONTRACTOR SHALL ABIDE BY ALL REQUIREMENTS FOR TRAFFIC CONTROL AND SAFETY WHEN WORKING IN THE ROAD RIGHT-OF-WAY.
  - PROTECT THE NEAREST TWO EXISTING DOWNSTREAM INLETS FROM SEDIMENTATION AND OTHER CONSTRUCTION MATERIALS. ALL CATCH BASIN INSERTS, CLEAN AND MAINTAIN PER MANUFACTURER'S STANDARDS.

**GPR SYMBOLS**

- PAINT OUT INDICATING POSSIBLE PIPING LOCATED BY GROUND PENETRATING RADAR
- PAINT LINE INDICATING POSSIBLE PIPING LOCATED BY GROUND PENETRATING RADAR
- PAINTED AREA INDICATING POSSIBLE TRENCHING LOCATED BY GROUND PENETRATING RADAR

- GENERAL NOTES**
- STORM WATER MANAGEMENT FOR THE PROPOSED SITE SHALL REMAIN, PRE-TREAT AND DISPOSE OF STORM WATER RUNOFF ENTIRELY ON-SITE.
  - EXCESS MATERIAL SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS.
  - ALL EROSION CONTROL AND STORM WATER FACILITIES SHALL BE REGULARLY INSPECTED AND MAINTAINED BY THE CONTRACTOR DURING CONSTRUCTION.
  - CONTRACTOR IS RESPONSIBLE FOR FILING NOTICE OF INTENT (NOI) WITH THE EPA. THIS PLAN IS NOT TO BE CONSIDERED A SWPPP (STORM WATER POLLUTION PREVENTION PLAN). IF A SWPPP IS REQUIRED IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
  - SECURITY FENCE IS NOT REQUIRED AROUND THE CONSTRUCTION SITE, CONTRACTOR TO SUPPLY WARNING FENCE IN AREAS WHERE CONSTRUCTION IS OCCURRING.
  - TOPOGRAPHIC SURVEY PROVIDED BY FOX LAND SURVEYING, INC. SURVEY IS A COMPILED OF UTILITY LOCATES, RECORD DRAWINGS, STAFF KNOWLEDGE, AND FIELD SURVEY DATA. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE ACCURACY OF THE CONVEYANCE OF THE CONTRACTOR. CONTRACTOR SHALL VERIFY EXISTING CONDITIONS.
  - COORDINATE WITH UTILITY COMPANIES AND COTR FOR SCHEDULING OF DISCONNECTION AND FOR CAPPING PROCEDURES.
  - REMOVE ALL LOOSE SOIL FROM AREAS OF EXCAVATION AND FILL WITH APPROVED BACKFILL. COMPACT IN LIFTS AS REQUIRED IN THE SPECIFICATIONS.
  - DURING ALL PHASES OF DEMOLITION AND CONSTRUCTION, PRECAUTION SHALL BE TAKEN TO INCURRING THE ADJOINING FACILITIES AS LITTLE AS REASONABLY POSSIBLE AND TO MAINTAIN ACCESS.
  - IRRIGATION, SPRINKLERS, AND APPLIANCE SHALL BE DEMOLISHED WHEN ENCOUNTERED.

**SHEET NOTES**

- SAW CUT AT NEAREST JOINT.
- (E) SIGN POST TO BE REMOVED.
- PROTECT (E) STRUCTURE.
- DEMOLISH AND REMOVE ALL (E) IRRIGATION COMPONENTS ENCOUNTERED.
- (E) FLAG POLE TO REMAIN AND BE PROTECTED.
- REMOVE (E) CONCRETE SIDEWALK.
- SEE SHEET A01 FOR INFORMATION ON (E) STAIRS, RAILING, DECKING, ETC.
- (E) WOOD DECK TO REMAIN AND BE PROTECTED.
- ALL (E) ROOF SUPPORT COLUMNS TO REMAIN AND BE PROTECTED.
- (E) PLANTER WALL TO REMAIN AND BE PROTECTED.
- MAIL BOX TO BE REMOVED.
- (E) SIGN POST TO BE REMOVED.
- (E) ELECTRICAL BOX MOUNTED ON COLUMN TO REMAIN AND BE PROTECTED.
- (E) STEAM LINES, INSULATED WITH ASBESTOS.
- ABANDONED SANITARY SEWER LINE.

**SHEET LEGEND**

- AREA OF ACTIVE CONSTRUCTION
- SEDIMENT STOP
- ASPHALT PAVEMENT TO BE REMOVED.
- CONCRETE PAVEMENT TO BE REMOVED.
- SURVEY CONTROL POINT

CSHQA

C.W. MOORE PLAZA  
250 S. 5TH ST. BOISE, ID. 83702  
(208) 343-4635 FAX (208) 343-1858  
http://www.cshqa.com

REVISIONS

DATE

C.W. MOORE PLAZA  
250 S. 5TH ST.  
PHONE: 208-343-4635 FAX: 208-343-1858

THESE DRAWINGS AND SPECIFICATIONS, AND ANY MATERIALS OR SERVICES ARE AND SHALL REMAIN THE PROPERTY OF CSHQA. NO PART OF THESE DRAWINGS OR SPECIFICATIONS SHALL BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN CONSENT OF CSHQA.

STAMP  
JOHN R. GREGAUD, P.E.  
REGISTERED PROFESSIONAL ENGINEER  
BOISE, ID. 11882  
JUN 10 2011

8/1/2011

OLD FILE NAME:  
531-10-114-C1.0  
XREF FILE NAME:  
531-10-114-XTBLK  
531-10-114-XFIRST FLR  
531-10-114-XGRID  
531-10-114-XSITEBASE  
531-10-114-XSITESURV

DEMOLITION & EROSION  
CONTROL PLAN

APPROVED: CHIEF OF FACILITY MANAGEMENT SERVICE  
APPROVED: MEDICAL CENTER DIRECTOR

PROJECT TITLE  
VAMC  
PHASE II: BUILDING 33  
RENOVATION

PROJECT NO.  
531-10-114

DRAWING NO.  
C1.0

DWG 04 of 101

DATE  
08/05/11

DEPARTMENT OF VETERANS AFFAIRS

\\servername\work  
Aug 01, 2011 - 10:59am  
D:\2009\08004\6\cshqa\02.drawing\531-10-114-C1.0.dwg