


LEGEND

ROOM NUMBER	
CLB-01	CEILING HEIGHT
CEILING TYPE	
TYPE CEILING FINISH	
C1	2x2 CLEAN ROOM ACOUSTIC TILE
C2	2x2 ACOUSTIC TILE
EX	EXISTING TO REMAIN
ME	MATCH EXISTING

SYMBOL	DESCRIPTION
	1' x 4' FLUORESCENT LIGHT FIXTURE
	2' x 4' FLUORESCENT LIGHT FIXTURE
	RECESSED DOWNLIGHT FIXTURE
	WALL SCONCE
	EXIT SIGN
	CEILING SUPPLY REGISTER
	CEILING RETURN REGISTER
	CEILING MOUNTED POWER/DATA PANEL
	LINEAR DIFFUSER
	SPRINKLER HEAD

GENERAL NOTES

- CONTRACTOR SHALL BE RESPONSIBLE FOR RE-INSTALLATION AND/OR REPLACEMENT OF CEILING COMPONENTS AND CEILING SYSTEMS COORDINATION SEQUENCING AND/OR EXECUTION ON ADJOINING FLOORS.
 - REFER TO MECHANICAL, ELECTRICAL & PLUMBING DWGS FOR ALL SPECIFIED ITEMS IE: LIGHTING FIXTURES, SPRINKLER HEADS, ETC.
 - REPAIR/ EXISTING GRID AND CEILING TILES AS NECESSARY AND PROVIDE ANY NEW COMPONENTS AS NEEDED TO MATCH EXISTING.
 - CONTINUE EXISTING GRID AND CEILING TILES FROM AREAS TO BE REMOVED OR PROVIDE NEW TO MATCH EXISTING. ALIGN NEW GRID WITH EXISTING.
 - PROVIDE ADDITIONAL CEILING T-BARS SPRINKERS AT ALL LIGHT FIXTURES, RECESSED DOWNLIGHTS, LINEAR DIFFUSERS, SCORED ACOUSTIC TILE AND ALL OTHER AREAS WHERE REQUIRED.
 - REMOVE EXISTING CEILING AS REQUIRED TO INSTALL NEW WORK. PATCH CEILING TO MATCH EXISTING. PROVIDE NEW PATCH TO MATCH EXISTING LIGHT FIXTURES TO REMAIN.
 - SEE DRAWING A210 FOR CEILING DETAILS.
 - SINGLE CURTAIN TRACKS TO BE PROVIDED AND INSTALLED BY CONTRACTOR. CORDS/CURTAINS BY OWNER.
 - ALL WORK STATIONS TO RECEIVE UNDER COUNTER TASK LIGHTING BY CABINWORK VENDOR.
- KEY NOTES**
- PROVIDE NEW 2x2 SPRINKLED CEILING SYSTEM IN ALL AREAS WHERE EXISTING DIFFUSERS PER MECH PLANS - PROVIDE NEW MECH EQUIPMENT IN CEILING (IE: LIGHTING FIXTURES, SPRINKLER HEADS, ETC.) TO REMAIN. LIGHT FIXTURES TO BE CLEANED AND RE-LAMPED - COORDINATE WITH OWNER.
 - PROVIDE NEW 6x6 B2 CEILING IN GLASS WASH ROOM AFTER INSTALLATION OF NEW PER MECH PLANS - ALL OTHER EXISTING EQUIPMENT IN CEILING (IE: LIGHTING, SPRINKLERS, PA SYSTEM SPEAKERS, ETC.) TO REMAIN. LIGHT FIXTURES TO BE CLEANED AND RE-LAMPED - COORDINATE WITH OWNER.
 - EXISTING POWER COLUMNS FOR CHEMISTRY EQUIPMENT TO REMAIN.



Project Title		Project Number	
LABORATORY RENOVATION		526-09-122	
100% CD SUBMISSION		Building Number 100	
1K Job Number 785400		Drawing Number 2-AS2.02	
Location BRONX, NY		Date 03/09/11	
Checked BL		Drawn WT	
Approved Project Director		Dwg. of	
Office of Facilities Management		Department of Veterans Affairs	

Drawing Title	
SECOND FLOOR PLAN - AREA 2B	
REFLECTED CEILING PLAN	
SCALE: 1/8"=1'-0"	
Approved Project Director	

ARCHITECT/ENGINEERS:	
MADAANY KORPEON ARCHITECTS 100 WEST 17TH STREET, 10TH FLOOR, NEW YORK, NY 10011 Tel: (212) 366-7888 Fax: (212) 366-7889	

CONSULTANTS:	
LNI Associates ENGINEERING-PLANNING-ARCHITECTURE-SIMMONS, LP 445 Godwin Avenue Midland Park, New Jersey 07432 Tel: (201) 447-8460 Fax: (201) 447-1233	

DESIGN APPROVED W/ COMMENT:	