


WATER COOLED CHILLER SCHEDULE

| WATER COOLED CHILLER SCHEDULE | | | | | | | | | | | | | | | |
|-------------------------------|-----------|-----------|------|---------------------|------------------|------------|------------|---------------------|---------------------|-----------|-----------|---------------------|---------------------|---------|---------------------------------------------------|
| UNIT NO. | LOCATION | MIN. TONS | NPLV | MAX. KW PER TON (W) | COMPRESSOR MOTOR | | EVAPORATOR | | | | CONDENSER | | | REMARKS | |
| | | | | | HP (KW) INPUT | PHASE VOLT | GPM | ENT. WATER TEMP. °F | LVG. WATER TEMP. °F | MAX. P.D. | GPM | ENT. WATER TEMP. °F | LVG. WATER TEMP. °F | | MAX. P.D. |
| 1** | BLDG. 147 | 1000 | .39 | .62 | 620 | 3-480 | 2400 | 54.0 | 44.0 | 30.8 | 3000 | 97 | 87 | 41.8 | YORK YK MAXE, MCQUAY WSC OR APPROVED EQUIVALENT * |
| 4** | BLDG. 147 | 600 | .37 | .62 | 390 | 3-480 | 1440 | 54.0 | 44.0 | 31.3 | 1800 | 97 | 87 | 37.2 | YORK YK MAXE, MCQUAY WSC OR APPROVED EQUIVALENT * |

* CHILLER SHALL HAVE VFD
 ** CHILLER EFFECIENCIES SHALL BE BASED UPON 85F ENTERING CONDENSER WATER.



ASSOCIATED DESIGN GROUP, INC.
 A PROFESSIONAL ENGINEERING COMPANY
 Lafayette, Louisiana (337) 234-6710

**V/A HOSPITAL
 CENTRAL PLANT MODIFICATIONS
 ALEXANDRIA, LA**

JOB NO: 11106
 SCALE: NO SCALE
 DATE: 5/18/2012
 SHEET: M4R2