


LEGEND

	SIMPLEX OUTLET
	DUPLEX OUTLET
	DATA PORT BOX
	THERMOSTAT, RELOCATE AS SHOWN IN ES DRAWINGS
	STRIP LIGHTING FIXTURE
	2X2 LIGHTING FIXTURE

- NOTES:**
- DEMOLISH ALL FIXTURES SHOWN DURING CONSTRUCTION IN THIS AREA. REMOVE ALL ABANDONED CONDUIT TO NEAREST CONCEALED JUNCTION BOX. INSTALL KO'S WHERE REQUIRED WIRING COMPLETELY. IT IS PERMISSIBLE TO RE-USE CONDUIT AND WIRING WHERE APPROPRIATE FOR NEW FIXTURES, COORDINATE WITH ES DRAWINGS.
 - WHERE CEILINGS ARE REPLACED, ALL LIGHTING FIXTURES ARE TO BE DEMOLISHED UNLESS THEY CAN BE RELOCATED TO MATCH DRAWING AS-2. MAINTAIN MAXIMUM 6'-0" LENGTH OF FLEXIBLE CONDUIT.
 - ALL CIRCUITS IN WORK MUST BE UNDER LOTO AT THE UPSTREAM PANEL UNTIL COMPLETELY INSTALLED AND TERMINATED IN ACCORDANCE WITH NFPA-70 AND 70E. WHERE LOCK OUT OF CIRCUITS IS NOT POSSIBLE WITH EXISTING BREAKERS, HOME RUN IS TO BE REMOVED FROM PANEL BREAKER AND SAFED OFF UNTIL WORK IS COMPLETED THEN RE-INSTALLED. **NO LIVE ELECTRICAL WORK IS PERMISSIBLE.**



<p>Contract Document Review: 3-16-2012</p> <p>Contract Documents: 2-20-2012</p> <p>INITIAL DRAWING: 5-19-2011</p> <p>Revisions: _____ Date: _____</p>		<p>CONSULTANTS:</p>	<p>ARCHITECT/ENGINEERS:</p>	<p>NORTH:</p>	<p>APPROVED:</p> <p>APPROVED:</p> <p>APPROVED:</p> <p>APPROVED:</p>	<p>Drawing Title</p> <p>ELECTRICAL DEMOLITION</p> <p>GROUND FLOOR</p> <p>1/4" = 1'</p>	<p>Project Title</p> <p>PHYSICAL THERAPY OFFICES</p>	<p>Project Number</p> <p>62044-11-224</p>	<p>Engineering Service</p> <p>Department of Veterans Affairs</p>
					<p>Approved: Director, VAHVHCS:</p>	<p>Location</p> <p>CASTLE POINT, NEW YORK</p>	<p>Building(s) Number</p> <p>15H</p>	<p>Drawing Number</p> <p>15H-ED-1</p>	
					<p>Approved: Chief of Engineering</p>	<p>Date</p> <p>5-19-2011</p>	<p>Checked</p>	<p>Drawn</p> <p>JEF</p>	
								<p>SHEET 13 OF 28</p>	