






three inches = one foot  
one and one half inches = one foot  
one inch = one foot  
three quarters inch = one foot  
one half inch = one foot  
one quarter inch = one foot  
one eighth inch = one foot  
one eighth inch = one foot

LEGEND	
 #	SIMPLEX OUTLET, # REFERS TO RUN SCHEDULE DWG ES-3
 #	DUPLEX OUTLET, # REFERS TO RUN SCHEDULE DWG ES-3
	DATA PORT BOX
	AUTOMATIC DOOR CONNECTION, SEE DRAWING AS-3

- NOTES:
- EXISTING OUTLETS TO REMAIN EXCEPT AS REQUIRED FOR DEMOLITION.
  - PROVIDE GFCI PROTECTED OUTLETS WHERE INDICATED.
  - ALL DATA BOXES ARE TO BE PROVIDED WITH (2) PHONE AND (2) DATA LINES.
  - PHONE LINES ARE TO BE GRAY CAT 6 CABLE.
  - DATA LINES ARE TO BE CAT 6 CABLE, (1) BLUE AND (1) WHITE PER BOX.
  - ALL DATA LINES ARE TO BE RUN TO SWITCH IN ROOM H-005. CONTRACTOR IS TO PROVIDE ALL CABLING, INSTALLATION, LABELING, AND TERMINATION WITH I.R.M. APPROVAL.
  - DATA AND POWER FIXTURES TO BE LOCATED 18" AFF UNLESS OTHERWISE NOTED.
  - PROVIDE CONNECTION FOR OVERHEAD LIFT CHARGING VIA SIMPLEX OUTLET 84" A.F.F.
  - INSTALL (1) SIMPLEX OUTLET 72" AFF AT THIS LOCATION ON CIRCUIT SHOWN FOR WALL MOUNT FANS. COORDINATE WITH DRAWING IF-1.
  - THERMOSTATS ARE RELOCATED FROM EXISTING LOCATIONS.
  - WHERE OUTLETS OR DATA BOXES ARE INDICATED AT A DESK OR CASEWORK LOCATION, THEY ARE TO BE INSTALLED AT 40" A.F.F.
  - ALL DEVICES OTHER THAN THOSE MOUNTED ON COLUMN SURROUNDS ARE TO BE RECESSED.
  - FIXTURES WITHOUT CIRCUIT NUMBERS ARE EXISTING



CONSULTANTS:		ARCHITECT/ENGINEERS:		NORTH:		APPROVED:		Drawing Title		Project Title		Project Number		<div>Engineering Service</div> <div>Department of Veterans Affairs</div>	
						APPROVED:		DATA AND COMMUNICATION PLAN		PHYSICAL THERAPY OFFICES		620A4-11-224			
						APPROVED:		GROUND FLOOR		Location		Building(s) Number			
						APPROVED:		1/4" = 1'		CASTLE POINT, NEW YORK		15H			
						APPROVED:		Approved: Director, VAHVHCS:		Date		Drawing Number			
Contract Documents		2-20-2012				APPROVED:		Approved: Chief of Engineering		12-15-2010		Checked		15H-ES-2	
INITIAL DRAWING		12-15-2010				APPROVED:				Date		Checked		SHEET 22 OF 28	
Revisions:		Date:				APPROVED:				Date		Checked		SHEET 22 OF 28	