

PO9. Saw

SCOPE OF WORK (CONSTRUCTION)

Project Number: 437-12-101

Project Title: Install ETO Abater

Description: Work shall include, but shall not be limited to: all required general construction, alterations, mechanical and electrical work, equipment, utility systems, necessary removal of existing structures, - labor and certain other items as indicated on the drawings and specifications to complete Fargo VA Health Care System project 437-12-101, Install ETO Abater in accordance with the contract documents.

The contractor shall provide and install the ETO Abater per plans and specifications. The contractor shall complete all general construction per plans and specifications to route and install all ETO Abater vent piping from the basement location up through all floors to the roof termination. Contractor will be responsible for all vent pipe enclosures including fireproofing, sealing, ceiling replacement, floor repairs, wall finishes and the re-installation of all existing items such as exit signs, access panels, sprinkler heads, radiant ceiling panels and any other existing items. All plumbing, fire protection, mechanical, electrical and other work associated with and necessary for the installation of the ETO Abater, shall be the responsibility of the contractor.

Duration: 220 days