

VA Project No. 562-16-202
AE Works Project No. 15023
Addendum 01 - Revision 01 dated 5/04/17

Erie VA Medical Center
Renovate 6th Floor East for Domiciliary

04-15

**SECTION 09 06 00
SCHEDULE FOR FINISHES**

SECTION 09 06 00-SCHEDULE FOR FINISHES

VAMC: Erie, PA
Project no. and Name: Renovate 6th Floor for Domiciliary
Submission CD-7
Date: 01/22/2016

SECTION 09 06 00
SCHEDULE FOR FINISHES

PART I - GENERAL

1.1 DESCRIPTION

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

1.2 MANUFACTURERS

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

1.3 SUBMITALS

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

1.4 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.
- B. MASTER PAINTING INSTITUTE: (MPI)
 - 2001.....Architectural Painting Specification Manual

04-15

PART 2- PRODUCTS

2.6 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES

B. SECTION 06 20 00, FINISH CARPENTRY

12. VANITIES (TYPES S4, S4 M)		
Room No. and Name	Component	Finish/Color
	Countertop	
	Trim	

2.8 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door	
Component	Color of Paint Type and Gloss
Frame	PT-4
Window frame	PT-4

B. SECTION 08 14 00, WOOD DOORS

Component	Finish/Color
Doors	Wood - Match existing facility
Frames	PT-4

VA Project No. 562-16-202
 AE Works Project No. 15023
Addendum 01 - Revision 01

Erie VA Medical Center
 Renovate 6th Floor East for Domiciliary

04-15

C. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	Paint to match adjacent GWB
Stainless steel	(Located in Wet Areas)

T. WINDOW STOOLS

Material	Finish
Existing To Remain	Existing To Remain

2.9 DIVISION 09 - FINISHES

2. SECTION 09 30 13, CERAMIC TILING		
Finish Code	Manufacturer	Mfg. Color Name/No
CT-1	Crossville, Inc.	Now - Moss 7A38 <u>Mainstreet - Bistro Brown AV213</u>
CT-2	Crossville, Inc.	Now - Moss (6x12 Cove Base) <u>Mainstreet - Bistro Brown AV213</u>
CT-3	Crossville, Inc.	Now - Moss (6x6 Diagonal Crosshatch) <u>Buenos Aires Mood - Polo VS150</u>
<u>CT-4</u>	<u>Crossville, Inc.</u>	<u>Buenos Aires Mood - Polo VS150</u>
Grout	TBD	Selected from Manufacturer's Standard Grout Colors

04-15

F. SECTION 09 51 00, ACOUSTICAL CEILINGS

Component	Color Pattern	Manufacturer	Mfg Name/No.
Exposed Suspension System	White	Armstrong	Sonata 9/16"
Exposed Suspension System	White	Armstrong	Prelude XL 15/16"
Type VI	White	Armstrong	Ultima Tegular, 2x2
Type AMP	White	Armsrong	Metalworks SecureLock 2x2

I. SECTION 09 65 19, RESILIENT TILE FLOORING

Finish Code	Size	Material/Component	Manufacturer	Mfg Name/No.
LVT-1	6"x36"	LVT	Armstrong	Natural Creations w/ I-Set - NC023 Medium
VCT	12" x 12"	VCT	Mannington	Sandrift 137

04-15

L. SECTION 09 65 13, RESILIENT BASE STAIR TREADS AND ACCESSORIES

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
RB-1	Rubber Base	4"	Johnsonite	Fawn 80

T. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
PT-1	Level 5	Sherwin Williams	SW7036 Accessible Beige
PT-2	Level 5	Sherwin Williams	SW2834 Birdseye Maple
PT-3	Level 5	Sherwin Williams	SW6212 Quietude
PT-4	Level 5	Sherwin Williams	SW7038 Tony Taupe

VA Project No. 562-16-202
AE Works Project No. 15023
Addendum 01 - Revision 01

Erie VA Medical Center
Renovate 6th Floor East for Domiciliary

04-15

P. SECTION 10 26 00, DOOR PROTECTION

Item	Material	Manufacturer	Mfg. Color Name/No.
Frame Protectors	Resilient	Acrovyn	858 Pumice
Door Protection	Resilient	Acrovyn	Provide samples for Owner/Architect selection

B. SECTION 12 32 00, WOOD CASEWORK

Item Type	Location	Finish/Color
Plastic Laminate	Cabinets	Wilsonart Laminate - 7040K-78
Solid Surface	Countertop	Hi-Macs - T002 Cosmos

VA Project No. 562-16-202
AE Works Project No. 15023
Addendum 01 - Revision 01

Erie VA Medical Center
Renovate 6th Floor East for Domiciliary

04-15

PART III EXECUTION

3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

04-15

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS	
Term	Abbreviation
Access Flooring	AF
Accordion Folding Partition	AFP
Acoustical Ceiling	AT
Acoustical Ceiling, Special Faced	AT (SP)
Acoustical Metal Pan Ceiling	AMP
Acoustical Wall Panel	AWP
Acoustical Wall Treatment	AWT
Acoustical Wallcovering	AWF
Anodized Aluminum Colored	AAC
Anodized Aluminum Natural Finish	AA
Baked On Enamel	BE
Brick Face	BR
Brick Flooring	BF
Brick Paving	BP
Carpet	CP
Carpet Athletic Flooring	CAF
Carpet Module Tile	CPT
Ceramic Glazed Facing Brick	CGFB
Ceramic Mosaic Tile	FTCT
Concrete	C
Concrete Masonry Unit	CMU
Divider Strips Marble	DS MB
Epoxy Coating	EC
Epoxy Resin Flooring	ERF
Existing	E

Exposed Divider Strips	EXP
Exterior	EXT
Exterior Finish System	EFS
Exterior Paint	EXT-P
Exterior Stain	EXT-ST
Fabric Wallcovering	WF
Facing Tile	SCT
Feature Strips	FS
Floor Mats & Frames	FM
Floor Tile, Mosaic	FT
Fluorocarbon	FC
Folding Panel Partition	FP
Foot Grille	FG
Glass Masonry Unit	GUMU
Glazed Face CMU	GCMU
Glazed Structural Facing Tile	SFTU
Granite	GT
Gypsum Wallboard	GWB
High Glazed Coating	SC
Latex Mastic Flooring	LM
Linear Metal Ceiling	LMC
Linear Wood Ceiling	LWC
Marble	MB
Material	MAT
Mortar	M
Multi-Color Coating	MC
Natural Finish	NF
Paint	P
Paver Tile	PVT
Perforated Metal Facing (Tile or Panels)	PMF
Plaster	PL
Plaster High Strength	HSPL
Plaster Keene Cement	KC
Plastic Laminate	HPDL

04-15

Polypropylene Fabric Wallcovering	PFW
Porcelain Paver Tile	PPT
Quarry Tile	QT
Radiant Ceiling Panel System	RCP
Resilient Stair Tread	RST
Rubber Base	RB
Rubber Tile Flooring	RT
Spandrel Glass	SLG
Stain	ST
Stone Flooring	SF
Structural Clay	SC
Suspension Decorative Grids	SDG
Terrazzo Portland Cement	PCT

Terrazzo Tile	TT
Terrazzo, Thin Set	
Textured Gypsum Ceiling Panel	TGC
Textured Metal Ceiling Panel	TMC
Thin set Terrazzo	TST
Veneer Plaster	VP
Vinyl Base	VB
Vinyl Coated Fabric Wallcovering	W
Vinyl Composition Tile	VCT
Vinyl Sheet Flooring	VSF
Vinyl Sheet Flooring (Welded Seams)	WSF
Wall Border	WB
Wood	WD

3.2 FINISH SCHEDULE SYMBOLS

Symbol Definition

** Same finish as adjoining walls
 - No color required
 E Existing
 XX To match existing
 EFTR Existing finish to remain
 RM Remove

--- E N D---